LEASE NO. GS-03P-LMD00631

This Lease is made and entered into between

CENTER DRIVE TITLE HOLDER LP

(Lessor), whose principal place of business is 254 W 31st Street, 4th Floor, NEW YORK, NY 10001-3967, and whose interest in the Property described herein is that of Fee Owner, and

The United States of America

(Government), acting by and through the designated representative of the General Services Administration (GSA), upon the terms and conditions set forth herein.

Witnesseth: The parties hereto, for the consideration hereinafter mentioned, covenant and agree as follows:

Lessor hereby leases to the Government the Premises described herein, being all or a portion of the Property located at

NORTH EAST COMMERCE CENTER, 4 CENTER DRIVE, NORTH EAST, MD 21901-2003

and more fully described in Section 1, together with rights to the use of parking and other areas as set forth herein, to be used for such purposes as determined by GSA.

LEASE TERM

To Have and To Hold the said Premises with its appurtenances for the term beginning upon acceptance of the Premises as required by this Lease and continuing for a period of

15 Years, 10 Years Firm,

subject to termination and renewal rights as may be hereinafter set forth. The commencement date of this Lease, along with any applicable termination and renewal rights, shall be more specifically set forth in a Lease Amendment upon substantial completion and acceptance of the Space by the Government.

In Witness Whereof, the parties to this Lease evidence their agreement to all terms and conditions set forth herein by their signatures below, to be effective as of the date of delivery of the fully executed Lease to the Lessor.

uildings Service

The information collection requirements contained in this Solicitation/Contract, that are not required by the regulation, have been approved by the Office of Management and Budget pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

LEASE NO. GS-03P-LMD00631 LESSOR: V GOVERNMENT:

	DN 1 THE PREMISES, RENT, AND OTHER TERMS	
1.01	THE PREMISES (WAREHOUSE) (OCT 2016)	.5
1.02	EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014)	.5
1.03	TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)	.6
1.04	CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)	.6
1.05	BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)	6
1.06	RENT AND OTHER CONSIDERATION (OCT 2017)	6
1.07	BROKER COMMISSION AND COMMISSION CREDIT (OCT 2016)	7
1.08	TERMINATION RIGHTS (OCT 2016)	
1.09	PARAGRAPH INTENTIONALLY DELETED	٠. ٢
1.10	PACHIMENTE INCONDODATED IN THE LEASE MADERIOLIES (OCT 2040)	. 1
1.5	DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (OCT 2018)	. 1
1.11	TENANT IMPROVEMENT ALLOWANCE (AUG 2011)	.7
1.12	TENANT IMPROVEMENT RENTAL ADJUSTMENT (OCT 2016)	.7
1.13	TENANT IMPROVEMENT FEE SCHEDULE (JUN 2012)	.7
1.14	PARAGRAPH INTENTIONALLY DELETED	.8
1.15	PARAGRAPH INTENTIONALLY DELETED	.8
1.16	PERCENTAGE OF OCCUPANCY FOR TAX ADJUSTMENT (OCT 2018)	.8
1.17	PARAGRAPH INTENTIONALLY DELETED	.8
1.18	OPERATING COST BASE (OCT 2016)	.8
1.19	RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)	8
1.20	HOURLY OVERTIME HVAC RATES (OCT 2016)	. 8
1.21	PARAGRAPH INTENTIONALLY DELETED	
1.22	BUILDING IMPROVEMENTS (MAR 2016)	
1.23	PARAGRAPH INTENTIONALLY DELETED	8
1.24	LESSOR'S DUNS NUMBER (OCT 2017)	8
SECTIO	DN 2 GENERAL TERMS, CONDITIONS, AND STANDARDS	
2.01	DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (OCT 2016)	.9
2.02	AUTHORIZED REPRESENTATIVES (OCT 2016)	10
2.03	ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018)	10
2.04	WAIVER OF RESTORATION (OCT 2018)	10
2.05	PAYMENT OF BROKER (JUL 2011)	10
2.06	CHANGE OF OWNERSHIP (OCT 2018)	10
2.07	REAL ESTATE TAX ADJUSTMENT (JUN 2012)	11
2.08	ADJUSTMENT FOR VACANT PREMISES (OCT 2017)	12
2.09	OPERATING COSTS ADJUSTMENT (JUN 2012)	12
2.10	ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)	13
2.11	PARAGRAPH INTENTIONALLY DELETED	13
CECTIC	NA CONSTRUCTION STANDARDS AND SUFFIX COMPONENTS	
	ON 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS	14
3.01	PARAGRAPH INTENTIONALLY DELETED	14
3.02	WORK PERFORMANCE (JUN 2012)	14
3.03	ENVIRONMENTALLY PREFERABLE PRODUCTS REQUIREMENTS) (OCT 2017)	14
3.04	EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (JUN 2012)	14
3.05	CONSTRUCTION WASTE MANAGEMENT (OCT 2017)	14
3.06	WOOD PRODUCTS (OCT 2016)	14
3.07	ADHESIVES AND SEALANTS (OCT 2017)	15
3.08	BUILDING SHELL REQUIREMENTS (WAREHOUSE) (OCT 2016)	15
3.09	RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)	15
3.10	QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)	15
3.11	VESTIBULES (APR 2011)	15
3.12	MEANS OF EGRESS (WAREHOUSE) (MAY 2015)	15
3.13	AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)	16
3.14	FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)	
3.15	ENERGY INDEPENDENCE AND SECURITY ACT (MAR 2016)	10
3.16	DADACOADLINICATIONALI V DELETED	17
3.10	PARAGRAPH INTENTIONALLY DELETED	1/
	PARAGRAPH INTENTIONALLY DELETED	1/
3.18	DEMOLITION (JUN 2012)	1/
3.19	ACCESSIBILITY (FEB 2007)	1/
3.20	EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)	1/
3.21	DOORS: IDENTIFICATION (APR 2011)	18
3.22	WINDOWS (APR 2011) 18	
3.23		40
3.24	PARTITIONS: GENERAL (APR 2015)	18
	PARTITIONS: PERMANENT (APR 2015)	18
3.25	PARTITIONS: PERMANENT (APR 2015)	18
3.26	PARTITIONS: PERMANENT (APR 2015)	18 18 18
3.26	PARTITIONS: PERMANENT (APR 2015)	18 18 18
3.26	PARTITIONS: PERMANENT (APR 2015)	18 18 18



3.30	MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)	
3.31	BUILDING SYSTEMS (APR 2011)	
3.32	ELECTRICAL—SHELL (WAREHOUSE) (MAY 2014)	19
3.33	PARAGRAPH INTENTIONALLY DELETED	19
3.34	DELIMPING CHIN 2012), 40	
3.35	PARAGRAPH INTENTIONALLY DELETED	19
3.36	RESTROOMS (WAREHOUSE) (OCT 2016)	19
3.37	PLUMBING FIXTURES: WATER CONSERVATION (OCT 2016)	
3.38	PARAGRAPH INTENTIONALLY DELETED	
3.39	HEATING AND VENTILATION—SHELL (WAREHOUSE) (OCT 2016)	20
3.40	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)	
3.41	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)	
3.42	LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (OCT 2016)	
3.43	ACOUSTICAL REQUIREMENTS (JUN 2012)	
3.44	PARAGRAPH INTENTIONALLY DELETED.	
3.45	PARAGRAPH INTENTIONALLY DELETED	
3.46	PARAGRAPH INTENTIONALLY DELETED.	
3.47	PARAGRAPH INTENTIONALLY DELETED.	
3.48	PARAGRAPH INTENTIONALLY DELETED	
3.49	SYSTEMS COMMISSIONING (APR 2011)	
3.50	LOADING DOCKS—SHELL (WAREHOUSE) (MAY 2014)	
3.51	EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)	
3.52		
3.53	MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)	
3.54	PARAGRAPH INTENTIONALLY DELETED	
3.54	PARAGRAPH INTENTIONALLY DELETED	23
SECTI	ON 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES	24
4.01	SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (OCT 2017)	
4.02	CONSTRUCTION DOCUMENTS (SEP 2012)	
4.03	TENANT IMPROVEMENTS PRICE PROPOSAL (SEP 2013)	24
4.04	BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) PRICE PROPOSAL (SEP 2012) INTENTIONALLY DELETED	24
4.05	TENANT IMPROVEMENTS PRICING REQUIREMENTS (SEP 2013)	24
4.06	GREEN LEASE SUBMITTALS (WAREHOUSE) (OCT 2018)	
4.07	CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (APR 2011)	
4.08	PROGRESS REPORTS (JUN 2012)	26
4.09	ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)	26
4.10	CONSTRUCTION INSPECTIONS (APR 2011)	
4.11	ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (MAY 2015)	26
4.12	LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (JUN 2012)	26
4.13	AS-BUILT DRAWINGS (OCT 2017)	
4.14	PARAGRAPH INTENTIONALLY DELETED.	
4.15	PARAGRAPH INTENTIONALLY DELETED	
4.16	LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)	
4.10	220001011002011WWW.02M211112200	
PECT	ION 5 TENANT IMPROVEMENT COMPONENTS	20
100		
5.01	TENANT IMPROVEMENT REQUIREMENTS (OCT 2016)	
5.02	PARAGRAPH INTENTIONALLY DELETED	
5.03	WINDOW COVERINGS (WAREHOUSE) (JUN 2012)	28
5.04	DOORS: SUITE ENTRY (SEP 2013)	
5.05	DOORS: INTERIOR (SEP 2013)	28
5.06	DOORS: HARDWARE (SEP 2013)	
5.07	DOORS: IDENTIFICATION (JUN 2012)	
5.08	PARTITIONS: SUBDIVIDING (SEP 2015)	28
5.09	CEILINGS—TI (WAREHOUSE) (OCT 2017)	
5.10	WALL FINISHES (JUN 2012)	
5.11	PAINTING—TI (OCT 2017)	
5.12	FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (OCT 2017)	
5.13	HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)	30
5.14	ELECTRICAL: DISTRIBUTION-TI (WAREHOUSE) (MAY 2014)	30
5.15	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)	
5.16	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)	
5.17	DATA DISTRIBUTION (JUN 2012)	30
5.18	ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (JUN 2012)	30
5.19	LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)	
5.20	LOADING DOCKS—TI (WAREHOUSE) (MAY 2014)	
5.21	AUTOMATIC FIRE SPRINKLER SYSTEM - TI (OCT 2016)	31
SECT	ION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM	92
05011	DROUGHAINES, SERVICES, AND DELIGATIONS DURING THE LEAGE LEVEL	

0.02	UTILITIES (APR 2011) 32	
6.02	PARAGRAPH INTENTIONALLY DELETED	32
6.03	UTILITY CONSUMPTION REPORTING (OCT 2016)	32
6.04	HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2018)	32
6.05	OVERTIME HVAC USAGE (OCT 2018)	32
6.06	JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)	33
6.07	PARAGRAPH INTENTIONALLY DELETED	33
6.08	PARAGRAPH INTENTIONALLY DELETED	33
6.09	SNOW REMOVAL (WAREHOUSE) (MAY 2014)	
6.10	MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)	33
6.11	MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (OCT 2016)	33
6.12	ASBESTOS ABATEMENT (APR 2011)	34
6.13	ONSITE LESSOR MANAGEMENT (APR 2011)	34
6.14	IDENTITY VERIFICATION OF PERSONNEL (OCT 2016)	
6.15	SCHEDULE OF PERIODIC SERVICES (JUN 2012)	
6.16	LANDSCAPING (OCT 2016)	35
6.17	LANDSCAPE MAINTENANCE (APR 2011)	35
6.18	RECYCLING—WAREHOUSE (MAY 2014)	35
6.19	RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)	35
6.20	RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)	00000000
	INTENTIONALLY DELETED	35
6.21	INDOOR AIR QUALITY (OCT 2016)	35
6,22	RADON IN AIR (OCT 2016)	
6.22	RADON IN AIR (SEP 2013) INTENTIONALLY DELETED	36
6.23	RADON IN WATER (JUN 2012) INTENTIONALLY DELETED	36
6.24	HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)	36
6.25	MOLD (OCT 2018) 36	
6.26	OCCUPANT EMERGENCY PLANS (SEP 2013)	36
6.27	FLAG DISPLAY (OCT-2016) INTENTIONALLY DELETED	37
6.28	PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)	37
6.29	TRASH DUMPSTER SERVICE - LESSOR PROVIDED (WAREHOUSE) (OCT 2016)	37
6.30	ACCESS TO BUILDING INFORMATION (MAY 2014)	37
PECT	TON 7 APPLITONAL TERMS AND CONDITIONS	
	10N 7 ADDITIONAL TERMS AND CONDITIONS	38
7.01	SÉCURITY REQUIREMENTS (OCT 2016)	38
7.02	MODIFIED LEASE PARAGRAPHS (OCT 2016)	38
7.03		
7.04	INTENTIONALLY DELETED	
7.04	UNIQUE REQUIREMENTS	
	ADDITIONAL WAREYARD REQUIREMENTS	
7.06	SUBLETTING AND ASSIGNMENT	
1.111	PRIOR LEASE	4.04

THE PREMISES, RENT, AND OTHER TERMS **SECTION 1**

1.01 THE PREMISES (WAREHOUSE) (OCT 2016) Unless otherwise noted, the Government accepts the Premises and tenant improvements in their existing condition, except where specifications or standards are contained elsewhere in this Lease. These standards include security improvements, Fire Protection and Life Safety requirements, ABAAS compliance, as well as compliance with all local codes and ordinances. Such acceptance by the Government of existing Premises shall not relieve Lessor of continuing obligations for cleaning, janitorial, maintenance, repair, etc. as set forth in the Lease paragraphs. Splatel of 189,915 ABOASF further defined as

The Premises are described as follows:

- A. <u>Warehouse and Related Space</u>: 191,573 rentable square feet yielding 186,275 ANSI/BOMA Office Area (ABOA) square feet (SF) of warehouse and related Space and 3,640 ABOA SF of Office and related space as depicted on the floor plan attached hereto as Exhibit A.
- Common Area Factor: The Common Area Factor (CAF), defined under Section 2 of the Lease, is established as 1 (one) percent. This factor, rounded to the nearest whole percentage, shall be used for purposes of rental adjustments in accordance with the Payment Clause of the General Clauses.
- EXPRESS APPURTENANT RIGHTS (WAREHOUSE) (MAY 2014) The Government shall have exclusive or non-exclusive (as identified) right to the use of Appurtenant Areas, and shall have the right to post Rules and Regulations Governing Conduct on Federal Property, Title 41, CFR, Part 102-74, Subpart C within such areas. The Government will coordinate with Lessor to ensure signage is consistent with Lessor's standards. Appurtenant to the Premises and included in the Lease are rights to use the following:
- Automobile Parking: The Lessor shall provide automobile parking spaces as required by the applicable code of the local government entity having jurisdiction over the Property. All spaces must be secured and lit in accordance with the Security Requirements set forth in this Lease. The cost of this parking shall be included as part of the rental consideration.
- Semi-Trailer Staging Area/Warevard: The existing warevard as depicted on the plan attached hereto as Exhibit B shall be repaired as a shell cost. Should new fencing be required to meet this requirement, the cost of new fencing shall be considered as a part of the shell to be provided by lessor. Lessor shall be responsible for maintenance of the wareyard and fence. Refer to the Lease Paragraphs, BUILDING IMPROVEMENTS and ADDITIONAL WAREYARD REQUIREMENTS.
- C.
- (1) At least one unobstructed route having no steps or abrupt changes in level shall connect with all accessible elements, spaces, buildings, and courses of passage. The minimum clear width of a route shall be 36 inches. If a route is less than 60 inches in width then it shall have level passing zones, spaced at no more than 200 feet apart, measuring a minimum of 60 inches by 60 inches.
 - (2) Objects projecting from walls with their leading edges between 27 and 80 inches above the finished floor shall protrude no more than 4 Inches into an accessible route. Freestanding objects mounted on posts or pylons may overhang 12 inches maximum from 27 to 80 inches above the ground or the finished floor. Objects mounted with their leading edges at or below 27 inches above the finished floor may protrude any distance. However, no protructing objects shall reduce the clear width of an accessible route or maneuvering space. If vertical clearance of an area adjoining an accessible route is reduced to less than 80 inches, a barrier to warn blind or visually impaired persons shall be
 - (3) Mechanical rooms and spaces which are not normally frequented by the public or occupants and are not part of an accessible or emergency route are excepted and need not be accessible.
 - (4) Gratings in a route surface shall have spaces no wider than ½ inch in one direction and shall be placed so that the long dimension of openings is perpendicular to the dominant direction of travel.
- D.
- (1) Any part of an accessible route with a slope greater than 1 foot rise in 20 feet shall be considered a ramp. Where ramps are necessary, they shall have a non-alip surface with a slope no greater than 9%. Ramps must have a minimum clear width of 3 feet with level landings at the top and bottom of each ramp run. Each landing shall be at least 5 feet in length and as wide as any ramp run leading into it. The maximum rise for any run shall be 30 inches. Intermediate landings for turning ramps shall measure a minimum of 5 feet by 5 feet.
 - (2) Lessor shall provide handralts complying with "HANDRAILS" (36 CFR 1191) on both sides of all ramps with a vertical rise greater than 6 inches. Ramps with drop-offs shall have curbs (minimum 2 inches high), walls, railings or projecting surfaces. Lessor shall provide curb ramps wherever an accessible route crosses a curb. Curb ramps shall not interfere with walks or vehicular traffic. The maximum slope of a curb ramp shall be a 1 inch rise per 12 inch run. The maximum length of a curb ramp shall be 6 feet with a minimum width of 36 inches, exclusive of flared sides. If no other alternative is feasible, accessible platform lifts may be used in lieu of a ramp or elevator. Lifts shall have accessible controls and clearances, shall comply with applicable safety regulations, and should facilitate unassisted entry and exit.
- Antennas, Satellite Dishes, and Related Transmission Devices:
 - (1) Space located on the roof of the Building sufficient in size for the installation and placement of telecommunications equipment,
 - (2) the right to access the roof of the Building, and

LESSOR: PL GOVERNMENT

- (3) use of all Building areas (e.g., chases, plenums, etc.) necessary for the use, operation, and maintenance of such telecommunications equipment at all times during the term of this Lease.
- F. Loading Docks. See "LOADING DOCKS SHELL WAREHOUSE" paragraph in Section 3 of this Lease.

TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)

At a minimum, a truck turning radius for a 53-foot tractor trailer shall be provided and maintained at all times for all loading docks designed for such sized trucks. One-way design for service traffic is preferred in order to avoid the need for large turning areas,

CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE) (MAY 2014)

Warehouse ceilings shall be at least 25 feet and no more than 35 feet measured from the floor to the lowest obstruction. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided.

BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIREMENTS (WAREHOUSE) (MAY 2014)

The existing bay width, depth, and column spacing is accepted as-is.

RENT AND OTHER CONSIDERATION (OCT 2017) 1.06

The Government shall pay the Lessor annual rent, payable in monthly installments in arrears, at the following rates: A.

	FIRM TERM	Non Firm Term
	ANNUAL RENT	ANNUAL RENT
SHELL RENT ¹	(b) (4)	
OPERATING COSTS ²		
TENANT IMPROVEMENTS RENT ³		
Building Specific Amortized Capital (BSAC)4		
PARKING ⁵		
TOTAL ANNUAL RENT	\$2,185,080.71	\$2,232,990.45
hell rent calculation		•

per RSF multiplied by the RSF stated under Paragraph 1.01

er RSF multiplied by the RSF stated under Paragraph 1.01

- B. Parking shall be provided at a rate of (b) per parking space per month (Surface).
- C. SUBPARAGRAPH INTENTIONALLY DELETED
- D. SUBPARAGRAPH INTENTIONALLY DELETED
- E. Rent is subject to adjustment based upon a mutual on-site measurement of the Space upon acceptance, not to exceed 190,290 ABOA SF based upon the methodology outlined under the "Payment" clause of GSA Form 3517.
- Rent is subject to adjustment based upon the final Tenant Improvement (TI) cost to be amortized in the rental rate, as agreed upon by the parties subsequent to the Lease Award Date.
- G. SUB-PARAGRAPH INTENTIONALLY DELETED
- If the Government occupies the Premises for less than a full calendar month, then rent shall be prorated based on the actual number of days of occupancy for that month.
- Rent shall be paid to the Lessor by electronic funds transfer in accordance with the provisions of the General Clauses. Rent shall be payable to the Payee designated by the Lessor in the System for Award Management (SAM). If the payee is different from the Lessor, both payee and Lessor must be registered in SAM,
- The Lessor shall provide to the Government, in exchange for the payment of rental and other specified consideration, the following:
 - 1. The leasehold interest in the Property described herein in the paragraph entitled "The Premises."
 - 2. All costs, expenses, and fees to perform the work required for acceptance of the Premises in accordance with this Lease, including all costs for labor, materials, and equipment, professional fees, contractor fees, attorney fees, permit fees, inspection fees, and similar such fees, and all related expenses;
 - Performance or satisfaction of all other obligations set forth in this Lease; and all services (with the exclusion of janitorial), utilities, maintenance required for the proper operation of the Property, the Building, and the Leased Premises, in accordance with the terms of the Lease, including, but not limited to, all inspections, modifications, repairs, replacements and improvements required to be made thereto to meet the requirements of this Lease. The Government shall be responsible for paying the cost of janitorial services directly to the provider.



⁽Firm Term) (A) per RSF multiplied by the RSF stated under Paragraph 1.01
(Non Firm Term) (A) per RSF multiplied by the RSF stated under Paragraph 1.02

Operating Costs rent calculation: Per RSF multiplied by the RSF stated under Paragraph 1.03

The Tenant Improvement Allowance of the control of the contr of the existing security improvements are accepted in as-is condition. Building Specific Amortized Capital (BSAC) of Parking costs described under sub-paragraph is beit

1.07 BROKER COMMISSION AND COMMISSION CREDIT (OCT 2016)
A. CBRE, INC. (Broker) is the authorized real estate Broker representing GSA in connection with this Lease transaction. The total amount of the
Commission is a large and is earned upon Lease execution, payable according to the Commission Agreement signed between the Lessor and
Broker. Only (4) of the Commission will be payable to CBRE, INC. with the remaining (5) (4) which is the Commission Credit, to be
credited to the shell rental portion of the annual rental payments due and owing to fully recapture this Commission Credit. The reduction in shell rent
shall commence with the first month of the rental payments and continue until the credit has been fully recaptured in equal monthly installments over
the shortest time practicable.
B. Notwithstanding the "Rent and Other Consideration" paragraph of this Lease, the shell rental payments due and owing under this Lease shall
be reduced to recapture fully this Commission Credit. The reduction in shell rent shall commence with the first month of the rental payments and

Month 1 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) Month 2 Rental Payment (b) (4) minus prorated Commission Credit of (b) (4) equals (b) (4) adjusted 7

Subject to change based on adjustments outlined under the paragraph "Rent and Other Consideration."

TERMINATION RIGHTS (OCT 2016)

The Government may terminate this Lease, in whole or in parts, at any time effective after the Firm Term of this Lease, by providing not less than 90 days' prior written notice to the Lessor. The effective date of the termination shall be the day following the expiration of the required notice period or the termination date set forth in the notice, whichever is later. No rental shall accrue after the effective date of termination.

PARAGRAPH INTENTIONALLY DELETED

1.10 DOCUMENTS INCORPORATED IN THE LEASE (WAREHOUSE) (OCT 2018)

The following documents are attached to and made part of the Lease:

continue as indicated in this schedule for adjusted Monthly Rent:

DOCUMENT NAME	No. of PAGES	EXHIBIT
FLOOR PLAN(S)	1	Α
PARKING/SITE PLAN(S)	1	В
EXPANSION SCOPE OF WORK	13	С
SECURITY REQUIREMENTS, LEVEL (b)	88	D
GSA FORM 3517B GENERAL CLAUSES	15	E
REPRESENTATION REGARDING CERTAIN TELECOMMUNICATIONS AND VIDEO	2	
SURVEILLANCE SERVICES OR EQUIPMENT		F
ADDENDUM TO GENERAL CLAUSES	- 5	G

1.11 TENANT IMPROVEMENT ALLOWANCE (AUG 2011)

The Tenant Improvement Allowance (TIA) for purposes of this Lease is (b) per ABOA SF. The TIA is the amount that the Lessor shall make available for the Government to be used for Tls. This amount is amortized in the rent over the Firm Term of this Lease at an annual interest rate of (b) (4)

TENANT IMPROVEMENT RENTAL ADJUSTMENT (OCT 2016)

- The Government, at its sole discretion, shall make all decisions as to the use of the TIA. The Government may use all or part of the TIA. The Government may return to the Lessor any unused portion of the TIA in exchange for a decrease in rent according to the agreed-upon amortization rate over the Firm Term.
- The Government may elect to make lump sum payments for any or all work covered by the TIA. That part of the TIA amortized in the rent shall be reduced accordingly. At any time after occupancy and during the Firm Term of the Lease, the Government, at its sole discretion, may elect to pay lump sum for any part or all of the remaining unpaid amortized balance of the TIA. If the Government elects to make a lump sum payment for the TIA after occupancy, the payment of the TIA by the Government will result in a decrease in the rent according to the amortization rate over the Firm Term of the Lease.
- C. If it is anticipated that the Government will spend more than the identified TIA, the Government may elect to:
 - Reduce the TI requirements;
 - Pay lump sum for the overage upon substantial completion in accordance with the "Acceptance of Space and Certificate of Occupancy" paragraph;
 - Negotiate an increase in the rent.

1.13	TENANT	IMPROVEMENT	FEE SCHEDUL	E (JUN 2012)
1.10	I PIANTA I	IMILIO A FINE HI	LEE SOUEDOF	-E (JUN &U Z)

For pricing TI costs, the following rates shall apply for the initial build-out of the Space,

INITIAL BUILD-OUT

LESSOR: 13/L GOVERNMENT.

ARCHITECT/ENGINEER FEES (\$ PER ABOA SF or % of TI Construction Costs)	(b) (4)
LESSOR'S PROJECT MANAGEMENT FEE (% OF TI CONSTRUCTION COSTS)		

1.14 PARAGRAPH INTENTIONALLY DELETED

1.15 PARAGRAPH INTENTIONALLY DELETED

1.16 PERCENTAGE OF OCCUPANCY FOR TAX ADJUSTMENT (OCT 2018)

- A. As of the Lease Award Date, the Government's Percentage of Occupancy, as defined in the "Real Estate Tax Adjustment" paragraph of this Lease is 55.46 percent. The Percentage of Occupancy is derived by dividing the total Government Space of 191,673 RSF by the total Building space of 345,600 RSF. The tax parcel number is 05108322.
- B. All relevant tax adjustment documentation (e.g. copies of paid tax receipts, invoices) must be submitted online via the GSA Real Estate Tax Portal at RET.GSA.GOV.

1.17 PARAGRAPH INTENTIONALLY DELETED

1.18 OPERATING COST BASE (OCT 2016)

The parties agree, for the purpose of applying the paragraph titled "Operating Costs Adjustment," that the Lessor's base rate for operating costs shall be (b) per RSF or \$ 12.7 (A) per annum.

1.19 RATE FOR ADJUSTMENT FOR VACANT LEASED PREMISES (SEP 2013)

In accordance with the paragraph entitled "Adjustment for Vacant Premises," if the Government fails to occupy or vacates the entire Premises prior to expiration of the term of the Lease, the operating costs paid by the Government as part of the rent shall be reduced by \$1.50 per ABOA SF of Space vacated by the Government.

1.20 HOURLY OVERTIME HVAC RATES (OCT 2016)

- A. The following rates shall apply in the application of the paragraph titled "Overtime HVAC Usage":
 - (b) (4) per hour for the entire office space only.

1.21 PARAGRAPH INTENTIONALLY DELETED

1.22 BUILDING IMPROVEMENTS (MAR 2016)

Before the Government accepts the Space, the Lessor shall complete the following additional Building improvements:

- A. Lessor shall repair and maintain existing loading dock tarmac in order to achieve a level and even driving surface. Extent of repair is from loading dock south side entry to HHS's last docking bay (Bays 1 through 39). Loading dock apron shall have sufficient structural capacity to handle standard 18 wheeler semi-trailer truck (minimum weight 40 tons) complete with requisite appropriately rated landing strip concrete pads.
- B. Existing windows need to be cleaned and sealed (if necessary) to ensure no water penetration.
- C. Existing Restrooms must be thoroughly cleaned and painted prior to acceptance. Replace stained or damaged ceiling tiles.
- D. As part of the shell consideration, Lessor shall repair the fence. At least one large hole in the fence is visible. Any security improvements to the fence will be paid as part of the Tenant Improvement Allowance.
- E. As evidence of mold remediation in the expansion space, Lessor shall complete indoor air quality test prior to acceptance of space.
- F. Lessor shall install LED exterior tights.
- G. Lessor shall install low flow water fixtures in the restrooms.
- H. Lessor shall address all 10 of the recommendations cited in the Fire Protection and Life Safety Property Condition Assessment submitted by the Lessor and prepared by Reardon Fire Consulting dated January 15, 2020. Please see the report for details. These items must be completed prior to commencement of a new Lesse:
 - a. Provide two batteries for FACP
 - b. Provide outside audible device for sprinkler system.
 - c. Remove all abandoned fire alarm devices within Suite 1.
 - d. Replace all damaged and non-functional Emergency Exit Lights.
 - e. Replace/Repair non-functioning exit signs.
 - f. Provide fire extinguishers.
 - g. Replace missing ceiling tiles.
 - h. Storage Configuration Review

1.23 PARAGRAPH INTENTIONALLY DELETED

1.24 LESSOR'S DUNS NUMBER (OCT 2017)

Lessor's Dun & Bradstreet DUNS Number: 078859367.

LESSOR: BA GOVERNMENT.

SECTION 2 GENERAL TERMS, CONDITIONS, AND STANDARDS

2.01 DEFINITIONS AND GENERAL TERMS (WAREHOUSE) (OCT 2016)

Unless otherwise specifically noted, all terms and conditions set forth in this Lease shall be interpreted by reference to the following definitions, standards, and formulas:

- A. <u>Appurtenant Areas</u>. Appurtenant Areas are defined as those areas and facilities on the Property that are not located within the Premises, but for which rights are expressly granted under this Lease, or for which rights to use are reasonably necessary or reasonably anticipated with respect to the Government's enjoyment of the Premises and express appurtenant rights (such as parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease).
- B. Broker. If GSA awarded this Lease using a contract real estate broker, Broker shall refer to GSA's broker.
- C. <u>Building</u>. Building(s) situated on the Property in which the Premises are located.
- D. <u>Commission Credit</u>. If GSA awarded this Lease using a Broker, and the Broker agreed to forego a percentage of its commission to which it is entitled in connection with the award of this Lease, the amount of this credit is referred to as the "Commission Credit."
- E. <u>Common Area Factor.</u> The "Common Area Factor" (CAF) is a conversion factor determined by the Building owner and applied by the owner to the ABOA SF to determine the RSF for the leased Space. The CAF is expressed as a percentage of the difference between the amount of rentable SF and ABOA SF, divided by the ABOA SF. For example 11,500 RSF and 10,000 ABOA SF will have a CAF of 15% [(11,500 RSF-10,000 ABOA SF)/10,000 ABOA SF]. For the purposes of this Lease, the CAF shall be determined in accordance with the applicable ANSI/BOMA standard for the type of space to which the CAF shall apply.
- F. Contract. "Contract" shall mean this Lease.
- G. <u>Contractor</u>. "Contractor" shall mean Lessor.
- H. <u>Davs.</u> All references to "day" or "days" in this Lease shall mean calendar days, unless specified otherwise.
- FAR. All references to the FAR shall be understood to mean the Federal Acquisition Regulation, codified at 48 CFR Chapter 1.
- J. <u>Firm Term/Non-Firm Term</u>. The Firm Term is that part of the Lease term that is not subject to termination rights. The Non-Firm Term is that part of the Lease term following the end of the Firm Term.
- K. GSAR. All references to the GSAR shall be understood to mean the GSA supplement to the FAR, codified at 48 CFR Chapter 5.
- Lease Term Commencement Date. The date on which the lease term commences.
- M. <u>Lease Award Date</u>. The date the LCO executes the Lease and mails or otherwise furnishes written notification of the executed Lease to the successful Offeror (date on which the parties' obligations under the Lease begin).
- N. <u>Premises.</u> Defined as the total Warehouse Area, Office Area, and other type of Space, together with all associated common areas, described in Section 1 of this Lease, and delineated by plan in the attached exhibit. Parking, wareyards, loading docks, aprons, loading ramps and other areas to which the Government has rights under this Lease are not included in the Premises.
- O. <u>Property.</u> Defined as the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas, wareyards, loading docks, aprons, loading ramps) to which the Government is granted rights.
- P. <u>Racking System Plan</u>—A plan that at a minimum must include clear ceiling height requirement(s), aisle width(s), shelving depth(s) and type of material(s) to be stored. In addition such Plan shall identify locations and dimensions of storage of materials in packed piles, on patlets, in racks, or on shelves.
- Q. Rentable Space or Rentable Square Feet (RSF). Rentable Space is the area for which a tenant is charged rent. It is determined by the Building owner and may vary by city or by building within the same city. The Rentable Space may include a share of Building support/common areas such as elevator lobbies, Building corridors, and floor service areas. Floor service areas typically include restrooms, janitor rooms, telephone closets, electrical closets, and mechanical rooms. The Rentable Space does not include vertical building penetrations and their enclosing walls, such as stairs, elevator shafts, and vertical ducts. Rentable Square Feet is calculated using the following formula for each type of Space (e.g., office, warehouse, etc.) included in the Premises: ABOA SF of Space x (1 + CAF) = RSF.
- R. Space. The Space shall refer to that part of the Premises to which the Government has exclusive use, such as Office Area, or other type of Space. Parking areas, wareyards, loading docks, aprons, loading ramps to which the Government has rights under this Lease are not included in the Space.
- S. <u>Warehouse and office space</u>. For the purposes of this Lease, Space shall be measured in accordance with the standard (Z65.1-1996) provided by American National Standards Institute/Building Owners and Managers Association (ANSI/BOMA) for Office Area, which means "the area

LESSOR: 132 GOVERNMENT:

where a tenant normally houses personnel and/or furniture, for which a measurement is to be computed." References to ABOA mean ANSI/BOMA Office Area.

T. Working Days. Working Days shall mean weekdays, excluding Saturdays and Sundays and Federal holidays.

2.02 AUTHORIZED REPRESENTATIVES (OCT 2016)

Signatories to this Lease shall have full authority to bind their respective principals with regard to all matters relating to this Lease. No other persons shall be understood to have any authority to bind their respective principals, except to the extent that such authority may be explicitly delegated by notice to the other party, or to the extent that such authority is transferred by succession of interest. The Government shall have the right to substitute its Lease Contracting Officer (LCO) by notice, without an express delegation by the prior LCO.

2.03 ALTERATIONS REQUESTED BY THE GOVERNMENT (OCT 2018)

- A. The Government may request the Lessor to provide alterations during the term of the Lease. Alterations will be ordered by issuance of a Lease Amendment, GSA Form 300, Order for Supplies or Services, or a tenant agency-approved form when specifically authorized to do so by the LCO. The General Services Administration Acquisition manual ("GSAM") clause, 552.270-31, Prompt Payment, including its invoice requirements, shall apply to orders for alterations. All orders are subject to the terms and conditions of this Lease and may be placed by the LCO or a warranted contracting officer's representative (COR) in GSA or the tenant agency when specifically authorized to do so by the LCO, subject to the threshold limitation below.
- B. Orders for alterations issued by an authorized COR are limited to no more than \$250,000 (LCOs are not subject to this threshold). This threshold will change according to future adjustments of the simplified acquisition threshold (see FAR 2.101). The LCO will provide the Lessor with a list of tenant agency officials authorized to place orders and will specify any limitations on the authority delegated to tenant agency officials. The tenant agency officials are not authorized to deal with the Lessor on any other matters.
- C. Payments for alterations ordered by the tenant agency under the authorization described in sub-paragraph B will be made directly by the tenant agency placing the order.

2.04 WAIVER OF RESTORATION (OCT 2018)

Lessor shall have no right to require the Government to restore the Premises upon expiration or earlier termination (full or partial) of the Lease, and waives all claims against the Government for waste, damages, or restoration arising from or related to (a) the Government's normal and customary use of the Premises during the term of the Lease (including any extensions thereof), as well as (b) any initial or subsequent alteration to the Premises regardless of whether such alterations are performed by the Lessor or by the Government. At its sole option, the Government may abandon property in the Space following expiration or earlier termination (full or partial) of the Lease, in which case the property will become the property of the Lessor and the Government will be relieved of any liability in connection therewith.

2.05 PAYMENT OF BROKER (JUL 2011)

If GSA awarded the Lease through its Broker, the Lessor shall pay GSA's Broker its portion of the commission one half upon Lease award and the remaining half upon acceptance of the Space. "Its portion of the commission" means the agreed-upon commission to GSA's Broker minus the Commission Credit specified in the Lease or Lease Amendment.

2.06 CHANGE OF OWNERSHIP (OCT 2018)

- A. If during the term of the Lease, title to the Property is transferred, the Lease is assigned, or the Lessor changes its legal name, the Lessor and its successor shall comply with the requirements of FAR Subpart 42.12. If title is transferred, the Lessor shall notify the Government within five days of the transfer of title.
- B. The Government and the Lessor may execute a Change of Name Agreement if the Lessor is changing only its legal name, and the Government's and the Lessor's respective rights and obligations remain unaffected. A sample form is found at FAR 42.1205.
- C. If title to the Property is transferred, or the Lease is assigned, the Government, the original Lessor (Transferor), and the new owner or assignee (Transferee) shall execute a Novation Agreement providing for the transfer of Transferor's rights and obligations under the Lease to the Transferee. When executed on behalf of the Government, a Novation Agreement will be made part of the Lease via Lease Amendment.
- D. In addition to all documents required by FAR 42.1204, the LCO may request additional information (e.g., copy of the deed, bill of sale, certificate of merger, contract, court decree, articles of incorporation, operation agreement, partnership certificate of good standing, etc.) from the Transferor or Transferee to verify the parties' representations regarding the transfer, and to determine whether the transfer of the Lease is in the Government's interest.
- E. If the LCO determines that recognizing the Transferee as the Lessor will not be in the Government's interest, the Transferor shall remain fully liable to the Government for the Transferee's performance of obligations under the Lease, notwithstanding the transfer. Under no condition shall the Government be obligated to release the Transferor of obligations prior to (a) the rent commencement date; and (b) any amounts due and owing to the Government under the Lease have been paid in full or completely set off against the rental payments due under the Lease.
- F. As a condition for being recognized as the Lessor and entitlement to receiving rent, the Transferee must register in the System for Award Management (SAM) for purposes of "All Awards" (See FAR 52.232-33), and complete all required representations and certifications within SAM. In addition, the Transferee must also complete a Foreign Ownership and Financing Representation.
- G. If title to the Property is transferred, or the Lease is assigned, rent shall continue to be paid to the original Lessor, subject to the Government's rights as provided for in this Lease. The Government's obligation to pay rent to the Transferee shall not commence until the Government has received all information reasonably required by the LCO under sub-paragraph D, the Government has determined that recognizing the Transferee as the Lessor is in the Government's interest (which determination will be prompt and not unreasonably withheld), and the Transferee has met all conditions specified in sub-paragraph F.

LESSOR: // GOVERNMENT:

LEASE NO. GS-03P-LMD00631, PAGE 10

2.07 REAL ESTATE TAX ADJUSTMENT (JUN 2012)

- A. <u>Purpose</u>: This paragraph provides for adjustment in the rent (tax adjustment) to account for increases or decreases in Real Estate Taxes for the Property after the establishment of the Real Estate Tax Base, as those terms are defined herein. Tax adjustments shall be calculated in accordance with this paragraph.
- B. <u>Definitions</u>: The following definitions apply to the use of the terms within this paragraph:

<u>Fully Assessed</u>. The Property is deemed to be "Fully Assessed" (and Real Estate Taxes are deemed to be based on a Full Assessment) only when a Taxing Authority has, for the purpose of determining the Lessor's liability for Real Estate Taxes, determined a value for the Property taking into account the value of all improvements contemplated for the Property pursuant to the Lesso, and issued to the Lessor a tax bill or other notice of levy wherein the Real Estate Taxes for the full Tax Year are based upon such Full Assessment. At no time prior to the issuance of such a bill or notice shall the Property be deemed Fully Assessed.

<u>Property</u>. "Property" has the same definition as provided in Section 2.01 of this Lease. It is the land and Buildings in which the Premises are located, including all Appurtenant Areas (e.g., parking areas, wareyards, loading docks, aprons, loading ramps) to which the Government is granted rights.

Real Estate Taxes. Those taxes levied upon the owners of real property by a Taxing Authority (as hereinafter defined) of a state or local Government on an ad valorem basis to raise general revenue for funding the provision of government services. "Real Estate Taxes" excludes, without limitation, special assessments for specific purposes, assessments for business improvement districts, and/or community development assessments.

<u>Taxing Authority</u>. The state, commonwealth, territory, county, city, parish, or political subdivision thereof, authorized by law to levy, assess, and collect Real Estate Taxes.

Tax Year. The 12-month period adopted by a Taxing Authority as its fiscal year for assessing Real Estate Taxes on an annual basis.

<u>Tax Abatement</u>. An authorized reduction in the <u>Lessor's liability for Real Estate Taxes below that determined by applying the generally applicable real estate tax rate to the Fully Assessed (as hereinafter defined) valuation of the Property.</u>

<u>Unadjusted Real Estate Taxes</u>. The full amount of Real Estate Taxes that would be assessed for the Property for one full Tax Year without regard to the Lessor's entitlement to any Tax Abatements (except if such Tax Abatement came into effect after the date of award of the Lease), and not including any late charges, interest or penalties. If a Tax Abatement comes into effect after the date of award of the Lease, "unadjusted Real Estate Taxes" are the full amount of Real Estate Taxes assessed for the Property for one full Tax Year, less the amount of such Tax Abatement, and not including any late charges, interest, or penalties.

Real Estate Tax Base. The Unadjusted Real Estate Taxes for the first full Tax Year following the commencement of the Lease term. If the Real Estate Taxes for that Tax Year are not based upon a Full Assessment of the Property, then the Real Estate Tax Base shall be the Unadjusted Real Estate Taxes for the Property for the first full Tax Year for which the Real Estate Taxes are based upon a Full Assessment. Such first full Tax Year may be hereinafter referred to as the Tax Base Year. Alternatively, the Real Estate Tax Base may be an amount negotiated by the parties that reflects an agreed upon base for a Fully Assessed value of the Property.

Percentage of Occupancy. That portion of the Property exclusively occupied or used by the Government pursuant to the Lease. For Buildings, the Percentage of Occupancy is determined by calculating the ratio of the RSF occupied by the Government pursuant to the Lease to the total RSF in the Building or Buildings so occupied, and shall not take into account the Government's ancillary rights including, but not limited to, parking or roof space for antennas (unless facilities for such ancillary rights are separately assessed). This percentage shall be subject to adjustment to take into account increases or decreases for Space leased by the Government or for rentable space on the Property.

C. Adjustment for changes in Real Estate Taxes. After the Property is Fully Assessed, the Government shall pay its share of any increases and shall receive its share of any decreases in the Real Estate Taxes for the Property, such share of increases or decreases to be referred to herein as "tax adjustment." The amount of the tax adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base, less the portion of such difference not paid due to a Tax Abatement (except if a Tax Abatement comes into effect after the date of award of the Lease). If a Tax Abatement comes into effect after the date of award of the Lease, the amount of the tax adjustment shall be determined by multiplying the Government's Percentage of Occupancy by the difference between the current year Unadjusted Real Estate Taxes and the Real Estate Tax Base. The Government shall pay the tax adjustment in a single annual lump sum payment to the Lessor. In the event that this tax adjustment results in a credit owed to the Government, the Government may elect to receive payment in the form of a rental credit or lump sum payment.

If the Property contains more than one separately assessed parcel, then more than one tax adjustment shall be determined based upon the Percentage of Occupancy, Real Estate Tax Base, and Real Estate Taxes for each respective parcel.

After commencement of the Lease term, the Lessor shall provide to the LCO copies of all real estate tax bills for the Property, all documentation of Tax Abatements, credits, or refunds, if any, and all notices which may affect the assessed valuation of the Property, for the Tax Year prior to the commencement of the Lease Term, and all such documentation for every year following. Lessor acknowledges that the LCO shall rely on the completeness and accuracy of these submissions in order to establish the Real Estate Tax Base and to determine tax adjustments. The LCO may memorialize the establishment of the Real Estate Tax Base by issuing a unilateral administrative lease amendment indicating the base year, the amount of the Real Estate Tax Base, and the Government's Percentage of Occupancy.

The Real Estate Tax Base is subject to adjustment when increases or decreases to Real Estate Taxes in any Tax Year are attributable to (a) improvements or renovations to the Property not required by this Lease, or (b) changes in net operating income for the Property not derived from this Lease. If either condition results in a change to the Real Estate Taxes, the LCO may re-establish the Real Estate Tax Base as the Unadjusted Real

LESSOR: 151- GOVERNMENT:

Estate Taxes for the Tax Year the Property is reassessed under such condition, less the amount by which the Unadjusted Real Estate Taxes for the Tax Year prior to reassessment exceeds the prior Real Estate Tax Base.

If this Lease includes any options to renew the term of the Lease, or be otherwise extended, the Real Estate Tax Base for determining tax adjustments during the renewal term or extension shall be the last Real Estate Tax Base established during the base term of the Lease.

If any Real Estate Taxes for the Property are retroactively reduced by a Taxing Authority during the term of the Lease, the Government shall be entitled to a proportional share of any tax refunds to which the Lessor is entitled, calculated in accordance with this Paragraph. Lessor acknowledges that it has an affirmative duty to disclose to the Government any decreases in the Real Estate Taxes paid for the Property during the term of the Lease. Lessor shall annually provide to the LCO all relevant tax records for determining whether a tax adjustment is due, irrespective of whether it seeks an adjustment in any Tax Year.

If the Lease terminates before the end of a Tax Year, or if rent has been suspended, payment for the real estate tax increase due because of this section for the Tax Year will be prorated based on the number of days that the Lease and the rent were in effect. Any credit due the Government after the expiration or earlier termination of the Lease shall be made by a lump sum payment to the Government or as a rental credit to any succeeding Lease, as determined in the LCO's sole discretion. Lessor shall remit any lump sum payment to the Government within 15 calendar days of payment or credit by the Taxing Authority to Lessor or Lessor's designee. If the credit due to the Government is not paid by the due date, interest shall accrue on the late payment at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978, as amended (41 USC § 611), that is in effect on the day after the due date. The interest penalty shall accrue daily on the amount of the credit and shall be compounded in 30-day increments inclusive from the first day after the due date through the payment date. The Government shall have the right to pursue the outstanding balance of any tax credit using all such collection methods as are available to the United States to collect debts. Such collection rights shall survive the expiration of this Lease.

In order to obtain a tax adjustment, the Lessor shall furnish the LCO with copies of all paid tax receipts, or other similar evidence of payment acceptable to the LCO, and a proper invoice (as described in GSA Form 3517, General Clauses, 552.270-31, Prompt Payment) for the requested tax adjustment, including the calculation thereof. All such documents must be received by the LCO within 60 calendar days after the last date the real estate tax payment is due from the Lessor to the Taxing Authority without payment of penalty or interest. FAILURE TO SUBMIT THE PROPER INVOICE AND EVIDENCE OF PAYMENT WITHIN SUCH TIME FRAME SHALL CONSTITUTE A WAIVER OF THE LESSOR'S RIGHT TO RECEIVE A TAX ADJUSTMENT PURSUANT TO THIS PARAGRAPH FOR THE TAX YEAR AFFECTED.

D. <u>Tax Appeals</u>. If the Government occupies more than 50 percent of the Building by virtue of this and any other Government Lease(s), the Government may, upon reasonable notice, direct the Lessor to initiate a tax appeal, or the Government may elect to contest the assessed valuation on its own behalf or jointly on behalf of Government and the Lessor. If the Government elects to contest the assessed valuation on its own behalf or on behalf of the Government and the Lessor, the Lessor shall cooperate fully with this effort, including, without limitation, furnishing to the Government information necessary to contest the assessed valuation in accordance with the filing requirements of the Taxing Authority, executing documents, providing documentary and testimonial evidence, and verifying the accuracy and completeness of records. If the Lessor initiates an appeal at the direction of the Government, the Government shall have the right to approve the selection of counsel who shall represent the Lessor with regard to such appeal, which approval shall not be unreasonably withheld, conditioned or delayed, and the Lessor shall be entitled to a credit in the amount of its reasonable expenses in pursuing the appeal.

2.08 ADJUSTMENT FOR VACANT PREMISES (OCT 2017)

- A. If the Government falls to occupy any portion of the leased Premises or vacates the Premises in whole or in part prior to expiration of the term of the Lease, the rental rate and the base for operating cost adjustments will be reduced using the figure specified in the "Rate for Adjustment for Vacant Leased Premises" paragraph of this Lease.
- B. If no rate reduction has been established in this Lease, the rate will be reduced by that portion of the costs per ABOA SF of operating expenses not required to maintain the Space.
- C. Said reduction shall occur after the Government gives 30 calendar days' prior notice to the Lessor and shall continue in effect until the Government occupies the vacant Premises or the Lease expires or is terminated.

2.09 OPERATING COSTS ADJUSTMENT (JUN 2012)

- A. Beginning with the second year of the Lease and each year thereafter, the Government shall pay, if the particular service is provided by lessor, annual incremental adjusted rent for changes in costs for landscaping, water, sewer charges, heating, electricity, and certain administrative expenses attributable to occupancy.
- B. The amount of adjustment will be determined by multiplying the base rate by the annual percent of change in the Cost of Living Index. The percent change will be computed by comparing the index figure published for the month prior to the Lease Term Commencement Date with the index figure published for the month prior which begins each successive 12-month period. For example, a Lease which commences in June of 2005 would use the index published for May of 2005, and that figure would be compared with the index published for May of 2006, May of 2007, and so on, to determine the percent change. The Cost of Living Index will be measured by the Department of Labor revised Consumer Price Index for Urban Wage Earners and Clerical Workers (CPI-VV), U.S. city average, all Items, (1982 to 1984 = 100) published by the Bureau of Labor Statistics. Payment will be made with the monthly installment of fixed rent. Rental adjustments will be effective on the anniversary date of the Lease; however, payment of the adjusted rental rate will become due on the first workday of the second month following the publication of the Cost of Living Index for the month prior to the commencement of each 12-month period.
- C. In the event of any decreases in the Cost of Living Index occurring during the term of the occupancy under the Lease, the rental amount will be reduced accordingly. The amount of such reductions will be determined in the same manner as increases in rent provided under this paragraph.
- D. If the Government exercises an option to extend the Lease term at the same rate as that of the original term, the option price will be based on the adjustment during the original term. Annual adjustments will continue.

LESSOR: KA GOVERNMENT:

2.10 ADDITIONAL POST-AWARD FINANCIAL AND TECHNICAL DELIVERABLES (JUN 2012)

- A. SUBPARAGRAPHINTENTIONALLY DELETED
- B. Within 20 days after Lease award, the Lessor shall provide to the LCO (or representative designated by the LCO) evidence of:
 - 1. A firm commitment of funds in an amount sufficient to perform the work.
 - 2. The names of at least two proposed construction contractors, as well as evidence of the contractors' experience, competency, and performance capabilities with construction similar in scope to that which is required herein.
 - 3. The license or certification to practice in the state where the Building is located from the individual(s) and/or firm(s) providing architectural and engineering design services.
- C. SUBPARAGRAPH INTENTIONALLY DELETED
- D. Within ten (10) calendar days after the LCO issues the Notice To Proceed (NTP) for TI construction, the Lessor shall provide to the LCO evidence of:
 - 1. Award of a construction contract for TIs with a firm completion date. This date must be in accordance with the construction schedule for TIs as described in the "Schedule for Completion of Space" paragraph of this Lease.
 - 2. Issuance of required permits for construction of the TIs.

2.11 PARAGRAPH INTENTIONALLY DELETED

LESSOR: Br GOVERNMENT:

GSA FORM L201WH (10/18)

LEASE NO. GS-03P-LMD00631, PAGE 13 LESSOR: 121- GOVERNMENT:

SECTION 3 CONSTRUCTION STANDARDS AND SHELL COMPONENTS

3.01 PARAGRAPH INTENTIONALLY DELETED

3.02 WORK PERFORMANCE (JUN 2012)

All work in performance of this Lease shall be done by skilled workers or mechanics and shall be acceptable to the LCO. The LCO may reject the Lessor's workers 1) if such are unlicensed, unskilled, or otherwise incompetent, or 2) if such have demonstrated a history of either untimely or otherwise unacceptable performance in connection with work carried out in conjunction with either this contract or other government or private contracts.

3.03 ENVIRONMENTALLY PREFERABLE PRODUCTS REQUIREMENTS) (OCT 2017)

- The Lessor must provide environmentally preferable products as detailed throughout individual subsections of this Lease.
- B. When individual subsections of this Lease do not contain specific requirements for environmentally preferable products, the Lessor must provide products meeting at least one of the environmentally preferable criteria outlined under the Green Procurement Compilation at www.sftool.gov/greenprocurement to determine whether any of these criteria are applicable for a product category.
- C. The Lessor, if unable to comply with the environmentally preferable products requirements above, must submit a waiver request for each material to the LCO within the TI pricing submittal. The waiver request shall be based on the following exceptions:
 - 1. Product cannot be acquired competitively within a reasonable performance schedule.
 - 2. Product cannot be acquired that meets reasonable performance requirements.
 - Product cannot be acquired at a reasonable price.
 - 4. An exception is provided by statute.

The price shall be deemed unreasonable when the total life cycle costs are significantly higher for the sustainable product versus the non-sustainable product. Life cycle costs are determined by combining the initial costs of a product with any additional costs or revenues generated from that product during its entire life.

3.04 EXISTING FIT-OUT, SALVAGED, OR REUSED BUILDING MATERIAL (JUN 2012)

- A. Items and materials existing in the Premises, or to be removed from the Premises during the demolition phase, are eligible for reuse in the construction phase of the project. The reuse of items and materials is preferable to recycling them; however, items considered for reuse shall be in refurbished condition and shall meet the quality standards set forth by the Government in this Lease. In the absence of definitive quality standards, the Lessor is responsible to confirm that the quality of the item(s) in question shall meet or exceed accepted industry or trade standards for first quality commercial grade applications.
- B. The Lessor shall submit a reuse plan to the LCO. The Government will not pay for existing fixtures and other TIs accepted in place. However, the Government will reimburse the Lessor, as part of the TIA, the costs to repair or improve such fixtures or improvements identified on the reuse plan and approved by the LCO.

3.05 CONSTRUCTION WASTE MANAGEMENT (OCT 2017)

- A. Recycling construction waste is mandatory for initial space alterations for TIs and subsequent alterations under the Lease.
- B. <u>SUBMITTAL REQUIREMENT</u>: Refer to the Green Lease Submittals paragraph of the Lease.
- C. The Lessor shall recycle the following items during both the demolition and construction phases of the project, subject to economic evaluation and feasibility: Ceiling grid and tile, light fixtures, including proper disposal of any transformers, ballasts, and fluorescent light bulbs, duct work and HVAC equipment, wiring and electrical equipment, aluminum and/or steel doors and frames, hardware, drywall, steel studs, carpet, carpet backing, and carpet padding, wood, insulation, cardboard packaging, pallets, windows and glazing materials, all miscellaneous metals (as in steel support frames for filing equipment), and all other finish and construction materials.
- D. If any waste materials encountered during the demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCBs) (such as fluorescent lamp ballasts), or other harmful substances, they shall be handled and removed in accordance with Federal and state laws and requirements concerning hazardous waste.
- E. In addition to providing "one time" removal and recycling of large scale demolition Items such as carpeting or drywall, the Lessor shall provide continuous facilities for the recycling of incidental construction waste during the initial construction.
- F. Construction materials recycling records shall be maintained by the Lessor and shall be accessible to the LCO. Records shall include materials recycled or land-filled, quantity, date, and identification of hazardous wastes.

3.06 WOOD PRODUCTS (OCT 2016)

A. For all new installations of wood products, the Lessor is encouraged to use independently certified forest products. For information on certification and certified wood products, refer to the Forest Stewardship Council United States (<u>HTTPS://US.FSC.ORG/EN-US</u>), or the Sustainable Forestry Initiative (<u>HTTP://WWW.SFIPROGRAM.ORG</u>/).

LESSOR: BM GOVERNMENT:

- B. New installations of wood products used under this contract shall not contain wood from endangered wood species, as listed by the Convention on International Trade in Endangered Species. The list of species can be found at https://www.fws.gov/international/plants/current-cites-listings-of-tree-species.html.
- C. Particle board, strawboard, and plywood materials shall comply with Department of Housing and Urban Development (HUD) standards for formaldehyde emission controls. Plywood materials shall not emit formaldehyde in excess of 0.2 parts per million (ppm), and particleboard materials shall not emit formaldehyde in excess of 0.3 ppm.
- D. All materials comprised of combustible substances, such as wood plywood and wood boards, shall be treated with fire retardant chemicals by a pressure impregnation process or other methods that treats the materials throughout as opposed to surface treatment.

3.07 ADHESIVES AND SEALANTS (OCT 2017)

All adhesives employed on this project (including, but not limited to, adhesives for carpet, carpet tile, plastic laminate, wall coverings, adhesives for wood, or sealants) shall meet at least one of the environmentally preferable criteria as outlined under the Green Procurement Compilation at https://sftool.gov/greenprocurement continued the Green Procurement Compilation at https://sftool.gov/greenprocurement and sealants with no formaldehyde or heavy metals. Adhesives and other materials used for the installation of carpets shall be limited to those having a flash point of 140 degrees F or higher.

3.08 BUILDING SHELL REQUIREMENTS (WAREHOUSE) (OCT 2016)

- A. The Building Shell shall be designed, constructed, and maintained in accordance with the standards set forth herein and completed prior to acceptance of Space. For pricing, fulfillment of all requirements not specifically designated as TIs, Building Specific Amortized Capital, Operating Costs, or other rent components as indicated shall be deemed included in the Shell Rent.
- B. Base structure and Building enclosure components shall be complete. All common areas accessible by the Government, such as lobbies, fire egress corridors and stainwells, elevators, garages, and service areas, shall be complete. Restrooms shall be complete and operational with an adequate number of fixtures for men and women to meet current local codes based on building occupancy and use. All newly installed Building shell components, including but not limited to, heating and ventilation, electrical, ceilings, sprinklers, etc., shall be furnished, installed, and coordinated with Tls. Circulation corridors are provided as part of the base Building only on multi-tenanted buildings where the corridor is common to more than one tenant. In single tenant buildings, only the fire egress corridor(s) necessary to meet code is provided as part of the shell.
- C. The Building Shell rental rate shall also include, but is not limited to, costs included listed under Section II of GSA Form 1217, Lessor's Annual Cost Statement, including insurance, taxes, lease commission and management, in addition to profit, reserve costs and loan financing for the Building.

3.09 RESPONSIBILITY OF THE LESSOR AND LESSOR'S ARCHITECT/ENGINEER (JUN 2012)

- A. The Lessor shall be responsible for the professional quality, technical accuracy, and the coordination of all designs, drawings, specifications, and other services furnished by the Lessor under this contract. The Lessor shall, without additional compensation, correct or revise any errors or deficiencies in its designs, drawings, specifications, or other services.
- B. THE LESSOR REMAINS SOLELY RESPONSIBLE FOR DESIGNING, CONSTRUCTING, OPERATING, AND MAINTAINING THE LEASED PREMISES IN FULL ACCORDANCE WITH THE REQUIREMENTS OF THE LEASE. The Government retains the right to review and approve many aspects of the Lessor's design, including without limitation, review of the Lessor's design and construction drawings, shop drawings, product data, finish samples, and completed base building and TI construction. Such review and approval is intended to identify potential design flaws, to minimize costly misdirection of effort, and to assist the Lessor in its effort to monitor whether such design and construction comply with applicable laws and satisfy all Lease requirements.
- C. Neither the Government's review, approval or acceptance of, nor payment through rent of the services required under this contract, shall be construed to operate as a waiver of any rights under this contract or of any cause of action arising out of the performance of this contract, and the Lessor shall be and remain liable to the Government in accordance with applicable law for all damages to the Government caused by the Lessor's negligent performance of any of the services required under this Lease.
- D. Design and construction and performance information is contained throughout several of the documents which comprise this Lease. The Lessor shall provide to space planners, architects, engineers, construction contractors, etc., all information required whether it is found in this Lease, special requirements and attachments, price lists, or design intent drawings. Reliance upon one of these documents to the exclusion of any other may result in an incomplete understanding of the scope of the work to be performed and/or services to be provided.

3.10 QUALITY AND APPEARANCE OF BUILDING (WAREHOUSE) (MAY 2014)

The Building in which the leased Space is located shall be designed, built, and maintained in good condition, suitable for Lessee's use at all times, and in accordance with the requirements of this Lease.

3.11 **VESTIBULES (APR 2011)**

- A. Vestibules shall be provided at public entrances and exits wherever weather conditions and heat loss are important factors for consideration. In the event of negative air pressure conditions, provisions shall be made for equalizing air pressure.
- B. The Lessor shall provide permanent entryway systems (such as grilles or grates) to control dirt and particulates from entering the Building at all primary exterior entryways.

3.12 MEANS OF EGRESS (WAREHOUSE) (MAY 2015)

A. Prior to occupancy, the Premises and any parking garage areas shall meet or will be upgraded to meet, either the applicable egress requirements in the National Fire Protection Association, Life Safety Code (NFPA 101), or the International Code Council, International Building Code

LESSOR: 18/4-GOVERNMENT

(IBC), each current as of the Lease Award Date, or use an alternative approach or method that achieves an equivalent level of safety deemed acceptable by the Government.

- B. The Space shall have unrestricted access to a minimum of two remote exits on each floor of Government occupancy.
- C. Doors shall not be locked in the direction of egress unless equipped with special locking hardware in accordance with requirements of NFPA 101 or the IBC.

3.13	AUTOMATIC FIRE SPRINKLER SYSTEM (WAREHOUSE) (MAY 2014)
(b) (5)	
(D)	

3.14 FIRE ALARM SYSTEM (WAREHOUSE) (MAY 2014)

	the remains a committee of the state of the
(b) (5)	
a dood ja	namos ana secupane, et me opase.

3.15 ENERGY INDEPENDENCE AND SECURITY ACT (MAR 2016)

A. Energy-related Requirements:

LEASE NO. GS-03P-LMD00631, PAGE 16

- 1. The Energy Independence and Security Act (EISA) establishes the following requirements for Government leases in Buildings that have not earned the ENERGY STAR® Label conferred by the Environmental Protection Agency (EPA) within one year prior to the due date for final proposal revisions ("most recent year").
- 2. If this Lease was awarded under any of EISA's Section 435 statutory exceptions, the Lessor shall either:
 - a. Earn the ENERGY STAR® Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding lease); or
 - (i) Complete energy efficiency and conservation improvements if any, agreed to by Lessor in lieu of earning the ENERGY STAR®
 Label prior to acceptance of the Space (or not later than one year after the Lease Award Date of a succeeding or superseding lease); and
 - (ii) Obtain and publicly disclose the Building's current ENERGY STAR® score (using EPA's Portfolio Manager tool), unless the Lessor cannot access whole building utility consumption data, or there is no building category within Portfolio Manager to benchmark against, including spaces—
 - That are located in States with privacy laws that provide that utilities shall not provide such aggregated information to multitenant building owners; and
 - II. For which tenants do not provide energy consumption information to the commercial building owner in response to a request from the building owner. (A Federal agency that is a tenant of the space shall provide to the building owner, or authorize the owner to obtain from the utility, the energy consumption information of the space for the benchmarking and disclosure required by this subparagraph D).
 - III. That cannot be benchmarked (scored) using EPA's Portfolio Manager tool because of excessive vacancy; in which case Lessor agrees to obtain the score and publicly disclose it within 120 days of the eligibility to obtain a score using the EPA Portfolio Manager tool.

Note: "public disclosure" means posting the Energy Star® score on state or local websites in those areas that have applicable disclosure mandates, and reporting the score to the Government via Portfolio Manager. In the absence of an applicable state or local disclosure

LESSOR: 182 GOVERNMENT:

mandate, Lessor shall either generate and display the Energy Star® score in a public space at the building location or post the score on Lessor's or Lessor's Parent/Affiliate website.

- 3. If this Lease was awarded to a Building to be built or to a Building predominantly vacant as of the due date for final proposal revisions and was unable to earn the ENERGY STAR® label for the most recent year (as defined above) due to insufficient occupancy, but was able to demonstrate sufficient evidence of capability to earn the ENERGY STAR® label, then Lessor must earn the ENERGY STAR® label within 18 months after occupancy by the Government.
- 4. The Lessor is encouraged to purchase at least 50 percent of the Government tenant's electricity from renewable sources.

B. <u>Hydrology-related Requirements</u>:

- 1. Per EISA Section 438, the sponsor of any development or redevelopment project involving a Federal facility with a footprint that exceeds 5,000 square feet shall use site planning, design, construction, and maintenance strategies for the property to maintain or restore, to the maximum extent technically feasible, the predevelopment hydrology of the Property with regard to the temperature, rate, volume, and duration of flow. If the Lessor proposes to satisfy the Government's space requirements through a development or redevelopment project, and the Government will be the sole or predominant tenant such that any other use of the Property will be functionally or quantitatively incidental to the Government's use, the Lessor is required to implement hydrology maintenance and restoration requirements as required by EISA Section 438.
 - a. For the purposes of applying EISA Section 438 in this Lease, "sponsor" shall mean "Lessor", and "exceeds 5,000 square feet" shall mean construction that disturbs 5,000 square feet or more of land area at the Property or on adjoining property to accommodate the Government's requirements, or at the Property for whatever reason. Information regarding implementation of the hydrology maintenance and restoration requirements can be found at: http://www.epa.gov/greeningepa/technical-guidance-implementing-stormwater-runoff-requirements-federal-projects
 - b. Lessor is required to implement these hydrology maintenance and restoration requirements to the maximum extent technically feasible, prior to acceptance of the Space, (or not later than one year after the Lease Award Date or Lease Term Commencement Date, whichever is later, of a succeeding or superseding lease). Additionally, this Lease requires EISA Section 438 storm water compliance not later than one year from the date of any applicable disturbance (as defined in EISA Section 438) of more than 5,000 square feet of ground area if such disturbance occurs during the term of the Lease if the Government is Government is the sole or predominant tenant. In the event the Lessor is required to comply with EISA Section 438, Lessor shall furnish the Government, prior to the filing for permits for the associated work, with a certification from Lessor's engineer that the design meets the hydrology maintenance and restoration requirements of EISA Section 438.

3.16 PARAGRAPH INTENTIONALLY DELETED

3.17 PARAGRAPH INTENTIONALLY DELETED

3.18 **DEMOLITION (JUN 2012)**

The Lessor shall remove existing abandoned electric, telephone, and data cabling and devices, as well as any other improvements or fixtures in place to accommodate the Government's requirements. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at the Lessor's expense.

3.19 ACCESSIBILITY (FEB 2007)

The Building, leased Space, and areas serving the leased Space shall be accessible to persons with disabilities in accordance with the Architectural Barriers Act Accessibility Standard (ABAAS), Appendices C and D to 36 CFR Part 1191 (ABA Chapters 1 and 2, and Chapters 3 through 10). To the extent the standard referenced in the preceding sentence conflicts with local accessibility requirements, the more stringent shall apply.

3.20 EXTERIOR AND COMMON AREA DOORS AND HARDWARE (WAREHOUSE) (MAY 2014)

A. Exterior Building doors and doors necessary to the lobbies, common areas, and core areas shall be required. This does not include suite entry or interior doors specific to Tls.

В.	Exterior doors shall be weather tight and shall open outward. (0) (5)
b) (5)	These doors shall have a minimum clear opening of 32" clear wide x 80" high (per leaf). Doors shall be heavy
duty, f	iush, (1) hollow steel construction, (2) solid core wood, or (3) insulated tempered glass. As a minimum requirement, hollow steel doors shall be
fully in	isulated, flush, #16-gauge hollow steel. Solid-core wood doors and hollow steel doors shall be at least 1-3/4 inches thick. Door assemblies shall
be of	durable finish and shall have an aesthetically pleasing appearance acceptable to the LCO. The opening dimensions and operations shall
confor	m to the governing building, fire safety, accessibility for the disabled, and energy codes and/or requirements. Fire door assemblies shall be listed
and la	beled. Labels on fire door assemblies shall be maintained in a legible condition.

- C. Exterior doors and all common area doors shall have door handles or door pulls with heavyweight hinges. All doors shall have corresponding doorstops (wall or floor mounted) and silencers. All public use doors and restroom doors shall be equipped with kick plates. All doors shall have automatic door closers. All Building exterior doors shall have locking devices installed to reasonably deter unauthorized entry. The Lessor is encouraged to avoid the use of chrome-plated hardware.
- D. There shall be unrestrictive access to a minimum of two remote exits on each floor of the Government's occupancy.

LESSOR: BA GOVERNMENT:

LEASE NO. GS-03P-LMD00631. PAGE 17

E. Loading docks shall have a roll-up coiling type door with lock.

3.21 DOORS: IDENTIFICATION (APR 2011)

All signage required in common areas unrelated to tenant identification shall be provided and installed by the Lessor.

3.22 WINDOWS (APR 2011)

- A. Office Space shall have windows in each exterior bay unless waived by the LCO.
- B. All windows shall be weather tight. Operable windows that open shall be equipped with locks. Off-street, ground-level windows and those accessible from adjacent roofs, and other structures that can be opened must be fitted with a sturdy locking device.

3.23 PARTITIONS: GENERAL (APR 2015)

Partitions in public areas shall be marble, granite, hardwood, or drywall covered with durable wall covering or high performance coating, or equivalent pre-approved by the LCO. Newly installed gypsum board material must be Greenguard Gold Certified or have 0 grams per liter of VOCs.

3.24 PARTITIONS: PERMANENT (APR 2015)

Permanent partitions shall extend from the structural floor slab to the structural ceiling slab. They shall be provided by the Lessor as part of shell rent as necessary to surround the Space, stairs, corridors, elevator shafts, restrooms, all columns, and janitor closets. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84). Stairs, elevators, and other floor openings shall be enclosed by partitions and shall have the fire resistance required by the applicable building code, fire code and ordinances adopted by the jurisdiction in which the Building is located (such as the International Building Code, etc.) current as of the Lease Award Date. Newly installed gypsum board material must be Greenguard Gold Certified or have 0 grams per liter of VOCs.

3.25 INSULATION: THERMAL, ACOUSTIC, AND HVAC (SEP 2013)

- A. All insulation products shall contain recovered materials as required by EPA's CPG and related recycled content recommendations.
- B. No insulation installed with this project shall be material manufactured using chlorofluorocarbons (CFCs), nor shall CFCs be used in the installation of the product.
- C. All insulation containing fibrous materials exposed to air flow shall be rated for that exposure or shall be encapsulated.
- D. Insulating properties for all materials shall meet or exceed applicable industry standards. Polystyrene products shall meet American Society for Testing and Materials (ASTM) C578 91.
- E. All insulation shall be low emitting with not greater than .05 ppm formaldehyde emissions.
- F. The maximum flame spread and smoke developed index for insulation shall meet the requirements of the applicable local codes and ordinances (current as of the Lease Award Date) adopted by the jurisdiction in which the Building is located.

3.26 WALL FINISHES—SHELL (JUN 2012)

- A. Prior to occupancy, all restrooms within the building common areas of government-occupied floors shall have semigloss paint on remaining wall areas, or other finish approved by the government.
- B. All elevator areas that access the Space and hallways accessing the Space shall be covered with wall coverings not less than 20 ounces per square yard, high performance paint, or an equivalent.

3.27 PAINTING—SHELL (OCT 2017)

- A. The Lessor shall bear the expense for all painting associated with the Building shell. These areas shall include all common areas. Exterior perimeter walls and interior core walls within the Space shall be spackled and prime painted with a primer that meets or is equivalent to the Green Seal GS-11 standard. If any Building shell areas are already painted prior to TIs, the Lessor shall repaint, at the Lessor's expense, as necessary during TIs.
- The costs for cyclical painting requirements as outlined in Section 6 shall be included in the shell rent.

3.28 FLOORS AND FLOOR LOAD—SHELL (WAREHOUSE) (APR 2015)

- A. Floors shall be of a common level, non-slip and acceptable to the Contracting Officer. The uniformly distributed design live floor load of all warehouse floors shall be no less than 250 pounds per ABOA SF. Written certification of the floor load capacity by a registered professional engineer may be required, at no cost to the Government. Calculations and structural drawings may also be required. Warehouse and storage area floors shall be smooth concrete and must be sealed with an epoxy or urethane sealer, acceptable to the Contracting Officer with an expected service life of no less than 5 years. All cracks in the concrete warehouse floor shall be repaired and all spall shall be patched with a commercial-grade epoxy cement. The floors must be resealed no less than once every 5 years(unless waived by the Contracting Officer. Non-performance of said sealing shall not be acceptable less approved via a written waiver from the GSA Contracting Officer. The Government shall be responsible for moving of all obstacles (such as pallets, boxes, forklifts, etc.) in the warehouse, excluding all permanent fixtures, so that the floors may be properly resealed. The Lessor shall be responsible for coordinating its work or that of its contractor with the efforts of the Government tenant agency.
- B. Office areas shall have a minimum live load capacity of 50 pounds per ABOA SF plus 20 pounds per ABOA SF for moveable partitions. Office storage areas shall have a minimum live load capacity of 100 pounds per ABOA SF including moveable partitions.
- C. SUB-PARAGRAPH INTENTIONALLY DELETED

LEASE NO. GS-03P-LMD00631, PAGE 18

LESSOR: KA GOVERNMENT:

3.29 FLOOR COVERING AND PERIMETERS—SHELL (WAREHOUSE) (MAY 2014)

A. Exposed interior floors in primary entrances and lobbies shall be marble, granite, ceramic tile or terrazzo. Exposed interior floors in secondary entrances, elevator lobbies, and primary interior corridors shall be high-grade carpet, marble, granite, or terrazzo. Resilient flooring shall be used in telecommunications rooms. Floor perimeters at partitions shall have wood, rubber, vinyl, marble, or carpet base.

- B. Terrazzo, unglazed ceramic tile, recycled glass tile, and/or quarry tile shall be used in all restroom and service areas of Government-occupied floors.
- C. Any alternate flooring must be pre-approved by the LCO
- D. The costs for cyclical carpet replacement requirements as outlined in Section 6 shall be included in the shell rent.

3.30 MECHANICAL, ELECTRICAL, PLUMBING: GENERAL (APR 2011)

The Lessor shall provide and operate all Building equipment and systems in accordance with applicable technical publications, manuals, and standard procedures. Mains, lines, and meters for utilities shall be provided by the Lessor. Exposed ducts, piping, and conduits are not permitted in the office Space.

3.31 BUILDING SYSTEMS (APR 2011)

Whenever requested, the Lessor shall furnish to GSA as part of shell rent, a report by a registered professional engineer(s) showing that the Building and its systems as designed and constructed will satisfy the requirements of this Lease.

3.32 ELECTRICAL—SHELL (WAREHOUSE) (MAY 2014)
(b) (5)

3.33 PARAGRAPH INTENTIONALLY DELETED

3.34 PLUMBING (JUN 2012)

The Lessor shall include the cost of plumbing in common areas. Hot and cold water risers and domestic waste and vent risers, installed and ready for connections that are required for Tis, shall be included in the shell rent.

3.35 PARAGRAPH INTENTIONALLY DELETED

3.36 RESTROOMS (WAREHOUSE) (OCT 2016)

A. For Warehouse Area, Lessor shall provide at its cost, restroom facilities which are handicap accessible, with an adequate number of fixtures for men and women to meet current local codes based on general warehousing use.

B. SUB-PARAGRAPH INTENTIONALLY DELETED

- C. If no new construction or major renovation of a restroom is occurring, compliance with local code is sufficient. Separate restroom facilities for men and women shall be provided in accordance with local code or ordinances, on each floor occupied by the Government in the Building. The facilities shall be located so that employees will not be required to travel more than 200 feet on one floor to reach the restrooms. Each restroom shall have sufficient water closets enclosed with modern stall partitions and doors, urinals (in men's room), and hot (set in accordance with applicable building codes) and cold water. Water closets and urinals shall not be visible when the exterior door is open.
- Each main restroom shall contain the following:
 - 1. A mirror and shelf above the lavatory.
 - 2. A toilet paper dispenser in each water closet stall that will hold at least two rolls and allow easy, unrestricted dispensing.
 - 3. A coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories.

LESSOR: BY- GOVERNMENT:

- 4. At least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories.
- 5. A coin-operated sanitary napkin dispenser in women's restrooms with a waste receptacle in each water closet stall.
- 6. A disposable toilet seat cover dispenser.
- 7. A counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground-fault interrupter-type convenience outlet located adjacent to the counter area. The counter should be installed to minimize pooling or spilling of water at the front edge.
- 8. A floor drain.
- 9. For new installations and major renovations, restroom partitions shall be made from recovered materials as listed in EPA's CPG.
- 10. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour. The exhaust fan systems shall be provided with a 24/7 seven day clock to allow programming.

3.37 PLUMBING FIXTURES: WATER CONSERVATION (OCT 2016)

The specifications listed under sub-paragraphs A through C apply for:

- 1. New installations of plumbing fixtures,
- 2. Replacement of existing plumbing fixtures, or
- 3. Existing non-conforming fixtures where the Government occupies the full floor.
- Water closets must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized.
- B. Urinals must conform to EPA WaterSense or fixtures with equivalent flush volumes must be utilized. Waterless urinals are acceptable.
- Faucets must conform to EPA WaterSense or fixtures with equivalent flow rates must be utilized.

Information on EPA WaterSense fixtures can be found at HTTPS://WWW3.EPA.GOV/WATERSENSE/.

3.38 PARAGRAPH INTENTIONALLY DELETED

3.39 HEATING AND VENTILATION—SHELL (WAREHOUSE) (OCT 2016)

- A. A 24/7 controlled room temperature of 68° 77° F is required during all seasons. "Controlled" allows for excursions of 59° 86°F and spikes to over 100°F for no more than 48 hour periods. These temperatures shall be maintained throughout the leased premises and service areas at all times, regardless of outside temperatures. At all times, humidity shall be maintained below 60% relative humidity. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the GSA Property Manager.
- B. Office Areas: Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all Building common areas. The Lessor shall provide conditioned air through medium pressure duct work at a rate of .75 cubic feet per minute per ABOA SF and systems shall be designed with sufficient systems capacity to meet all requirements in this Lease.
- C. Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.
- D. <u>Equipment Performance</u>. Temperature control for office Spaces shall be provided by concealed central heating and air conditioning equipment. The equipment shall maintain Space temperature control over a range of internal load fluctuations of plus 0.5 W/SF to minus 1.5 W/SF from initial design requirements of the tenant.
- E. <u>Ductwork Re-use and Cleaning</u>. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.
- F. During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the latest edition of the American National Standards Institute, American Society of Heating, Refrigeration and Air-Conditioning Engineers (ANSI/ASHRAE) Standard 62.1, Ventilation for Acceptable Indoor Air Quality.

(b) (5)

- H. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour.
- SUB-PARAGRAPH INTENTIONALLY DELETED
- J. Warehouse and Office areas: HVAC systems must conform to the locally approved building code.

LESSOR: BM GOVERNMENT:

(b) (5)	
2.44	THE CONTRACTOR OF THE PROPERTY ASSESSMENT OF THE CONTRACTOR OF THE
(b) (5)	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)
(b) (5)	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)
3.41 (b) (5)	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)
(b) (5)	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)
(b) (5)	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)
(b) (5)	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (JUN 2012)

3.42 LIGHTING: INTERIOR AND PARKING—SHELL (WAREHOUSE) (OCT 2016)

TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (SEP 2000)

Warehouse/Storage Space & Overall:

- A. Lessor shall provide a minimum lighting level of 10 foot-candles, as measured 30 inches above the floor, in aisles and open storage areas in the warehouse Space with the storage racks full. Lessor shall provide a minimum lighting level in the shipping and receiving areas of 30 foot-candles, when measured 30 inches above the floor. Lessor must provide lighting that is equivalent to the energy efficiency requirements in any office areas, Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all non-office areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided as part of Shell Rent in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs. Lessor shall not be responsible for lighting levels in the new expansion space since the Government approved the lighting installation prior to the finalization of the Government's racking plan.
- B. Occupancy Sensors: The Lessor shall provide ceiling mount occupancy sensors (over aisles and open areas), or scheduling controls through a building automation system (BAS) throughout the storage portion of the Space in order to reduce the hours that the lights are on when a particular area is unoccupied. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.
- C. Building Perimeter:
 - 1. Exterior parking areas, vehicle driveways, pedestrian walks, and the Building perimeter lighting levels, (especially at loading dock doors), shall be designed per Illuminating Engineering Society (IES) standards. Provide 5 foot-candles for doorway areas, 3 foot-candles for transition areas and at least 1 foot-candle at the surface throughout the parking lot. Parking lot fixtures shall provide a maximum to minimum uniformity ratio of 15:1 and a maximum to average uniformity ratio of 4:1. Sodium vapor lighting fixtures are prohibited.
 - 2. SUB-PARAGRAPH INTENTIONALLY DELETED
- D. SUB-PARAGRAPH INTENTIONALLY DELETED
- E. SUB-PARAGRAPH INTENTIONALLY DELETED

(b) (5)

G. Office Area Lighting Levels: Fixtures shall have a minimum of two tubes and shall provide 50 foot-candles at desktop level (30" above finished floor) with a maximum uniformity ratio of 1.5:1. Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all other Building areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs.

LESSOR: 10/18) GOVERNMENT: GSA FORM L201WH (10/18)

3.43 ACOUSTICAL REQUIREMENTS (JUN 2012)

A. <u>Reverberation Control</u>. Private office and conference rooms using suspended acoustical ceilings shall have a noise reduction coefficient (NRC) of not less than 0.65 in accordance with ASTM C-423. Open office using suspended acoustical ceilings shall have a NRC of not less than 0.75. Private offices, conference rooms, and open offices using acoustical cloud or acoustical wall panels with a minimum of 70% coverage shall have a NRC of not less than 0.85.

B. SUB PARAGRAPH INTENTIONALLY DELETED

C. <u>Noise Isolation</u>. Rooms separated from adjacent spaces by ceiling high partitions (not including doors) shall not be less than the following noise isolation class (NIC) standards when tested in accordance with ASTM E-336:

Conference rooms: NIC 40

Offices: NIC 35

- D. <u>Testing</u>. The LCO may require, at Lessor's expense, test reports by a qualified acoustical consultant showing that acoustical requirements have been met.
- 3.44 PARAGRAPH INTENTIONALLY DELETED
- 3.45 PARAGRAPH INTENTIONALLY DELETED
- 3.46 PARAGRAPH INTENTIONALLY DELETED
- 3.47 PARAGRAPH INTENTIONALLY DELETED
- 3.48 PARAGRAPH INTENTIONALLY DELETED

3.49 SYSTEMS COMMISSIONING (APR 2011)

The Lessor shall incorporate commissioning requirements to verify that the installation and performance of energy consuming systems meet the Government's project requirements. The commissioning shall cover only work associated with TIs or alterations or at a minimum: heating, ventilating, air conditioning and refrigeration (HVAC&R) systems and associated controls, lighting controls, and domestic hot water systems.

3.50 LOADING DOCKS-SHELL (WAREHOUSE) (MAY 2014)

- A. Lessor shall provide a minimum of ten (10) loading dock(s) for the exclusive use of the Government. The Lease Contracting Officer accepts existing thirty-nine (39) loading docks as configured.
- B. Lessor shall equip each dock with two molded rubber bumpers (at least 6 inches by 12 inches by 14 inches) and heavy-duty bump blocks (the dock must be fully protected with edge guards and dock bumpers). Lessor shall equip each dock with exterior dock seals to prevent the exchange of air from indoors to outdoors and vice versa when the trailer docked for loading or unloading. The entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.
- C. Dock-high doors shall be a minimum of 8' wide by 10' high and shall be approximately 48" above finished exterior grade unless otherwise specified in the Agency Special Requirements. Doors shall be insulated (R8 or better) with 2" angled, metal track and manual push-up. Door shall be spring loaded to assist opening and to safe return to the closed position. Weather-tight seals shall be provided around all 4 sides of the doors.
- D. Drive-in doors shall be a minimum of 12' wide by 14' high unless otherwise specified in the Agency Special Requirements. The slope of the ramp shall not exceed 9% or by local code, whichever is more stringent. Doors shall be insulated (R8 or better) with 2" angled, metal track with chain hoist for opening and closing. Weather-tight seals shall be provided around all 4 sides of the doors.
- E. Lessor shall equip two docks (Docks 2 and 19) with **hydraulic dock levelers**. If exterior to the building, the entire loading dock bay shall be enclosed unless otherwise specified by Lessee. Any open loading docks must be covered at least 1,200 mm (4 feet) beyond the edge of the loading dock platform over the loading berth. Lessor shall provide a means to reduce the infiltration of outside debris into the building at the entrances and exits at loading docks and service entrances.
- F. Lessor shall provide sufficient ventilation to remove carbon monoxide even when doors and windows are shut. Ventilation air intakes must be at least 25 feet away from loading docks, garage entries, and similar carbon monoxide contamination points. Docks shall be separated by at least 50 feet in any direction from utility rooms, utility mains, and service entrances, including electrical, telephone/data, fire detection/alarm systems, fire suppression water mains, cooling and heating mains, etc. All regular and emergency fuel storage locations shall be located away from loading docks.
- G. All dock wells shall be level throughout. Each dock shall have an **industrial steel warehouse & dock door** with lock. The loading dock area shall be nearly flat with a 1:50 slope for drainage. The minimum headroom in the loading berth and apron space is 4,600 mm (15 feet). When a steeper slope is required in the apron area, the headroom must increase with a gradient allowance to permit trucks to traverse the grade change.
- H. Lessor shall equip each loading dock with adjustable lights capable of illuminating the truck or van interior. Each dock shall have either a trailer lock or wheel chocks chained to the platforms. Where specified by Government on Exhibit B (Floor Plans), the Lessor shall provide a ramp from the loading dock down to the vehicle parking area to facilitate deliveries from small trucks and vans. This ramp must have a maximum 9% slope. Public and loading dock access must not be from the same point of access (at least one personnel door shall be provided in addition to overhead doors).
- I. Ten (10) docks to be determined by the Government shall provide shelter to people and materials in inclement weather. Operating controls for individual dock doors, dock levelers and lights shall be located on the interior wall adjacent to each dock door.

LESSOR: # GOVERNMENT:

LEASE NO. GS-03P-LMD00631, PAGE 22

- J. Service dock access may be from an alley, from a below grade ramp, or from a site circulation drive. Lessor shall provide sufficient space for an 18 wheeler truck to maneuver and service the facility, and also to screen the service drive as much as possible. The service drive must always be separated from access to the parking area. One-way design for service traffic is preferred in order to avoid the need for large turning areas. The service area of the facility must not interfere with public access roadways.
- K. SUBPARAGRAPH INTENTIONALLY DELETED
- L. Loading dock areas must be separated and visually screened (wherever practical) from the main public building entrance(s). Lessor shall provide an internal staging area adjacent to the loading dock. The staging area must not interfere with emergency egress from the building. Loading docks must have a direct route to freight elevators (if any) and be sized to accommodate the transport of supplies, equipment replacement parts, and building goods. If provided for, a dock manager's room must have visual control of the entire dock area as well as the building entrance and exit. Service circulation must be separated from public areas such as lobbies, corridors, and elevators. Loading dock stairs must be on the driver's left when backing into the dock. The grade of the apron must slope away from the loading dock and shall not exceed an 8.3% slope.
- M. SUB-PARAGRAPH INTENTIONALLY DELETED.
- 3.51 EMERGENCY POWER TO CRITICAL SYSTEMS (WAREHOUSE) (MAY 2014)

(b) (5)

3.52 MECHANICAL AREAS AND BUILDING ROOFS (WAREHOUSE) (MAY 2014)

Roof access shall meet the applicable egress requirements in the National Fire Protection Association (NFPA) 101, Life Safety Code or IBC (current as of the Award Date of this Lease).

- 3.53 PARAGRAPH INTENTIONALLY DELETED
- 3.54 PARAGRAPH INTENTIONALLY DELETED

LESSOR: Bh GOVERNMENT:

LEASE NO. GS-03P-LMD00631, PAGE 23

SECTION 4 DESIGN, CONSTRUCTION, AND POST AWARD ACTIVITIES

4.01 SCHEDULE FOR COMPLETION OF SPACE (WAREHOUSE) (OCT 2017)

Design and construction activities for the Space shall commence upon Lease award. The Lessor shall schedule the following activities to achieve timely completion of the work required by this Lease:

A. SUB-PARAPGRAPH INTENTIONALLY DELETED

- B. <u>Government-Provided Scope of Work</u>: The Government shall prepare and provide to the Lessor the Government's approved scope of work for tenant improvements required in existing space. The Government does not require any changes to the existing layout.
- C. The Lessor's preparation and submission of construction documents (CDs): If the Government's Scope of Work requires CDs, the Lessor as part of the TI must complete CDs not later than Thirty (30) Working Days following the submittal of the Government's scope of work. The pricing for this work is included under the A/E fees established under Section 1 of the Lease. If during the preparation of CDs the Lessor becomes aware that any material requirement indicated in the Government's scope of work cannot be reasonably achieved, the Lessor shall promptly notify GSA, and shall not proceed with completion of CDs until direction is received from the LCO. The LCO shall provide direction within ten (10) Working Days of such notice, but the Government shall not be responsible for delays to completion of CDs occasioned by such circumstances. For the purpose of this paragraph, a "material requirement" shall mean any requirement necessary for the Government's intended use of the Space as provided for in, or reasonably inferable from, the Lease and the approved DIDs (e.g., number of workstations and required adjacencies).
- D. <u>Government review of CDs</u>: The Government shall have fifteen (15) Working Days to review CDs before Lessor proceeds to prepare a TI price proposal for the work described in the CDs. At any time during this period of review, the Government shall have the right to require the Lessor to modify the CDs to enforce conformance to Lease requirements and the Government's scope of work.
- E. <u>The Lessor's preparation and submission of the TI price proposal</u>: The Lessor shall prepare and submit a complete TI price proposal in accordance with this Lease within twenty (20) Working Days following the end of the Government CD review period or submittal of Government scope of work if CDs are not required.

F. SUB-PARAGRAPH INTENTIONALLY DELETED

G. <u>Negotiation of TI price proposal and issuance of notice to proceed (NTP)</u>: The Government shall issue NTP following the submission of the TI price proposal, provided that the TI price proposal conforms to the requirements of the paragraph titled "Tenant Improvements Price Proposal" and the parties negotiate a fair and reasonable price for TIs.

H. SUB-PARAGRAPH INTENTIONALLY DELETED

I. <u>Construction of Tis and completion of other required construction work</u>: The Lessor shall complete all work required to prepare the Premises as required in this Lease ready for use not later than seventy-five (75) Working Days following issuance of NTP.

4.02 CONSTRUCTION DOCUMENTS (SEP 2012)

The Lessor's CDs shall include all mechanical, electrical, plumbing, fire protection, life safety, lighting, structural, security, and architectural improvements scheduled for inclusion into the Space. CDs shall be annotated with all applicable specifications. CDs shall also clearly identify TIs already in place and the work to be done by the Lessor or others. Notwithstanding the Government's review of the CDs, the Lessor is solely responsible and liable for their technical accuracy and compliance with all applicable Lease requirements.

4.03 TENANT IMPROVEMENTS PRICE PROPOSAL (SEP 2013)

The Lessor's TI price proposal shall be supported by sufficient cost or pricing data to enable the Government to evaluate the reasonableness of the proposal, or documentation that the Proposal is based upon competitive proposals (as described in the "Tenant Improvements Pricing Requirements" paragraph) obtained from entities not affiliated with the Lessor. Any work shown on the CDs that is required to be included in the Bullding shell rent or already priced as BSAC shall be clearly identified and excluded from the TI price proposal. After negotiation and acceptance of the TI price, GSA shall issue a NTP to the Lessor.

4.04 BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC) PRICE PROPOSAL (SEP 2012) INTENTIONALLY DELETED

4.05 TENANT IMPROVEMENTS PRICING REQUIREMENTS (SEP 2013)

- A. Under the provisions of FAR Subpart 15.4, the Lessor shall submit a TI price proposal with information that is adequate for the Government to evaluate the reasonableness of the price or determining cost realism for the TIs within the time frame specified in this section. The TI price proposal shall use the fee rates specified in the "Tenant Improvement Fee Schedule" paragraph of this Lease. The Lessor shall exclude from the TI price proposal all costs for fixtures and/or other TIs already in place, provided the Government has accepted same. However, the Lessor will be reimbursed for costs to repair or improve the fixture(s) and/or any other improvements already in place. The Lessor must provide certified cost or pricing data for TI proposals exceeding the threshold in FAR 15.403-4, to establish a fair and reasonable price. For TI proposals that do not exceed the threshold in FAR 15-403-4, the Lessor shall submit adequate documentation to support the reasonableness of the price proposal as determined by the LCO.
- B. The TIs scope of work includes the Lease, the DIDs, the CDs, and written specifications. In cases of discrepancies, the Lessor shall immediately notify the LCO for resolution. All differences will be resolved by the LCO in accordance with the terms and conditions of the Lease.

LESSOR: 152 GOVERNMENT.

- C. In lieu of requiring the submission of detailed cost or pricing data as described above, the Government (in accordance with FAR 15.403) is willing to negotiate a price based upon the results of a competitive proposal process. A minimum of two qualified General Contractors (GCs) shall be invited by the Lessor to participate in the competitive proposal process. Each participant shall compete independently in the process. In the absence of sufficient competition from the GCs, a minimum of two qualified subcontractors from each trade of the Tenant Improvement Cost Summary (TICS) Table (described below) shall be invited to participate in the competitive proposal process.
- D. Each TI proposal shall be (1) submitted by the proposed General Contractors (or subcontractors) using the TICS Table in CSI MasterFormat; (2) reviewed by the Lessor prior to submission to the Government to ensure compliance with the scope of work (specified above) and the proper allocation of shell and TI costs; and (3) reviewed by the Government. General Contractors shall submit the supporting bids from the major subcontractors along with additional backup to the TICS Table in a format acceptable to the Government. Backup will follow the TICS table MasterFormat cost elements and be to level 5 as described in P-120, Project Estimating Requirements for the Public Buildings Service.
- E. Unless specifically designated in this Lease as a TI or BSAC cost, all construction costs shall be deemed to be included in the Shell Rent. Any costs in the GC's proposal for Building shell items shall be clearly identified on the TICS Table separately from the TI costs.
- F. The Government reserves the right to determine if bids meet the scope of work, that the price is reasonable, and that the Lessor's proposed contractors are qualified to perform the work. The Government reserves the right to reject all bids at its sole discretion. The Government reserves the right to attend or be represented at all negotiation sessions between the Lessor and potential contractors.
- G. The Lessor shall demonstrate to the Government that best efforts have been made to obtain the most competitive prices possible, and the Lessor shall accept responsibility for all prices through direct contracts with all contractors. The LCO shall issue to the Lessor a NTP with the TIs upon the Government's sole determination that the Lessor's proposal is acceptable. The Lessor shall complete the work within the time frame specified in this section of the Lease.

4.06 GREEN LEASE SUBMITTALS (WAREHOUSE) (OCT 2018)

The Lessor shall submit to the LCO:

- A. Product data sheets for floor coverings, paints and wall coverings, ceiling materials, all adhesives, wood products, suite and interior doors, subdividing partitions, walf base, door hardware finishes, window coverings, millwork substrate and millwork finishes, lighting and lighting controls, and insulation to be used within the leased Space. This information must be submitted NO LATER THAN the submission of the DIDs.
- B. SDS or other appropriate documents upon request for products listed in the Lease. All SDS shall comply with Occupational Safety and Health Administration (OSHA) requirements for the Globally Harmonized System of Classification and Labeling of Chemicals (GHS). The Lessor and its agents shall comply with all recommended measures in the SDS to protect the health and safety of personnel.
- C. Re-use plan required in accordance with the "Existing Fit-out, Salvaged, or Re-used Building Material" paragraph in the Lease.
- D. Any waiver needed when not using materials from the Green Procurement Compilation list of acceptable products in accordance with the "Environmentally Preferable Product Requirements" paragraph in the Lease.
- E. Radon test results as may be required by the "Radon in Air" and "Radon in Water" paragraphs in the Lease.
- F. <u>Construction waste management plan</u>: Prior to construction commencement, a proposed plan following industry standards to recycle construction waste. The construction waste management plan shall quantify material diversion goals and maximize the materials to be recycled and/or salvaged (at least 50 percent) from construction, demolition, and packaging debris. Where the small quantity of material, the extraordinarily complex nature of the waste disposal method, or prohibitive expense for recycling would represent a genuine hardship, the Government, upon written request of the Lessor and approval of the LCO, may permit alternative means of disposal.
- G. <u>Building recycling service plan</u>: A Building recycling service plan with floor plans annotating recycling area(s) as part of DIDs to be reflected on the CD submission.
- H. A signed statement from the Lessor for the leased Space explaining how all HVAC systems serving the leased Space will achieve the desired ventilation of the Space during the flush-out period called for in the Lease.
- 1. A written commissioning plan submitted to the LCO prior to the completion of DIDs that includes:
 - A schedule of systems commissioning (revised as needed during all construction phases of the project, with such revisions provided to the LCO immediately); and
 - 2. A description of how commissioning requirements will be met and confirmed.
- J. If renewable source power is purchased, documentation within 9 months of occupancy.

4.07 CONSTRUCTION SCHEDULE AND INITIAL CONSTRUCTION MEETING (APR 2011)

The Lessor shall furnish a detailed construction schedule (such as Critical Path Method) to the Government within ten (10) Working Days of issuance of the NTP. Such schedule shall also indicate the dates available for Government contractors to install telephone/data lines or equipment, if needed. Within five (5) Working Days of NTP, the Lessor shall initiate a construction meeting. The Lessor will have contractor representatives including its architects, engineers, general contractor and sub-contractor representatives in attendance. The Lessor shall keep meeting minutes of discussion topics and attendance.

LESSOR: 18 GOVERNMENT:

4.08 PROGRESS REPORTS (JUN 2012)

After start of construction, the Lessor shall submit to the LCO written progress reports at intervals of ten (10) Working Days. Each report shall include information as to the percentage of the work completed by phase and trade; a statement as to expected completion and occupancy dates; changes introduced into the work; and general remarks on such items as material shortages, strikes, weather, etc., that may affect timely completion. In addition, at the Government's discretion, the Lessor shall conduct meetings every two weeks to brief Government personnel and/or contractors regarding the progress of design and construction of the Space. The Lessor shall be responsible for taking and distributing minutes of these meetings.

4.09 ACCESS BY THE GOVERNMENT PRIOR TO ACCEPTANCE (SEP 2013)

The Government shall have the right to access any space within the Building during construction for the purposes of performing inspections or installing Government furnished equipment. The Government shall coordinate the activity of Government contractors with the Lessor to minimize conflicts with and disruption to other contractors on site. Access shall not be unreasonably denied to authorized Government officials including, but not limited to, Government contractors, subcontractors, or consultants acting on behalf of the Government on this project.

4.10 CONSTRUCTION INSPECTIONS (APR 2011)

- A. The LCO or the LCO's designated technical representative may periodically inspect construction work to review compliance with Lease requirements and approved DIDs.
- B. Periodic reviews, witnessing of tests, and inspections by the Government shall not constitute approval of the Lessor's apparent progress toward meeting the Government's objectives but are intended to discover any information which the LCO may be able to call to the Lessor's attention to prevent costly misdirection of effort. The Lessor shall remain responsible for designing, constructing, operating, and maintaining the Building in full accordance with the requirements of the Lease.

4.11 ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (MAY 2015)

- A. Ten (10) Working Days prior to the completion of the Space, the Lessor shall issue written notice to the Government to schedule the inspection of the Space for acceptance. The Government shall accept the Space only if the construction of Building shell and TIs conforming to this Lease and the approved DIDs is substantially complete, a Certificate of Occupancy (C of O) has been issued as set forth below, and the Building improvements necessary for acceptance as described in the paragraph "Building Improvements" are completed.
- B. The Space shall be considered substantially complete only if the Space may be used for its intended purpose, and completion of remaining work will not interfere unreasonably with the Government's enjoyment of the Space. Acceptance shall be final and binding upon the Government with respect to conformance of the completed TIs to the approved DIDs, with the exception of items identified on a punch list generated as a result of the inspection, concealed conditions, latent defects, or fraud, but shall not relieve the Lessor of any other Lease requirements.
- C. The Lessor shall provide a valid C of O, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue C of O's or if the C of O is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease.
- D. The Government will not be required to accept space prior to the schedule outlined in this Lease.

4.12 LEASE TERM COMMENCEMENT DATE AND RENT RECONCILIATION (JUN 2012)

At acceptance, the Space shall be measured in accordance with the standards set forth in this Lease to determine the total ABOA SF in the Space. The rent for the Space will be adjusted based upon the measured ABOA square footage as outlined under the Payment clause of the General Clauses. At acceptance, the Lease term shall commence. The Lease Term Commencement Date, final measurement of the Premises, reconciliation of the annual rent, and amount of Commission Credit, if any, shall be memorialized by Lease Amendment.

4.13 AS-BUILT DRAWINGS (OCT 2017)

Not later than thirty (30) days after the acceptance of the Space, the Lessor, at Lessor's expense, shall furnish to the Government a complete set of Computer Aided Design (CAD) files of as-built floor plans showing the Space under Lease, as well as corridors, stairways, and core areas. The plans shall have been generated by a CAD program which is compatible with the latest release of AutoCAD. The required file extension is ".DWG." Clean and purged files shall be submitted in a digital format. They shall be labeled with Building name, address, list of drawing(s), date of the drawing(s), and Lessor's architect and architect's phone number. The Lessor's operator shall demonstrate the submission on GSA equipment, if requested by the LCO.

4.14 PARAGRAPH INTENTIONALLY DELETED

4.15 PARAGRAPH INTENTIONALLY DELETED

4.16 LESSOR'S PROJECT MANAGEMENT FEE (SEP 2013)

A. The Lessor's project management fee shall cover all of the Lessor's project management costs associated with the delivery of Tenant Improvements, including, but not limited to:

- 1. Legal fees
- 2. Travel costs
- 3. Insurance
- 4. Home office overhead and other indirect costs

LESSOR: 17/1 GOVERNMENT:

- 5. Carrying costs, exclusive of the TI amortization rate. Carrying costs are those costs of capital incurred for the delivery of TI, for the period starting from Lessor's outlay of funds, until the Lease Term Commencement Date.
- 6. Municipal, county, or state fees (not related to sales tax)
- 7. TI proposal preparation costs
- 8. Lessor's labor costs related to the management of the TI build-out.
- B. At a minimum, the Lessor shall be responsible for performing the following services in order to receive the project management fee:
 - 1. Provide assistance and expertise to the Government project team in the form of coordination, management, and administration of the design and construction process;
 - 2. Monitor performance of the general contractor and other contractors, control schedules, and oversee financial accounts;
 - 3. Conduct and document design and construction project meetings;
 - Perform administrative tasks, including documentation, record keeping (issuing meeting minutes), and payment validation in addition to submittal and change order processing;
 - 5. Maintain Request for Information (RFI), submittal, and change order logs; and
 - Provide technical expertise (e.g. testing, estimating, resolving claims, or responding to inquiries).

LESSOR: A GOVERNMENT:

SECTION 5 TENANT IMPROVEMENT COMPONENTS

5.01 TENANT IMPROVEMENT REQUIREMENTS (OCT 2016)

The TIs shall be designed, constructed, and maintained in accordance with the standards set forth in this Lease. For pricing, only those requirements designated within this Section 5, or designated as TIs within the attached agency requirements, shall be deemed to be TI costs.

5.02 PARAGRAPH INTENTIONALLY DELETED

5.03 WINDOW COVERINGS (WAREHOUSE) (JUN 2012)

A. <u>Window Blinds</u>. All exterior windows shall be equipped with window blinds in new or like new condition, which shall be provided as part of the Tls. The blinds may be aluminum or plastic vertical blinds, horizontal blinds with aluminum slats of one-inch width or less, solar fabric rotter shades, or an equivalent product pre-approved by the Government. The window blinds shall have non-corroding mechanisms and synthetic tapes. Color selection will be made by the Government,

B. SUB-PARAGRAPH INTENTIONALLY DELETED

5.04 DOORS: SUITE ENTRY (SEP 2013)

Suite entry doors shall be provided as part of the TIs and shall have a minimum clear opening of 32" wide x 84" high (per leaf). Doors shall meet the requirements of being a flush, solid core, 1-3/4-inch thick, wood door with a natural wood veneer face or an equivalent pre-approved by the Government. Hollow core wood doors are not acceptable. They shall be operable by a single effort; and shall meet the requirement of NFPA 101, Life Safety Code or the International Building Code (current as of the Lease Award Date). Doors shall be installed in a metal frame assembly which is primed and finished with a low VOC semigloss oil-based paint finish with no formaldehyde.

5.05 DOORS: INTERIOR (SEP 2013)

	751
\cup	(U)

5.06 DOORS: HARDWARE (SEP 2013)

(h	(5)
ľ	(U)

5.07 DOORS: IDENTIFICATION (JUN 2012)

Door identification shall be installed in approved locations adjacent to office entrances as part of the TIs. The form of door identification shall be approved by the Government.

5.08 PARTITIONS: SUBDIVIDING (SEP 2015)

- A. Office subdividing partitions shall comply with applicable building codes and local requirements and ordinances and shall be provided as part of the TIs. Partitioning shall extend from the finished floor to the finished ceiling and shall be designed to provide a minimum sound transmission class (STC) of 37. Partitioning shall be installed by the Lessor at locations to be determined by the Government as identified in the DIDs. They shall have a flame spread rating of 25 or less and a smoke development rating of 450 or less (ASTM E-84).
- B. HVAC shall be rebalanced and lighting repositioned, as appropriate, after installation of partitions.
- C. If installed in accordance with the "Automatic Fire Sprinkler System" and "Fire Alarm System" paragraphs, sprinklers and fire alarm notification appliances shall be repositioned as appropriate after installation of partitions to maintain the level of fire protection and life safety.
- D. Partitioning requirements may be satisfied with existing partitions if they meet the Government's standards and layout requirements.
- E. Newly installed gypsum board material must be Greenguard Gold Certified or have 0 grams per liter of VOCs.

5.09 CEILINGS-TI (WAREHOUSE) (OCT 2017)

Government designated office and related areas shall contain a complete acoustical ceiling system (such a ceiling system include grid and lay-in tiles or other Building standard ceiling system as approved by the LCO).

A. Ceilings in office and related areas shall be at a minimum 9 feet and 0 inches and no more than 12 feet and 0 inches measured from floor to the lowest obstruction. Areas with raised flooring shall maintain these ceiling-height limitations above the finished raised flooring. Bulkheads and hanging or surface mounted light fixtures which impede traffic ways shall be avoided. Ceilings shall be uniform in color and appearance throughout the Space, with no obvious damage to tiles or grid.

LESSOR: BY GOVERNMENT

- B. Prior to closing the ceiling, Lessor shall coordinate with the Government for the installation of any items above the ceiling.
- C. Should the ceiling be installed in the Space prior to construction of the TI, then Lessor shall be responsible for all costs for the disassembly, storage during construction, and subsequent re-assembly of ceiling components which may be required to complete the TI. Lessor shall also bear the risk for any damage to the ceiling or any components thereof during the construction of the TI.
- D. Ceilings shall be a flat plane in each room and shall be suspended and finished as follows unless an alternate equivalent is pre-approved by the LCO:
 - 1. Restrooms. Plastered or spackled and taped gypsum board.
 - 2. Offices and conference rooms. Mineral and acoustical tile or lay in panels with textured or patterned surface and tegular edges or an equivalent pre-approved by the LCO. Newly installed tiles or panels shall meet at least one of the environmentally preferable criteria as outlined under the Green Procurement Compilation at https://sftool.gov/green/procurement/.
 - 3. Corridors and eating/galley areas. Plastered or spackled and taped gypsum board or mineral acoustical tile.

E. SUB-PARAGRAPH INTENTIONALLY DELETED

5.10 WALL FINISHES (JUN 2012)

If the Government chooses to install a wall covering, the minimum standard is vinyl-free, chlorine-free, plasticizer-free wall covering with recycled content or bio-based commercial wall covering weighing not less than 13 ounces per square yard or equivalent. If the Government chooses to install a high-performance paint coating, it shall comply with the VOC limits of the Green Seal Standard GS-11.

5.11 PAINTING—TI (OCT 2017)

- A. Prior to acceptance, all surfaces within the Space which are designated by GSA for painting shall be newly finished in colors acceptable to the Government.
- B. The Lessor shall provide interior paints, primers, coatings, stains, and sealers that meet or are equivalent to the Green Seal GS-11 standard that incorporates environmental, health, and performance criteria.
- C. The Lessor shall use reprocessed latex paint in accordance with EPA's CPG (Comprehensive Procurement Guidelines) on all painted surfaces where feasible. The type of paint shall be acceptable to the Government.

5.12 FLOOR COVERINGS AND PERIMETERS—TI (WAREHOUSE) (OCT 2017)

- A. Carpet tiles meeting the requirements set forth in the specifications below shall be installed in all office areas unless otherwise waived by the Contracting Officer. Office area floor perimeters at partitions shall have wood, rubber, vinyl, or carpet base. Floor covering shall be installed in accordance with manufacturing instructions to lay smoothly and evenly.
- B. Existing warehouse flooring is approved in its current condition.
- C. Any alternate flooring shall be pre-approved by the Government.
- D. SPECIFICATIONS FOR CARPET TO BE NEWLY INSTALLED OR REPLACED
 - 1. <u>Product sustainability and environmental requirements.</u> Floor covering and perimeter products must meet at least one of the environmentally preferable criteria within the non-federal, multi-attribute standards and ecolabels categories, as outlined under the Green Procurement Compilation at <u>WWW.SFTOOL.GOV/GREENPROCUREMENT</u>.
 - 2. <u>Face fiber content</u>. Face yarn must be 100 percent nylon fiber. Loop Pile shall be 100 percent Bulk Continuous Filament (BCF); cut and loop shall be 100 percent BCF for the loop portion and may be BCF or staple for the cut portion; cut pile carpet shall be staple or BCF.
 - 3. Performance requirements for broadloom and modular tile:
 - a. Static: Less than or equal to 3.5 kV when tested by AATCC Test Method 134 (Step Test Option).

b. Flammability: Meets CPSC-FF-1-70, DOC-FF-1-70 Methenamine Tablet Test criteria.

- c. Flooring Radiant Panel Test: Meets NFPA 253 Class I or II depending upon occupancy and fire code when tested under ASTM E-648 for glue down installation.
- d. Smoke Density: NBS Smoke Chamber—Less than 450 Flaming Mode when tested under ASTM E-662.

NOTE: Testing must be performed in a NVLAP accredited laboratory.

- 4. <u>Texture Appearance Retention Rating (TARR)</u>. Carpet must meet TARR rating of at least 3.0 TARR for moderate traffic areas such as private offices, and heavy traffic areas such as training space, conference rooms, courtrooms, etc., and at least 3.5 TARR for severe traffic areas, including open office space, cafeteria, corridors and lobbies. The carpet must be evaluated using ASTM D-5252 Hexapod Drum Test as per the commercial carpet test procedure and the TARR classification determined using ASTM D-7330.
- 5. <u>Carpet reclamation.</u> Reclamation of existing carpet to be determined with potential vendor. When carpet is replaced, submit certification documentation from the reclamation facility to the LCO.

LESSOR: 15:1- GOVERNMENT:

LEASE NO. GS-03P-LMD00631, PAGE 29

6. <u>Warranty</u>. Submit a copy of the manufacturer's standard warranty to the LCO within the first 60 days of Government occupancy. The Government is to be a beneficiary of the terms of this warranty.

5.13 HEATING AND AIR CONDITIONING—TI (WAREHOUSE) (MAY 2014)

Zone Control. Provide individual thermostat control for office Space with control areas not to exceed 1,500 ABOA SF. Interior spaces must be separately zoned. Specialty occupancies (conference rooms, kitchens, etc.) must have active controls capable of sensing Space use and modulating HVAC system in response to Space demand. Areas that routinely have extended hours of operation shall be environmentally controlled through dedicated heating and air conditioning equipment. Special purpose areas (such as photocopy centers, large conference rooms, computer rooms, etc.) with an internal cooling load in excess of 5 tons shall be independently controlled. Provide concealed package air conditioning equipment to meet localized spot cooling of tenant special equipment. Portable space heaters are prohibited.

(b) (5)	FI FCTRICAL* DISTRIBUTION TO AWAREHOUSE (MAY 2014)
(3) (3)	
5,15	TELECOMMUNICATIONS: DISTRIBUTION AND EQUIPMENT (JUN 2012)
(b) (5)	
5.16	TELECOMMUNICATIONS: LOCAL EXCHANGE ACCESS (AUG 2008)
(b) (5)	
5.17	DATA DISTRIBUTION (JUN 2012)
(b) (5)	
(D) (J)	
5.40	PLECTRICAL TELEPRIANE DATA FOR OVERTING PURNITURE (111) 6440
5.18	ELECTRICAL, TELEPHONE, DATA FOR SYSTEMS FURNITURE (JUN 2012)
(b) (5)	
(b) (5)	

LEASE NO. GS-03P-LMD00631, PAGE 30

LESSOR: K GOVERNMENT:

5.19 LIGHTING: INTERIOR AND PARKING—TI (WAREHOUSE) (MAY 2014)

WAREHOUSE AREAS:

- A. FIXTURES: Once the design intent drawings are approved, the Lessor shall design and provide interior lighting to comply with requirements under the paragraph, "Lighting: Interior and Parking—Shell." Any additional lighting fixtures and/or components required beyond what would have been provided for an open warehouse 10 foot candle plan plus shipping & receiving areas of 30 foot candles (Shell) are part of the TIs.
- B. Lighting for the warehouse, shipping, and receiving portions of the Space is detailed in Section 3 and is part of Shell.
- C. BUILDING PERIMETER: There may be additional requirements for lighting in exterior parking areas, vehicle driveways, pedestrian walkways, and Building perimeter in the Security Requirements attached to this Lease. Such additional lighting required to meet Security Requirements shall be BSAC.

OFFICE AREAS:

NOTE: FOR PRICING ESTIMATING PURPOSES, FIXTURES IN OFFICE AREAS WILL BE INSTALLED AT THE AVERAGE RATIO OF 1 FIXTURE PER 80 ABOA SF.

- A. FIXTURES: High efficiency T-8, T-5, or LED light fixtures (and associated ballasts or drivers) shall be installed as either ceiling grid or pendant mounted for an open-office plan. Ceiling grid fixtures shall be either 2' wide by 4' long or 2' wide by 2' long. Lessor shall provide a minimum overall lighting fixture efficiency of 85 percent. Lamps shall maintain a uniform color level throughout the lease term.
- B. LIGHTING LEVELS: Fixtures shall have a minimum of two tubes and shall provide 50 foot-candles at desktop level (30" above finished floor) with a maximum uniformity ratio of 1.5:1.
- C. POWER DENSITY:

Existing Buildings: The maximum fixture power density shall not exceed 1.4 watts per ABOA SF.

New Construction: The maximum fixture power density shall not exceed 1.1 watts per ABOA SF.

- D. DAYLIGHTING CONTROLS: If the office portion of the Space is more than 10,000 ABOA SF, the Lessor shall provide daylight dimming controls in atriums or within 15 feet of windows and skylights where daylight can contribute to energy savings. Daylight harvesting sensing and controls shall be either integral to the fixtures or ceiling mounted and shall maintain required lighting levels in office work areas.
- E. OCCUPANCY/VACANCY SENSORS: The Lessor shall provide ceiling mount occupancy sensors, or vacancy sensors (preferred), or scheduling controls through a building automation system (BAS) throughout the office portion of the Space in order to reduce the hours that the lights are on when a particular space is unoccupied. Occupancy sensors only shall be installed in the non-office areas of the Space as part of Shell Rent. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

5.20 LOADING DOCKS-TI (WAREHOUSE) (MAY 2014)

The Government may require hydraulic dock levelers or loading ramps for any warehouse dock (other than drive thrus) not already having dock high loading docks.

5.21 AUTOMATIC FIRE SPRINKLER SYSTEM - TL/OCT 2016)

(b) (5)

MENT:

LEASE NO. GS-03P-LMD00631, PAGE 31

LESSOR: MA GOVERNMENT:

SECTION 6 UTILITIES, SERVICES, AND OBLIGATIONS DURING THE LEASE TERM

6.01 PROVISION OF SERVICES, ACCESS, AND NORMAL HOURS (WAREHOUSE) (MAY 2014)

- A. The Government's normal hours of operations are established as **7:00** AM to **6:00** PM, Monday through Friday, with the exception of Federal holidays. Services, maintenance, and utilities shall be provided during these hours. The Government shall have access to the Premises and its Appurtenant Areas at all times without additional payment, including the use, during other than normal hours, of necessary services and utilities such as elevators, restrooms, lights, and electric power.
- B. The Lessor and the Lessor's representatives, employees and contractors shall demonstrate a cooperative, positive, welcoming, respectful, professional and business-like demeanor and shall present a neat, clean, job-appropriate (professional) appearance.

6.02 UTILITIES (APR 2011)

The Lessor is responsible for providing all utilities necessary for base Building and tenant operations as part of the rental consideration.

6.02 PARAGRAPH INTENTIONALLY DELETED

6.03 UTILITY CONSUMPTION REPORTING (OCT 2016)

Upon the effective date of the Lease, only for leases over 10,000 RSF, the Lessor shall provide regular quarterly reports for the amount of utilities (including water) consumed at the Building broken down by utility type per month for the duration of the Lease. Lessors shall report this utility consumption data within 45 calendar days of the end of each calendar quarter in the Environmental Protection Agency (EPA) Portfolio Manager online tool https://www.energystar.gov/. Data reported includes, but is not limited to, the number of actual units consumed, by utility type per month, and associated start and end date(s) for that consumption.

(Refer to the following link for reporting guidance: www.gsa.gov/ucr)

6.04 HEATING AND AIR CONDITIONING (WAREHOUSE) (OCT 2018)

- A. In all office areas, thermostats shall be set to maintain temperatures between 70°F and 74°F during the heating season and between 74°F and 78°F during the cooling season.. These temperatures shall be maintained throughout the leased Premises and service areas, regardless of outside temperatures, during the hours of operation specified in the Lease. The Lessor shall perform any necessary systems start-up required to meet the commercially equivalent temperature levels prior to the first hour of each day's operation. At all times, humidity shall be maintained below 60% relative humidity.
- B. In all office areas, during non working hours, heating temperatures shall be set no higher than 55° Fahrenheit, and air conditioning shall not be provided except as necessary to return Space temperatures to a suitable level for the beginning of working hours. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative.
- C. In all office areas, thermal comfort. During all working hours, comply with the latest edition of ASHRAE Standard 55, Thermal Comfort Conditions for Human Occupancy.
- D. Warehouse or garage areas require a controlled room temperature of 68° 77°F during all seasons, USP Controlled Room Temperature*. These temperatures shall be maintained through the leased premises and service areas at all times, regardless of outside temperatures. At all time, humidity shall be maintained below 60% relative humidity. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the GSA Property Manager or other designated Government official. The difference in cost between this requirement and that noted in Shell Paragraph 1.2 Shell HVAC above, is considered the tenant improvement portion of HVAC.
- *For the shipping and storage of pharmaceuticals, the United States Pharmacopeia-National Formulary (USP-NF) defines controlled room temperature as between 20 to 25 °C (68 to 77 °F), with excursions between 15 to 30 °C (59 to 86 °F) allowed, provided the mean kinetic temperature does not exceed 25 °C (77 °F).
- E. The Lessor shall conduct HVAC system balancing after any HVAC system alterations during the term of the Lease and shall make a reasonable attempt to schedule major construction outside of office hours.
- F. Normal HVAC systems' maintenance shall not disrupt tenant operations.

(b) (5)

- H. SUB-PARAGRAPH INTENTIONALLY DELETED
- I. SUB-PARAGRAPH INTENTIONALLY DELETED
- 6.05 OVERTIME HVAC USAGE (OCT 2018)
- A. If there is to be a charge for heating or cooling outside of the Building's normal hours, such services shall be provided at the hourly rates set forth elsewhere in the Lease. Overtime usage services may be ordered by the Government's authorized representative only.

LESSOR: BR GOVERNMENT

- B. When the cost of service is \$3,500 or less, the service may be ordered orally. An invoice shall be submitted to the official placing the order for certification and payment. Orders for services costing more than \$3,500 shall be placed using GSA Form 300, Order for Supplies or Services, or other approved service requisition procurement document. An invoice conforming to the requirements of this Lease shall be submitted to the official placing the order for certification and payment.
- C. Failure to submit a proper invoice within 120 days of providing overtime utilities shall constitute a waiver of the Lessor's right to receive any payment for such overtime utilities pursuant to this Lease.

6.06 JANITORIAL SERVICES (WAREHOUSE) (MAY 2014)

The Government will be responsible for janitorial service for the interior Government Premises, inclusive of the restrooms. It is the Lessor's responsibility to maintain and clean the exterior and the common areas of the building. The Government will remove the trash from the Building; however, the Lessor is responsible for removing the trash from the dumpster.

- A. <u>Daily</u>. Police sidewalks, parking areas, and driveways.
- B. Weekly. Sweep sidewalks, parking areas, and driveways (weather permitting).
- C. Twice a year. Wash all exterior windows and other glass surfaces.
- D. Annually. Clean balconies, ledges, courts, areaways, and flat roofs.
- E. <u>As required</u>. Properly maintain plants and lawns. Provide initial supply, installation, and replacement of light bulbs, tubes, ballasts, and starters. Provide and empty exterior ash cans and clean area of any discarded cigarette butts.
- F. <u>Pest control</u>. Control pests as appropriate, using Integrated Pest Management techniques, as specified in the GSA Environmental Management Integrated Pest Management Technique Guide (E402-1001).
- 6.07 PARAGRAPH INTENTIONALLY DELETED
- 6.08 PARAGRAPH INTENTIONALLY DELETED

6.09 SNOW REMOVAL (WAREHOUSE) (MAY 2014)

Lessor shall provide snow removal services for the Government on all days for which this Lease has designated normal hours. Lessor shall clear parking lots if the accumulation of snow exceeds two inches. Lessor shall clear sidewalks, walkways, loading docks, dock ramps, and entrances before accumulation exceeds 1.5 inches. The snow removal shall take place no later than 5:00 AM, without exception. Should accumulation continue throughout the day, the Lessor shall provide such additional snow removal services to prevent accumulation greater than the maximums specified in this paragraph. In addition to snow removal, the Lessor shall keep sidewalks, walkways, loading docks, dock ramps, and entrances free of ice during the normal hours. The Lessor shall remove excess buildup of sand and/or ice melt to minimize slipping hazards. If the Building entrance(s) has a northern exposure, then Lessor shall take additional measures to protect the safety of pedestrians.

6.10 MAINTENANCE AND TESTING OF SYSTEMS—WAREHOUSE (MAY 2014)

A. The Lessor is responsible for the total maintenance, repair and replacement of the leased Premises, the Building, and the Property. Such maintenance, repairs and replacements include the site and private access roads, and all necessary repairs and replacements to the loading docks, ramps, levelers and all other associated equipment and features. All equipment and systems shall be maintained, repaired, and replaced to provide reliable, energy efficient service without unusual interruption, disturbing noises, exposure to fire or safety hazards, uncomfortable drafts, excessive air velocities, or unusual emissions of dirt. The Lessor's maintenance responsibility includes initial supply and replacement of all supplies, materials, and equipment necessary for such maintenance. Maintenance, testing, and inspection of appropriate equipment and systems shall be done in accordance with current applicable codes, and inspection certificates shall be displayed as appropriate. Copies of all records in this regard shall be forwarded to the Government's designated representative.

B. At the Lessor's expense, the Government reserves the right to require documentation of proper operations or testing inspection, testing, and maintenance of fire protection systems, such as fire alarm, fire sprinkler, standpipes, fire pump, emergency lighting, illuminated exit signs, emergency generator, prior to occupancy to ensure proper operation. These tests shall be witnessed by the Government's designated representative.

6.11 MAINTENANCE OF PROVIDED FINISHES (WAREHOUSE) (OCT 2016)

A. <u>Paint, wall coverings</u>. Lessor shall maintain all wall coverings and high performance paint coatings in "like new" condition for the life of the Lease. All painted surfaces shall be repainted at the Lessor's expense, including the moving and returning of furnishings, any time during the occupancy by the Government if the paint is peeling or permanently stained, except where damaged due to the negligence of the Government. All work shall be done after normal working hours as defined elsewhere in this Lease. In addition to the foregoing requirement,

- Lessor shall repaint common areas at least every three years.
- 2. SUB-PARAGRAPH INTENTIONALLY DELETED
- 3. SUB-PARAGRAPH INTENTIONALLY DELETED
- B. Carpet and flooring.
 - 1. Except when damaged by the Government, the Lessor shall repair or replace flooring at any time during the Lease term when:

LESSOR: Br GOVERNMENT:

- a. Backing or underlayment is exposed;
- b. There are noticeable variations in surface color or texture;
- It has curls, upturned edges, or other noticeable variations in texture;
- d. Tiles are loose; or,
- Tears or tripping hazards are present.

2. SUB-PARAGRAPH INTENTIONALLY DELETED

- Repair or replacement shall include the moving and returning of furnishings, including disassembly and reassembly of systems furniture per manufacturer's warranty, if necessary. Work shall be performed after the normal hours established elsewhere in this Lease.
- 4. Except when damaged by the Government, Lessor shall reseal flooring in warehouse areas whenever there are noticeable variations in surface color or texture.

6.12 ASBESTOS ABATEMENT (APR 2011)

If asbestos abatement work is to be performed in the Space after occupancy, the Lessor shall submit to the Government the occupant safety plan and a description of the methods of abatement and re-occupancy clearance, in accordance with OSHA, EPA, DOT, state, and local regulations and guidance, at least 4 weeks prior to the abatement work.

6.13 ONSITE LESSOR MANAGEMENT (APR 2011)

The Lessor shall provide an onsite Building superintendent or a locally designated representative available to promptly respond to deficiencies, and immediately address all emergency situations.

6.14 IDENTITY VERIFICATION OF PERSONNEL (OCT 2016)

- A. The Government reserves the right to verify identities of personnel with routine and/or unaccompanied access to the Government's Space, including both pre and post occupancy periods. The Lessor shall comply with the agency personal identity verification procedures below that implement Homeland Security Presidential Directive-12 (HSPD-12), Office of Management and Budget (OMB) guidance M-05-24 and M-11-11, and Federal Information Processing Standards Publication (FIPS PUB) Number 201, as amended. These policies require the Government to conduct background investigations and make HSPD-12 compliant suitability determinations for all persons with routine or unaccompanied access to Government leased space. By definition, this includes at a minimum each employee of the Lessor, as well as employees of the Lessor's contractors or subcontractors who will provide building operating services requiring routine access to the Government's leased Space for a period greater than 6 months. The Government may also require this information for the Lessor's employees, contractors, or subcontractors who will be engaged to perform alterations or emergency repairs in the Government's Space.
- B. Application Process: The background investigation will be done using the Government's prescribed process. The Lessor must provide information on each of their contractor/personnel meeting the above criteria to the Government, whereupon each identified contractor/personnel will be notified with instructions for completing the identity verification application within a given time frame. The application process will include completing supplemental information forms that must be inputted into the identity verification system in order for the application to be considered complete. Additionally, the Lessor must ensure prompt completion of the fingerprint process for their contractor/personnel. Email notifications will be sent with instructions on the steps to be taken to schedule an appointment for fingerprinting at an approved regional location along with instructions on how to complete the background investigation application.
- C. The Lessor must ensure the Lease Contracting Officer (or the Lease Contracting Officer's designated representative) has all of the requested documentation timely to ensure the completion of the investigation.
- D. Based on the information furnished, the Government will conduct background investigations. The Lease Contracting Officer will advise the Lessor in writing if a person fails the investigation, and, effective immediately, that person will no longer be allowed to work or be assigned to work in the Government's Space.
- E. Throughout the life of the Lease, the Lessor shall provide the same data for any new employees, contractors, or subcontractors who will be assigned to the Government's Space in accordance with the above criteria. In the event the Lessor's contractor or subcontractor is subsequently replaced, the new contractor or subcontractor is not required to have persons re-apply who were cleared through this process white associated with the former contractor or subcontractor in accordance with GSA policy. The Lessor shall require each cleared person to re-apply and obtain a new clearance in accordance with GSA policy.
- F. The Lessor is accountable for not allowing contractors to start work without the successful completion of the appropriate background investigation as required by GSA policy.
- G. Access Card Retrieval/Return: Upon an Entry on Duty notification, the Government will issue a Personal Identity Verification (PIV) credential that is sometimes referred to as a GSA Access card. Lessors are responsible for all PIV credential issued to their contractors/personnel pursuant to this Lease. Lessors are specifically responsible for ensuring that all GSA PIV access cards are returned to the Lease Contracting Officer or their designee whenever their employees or a contractor no longer require access to the Space (such as When no longer needed for contract performance, upon completion of the Contractor employee's employment, and upon contract completion or termination). Additionally, the Lessor must notify the Lease Contracting Officer or their designee whenever a GSA PIV Access card is lost or stolen in which event the Lessor may be responsible for reimbursing the Government for replacement credentials at the current cost per PIV HSPD12 credential. Unreturned PIV Access cards will be considered as lost or stolen cards.
- H. The Government reserves the right to conduct additional background checks on Lessor personnel and contractors with routine access to Government leased Space throughout the term of the Lease to determine who may have access to the Premises.

LESSOR: BA GOVERNMENT

- I. The Lease Contracting Officer may delay final payment under a contract if the Contractor fails to comply with these requirements.
- J. The Lessor shall insert this paragraph in all subcontracts when the subcontractor is required to have physical access to a federally controlled facility or access to a federal information system.

6.15 SCHEDULE OF PERIODIC SERVICES (JUN 2012)

Within 60 days after occupancy by the Government, the Lessor shall provide the LCO with a detailed written schedule of all periodic services and maintenance to be performed other than daily, weekly, or monthly.

6.16 LANDSCAPING (OCT 2016)

- A. Landscape management practices shall prevent pollution by:
 - 1. Employing practices which avoid or minimize the need for fertilizers and pesticides;
 - 2. Prohibiting the use of the 2,4-Dichlorophenoxyacetic Acid (2,4-D) herbicide and organophosphates; and
 - 3. Composting/recycling all yard waste.
- B. The Lessor shall use landscaping products with recycled content as required by EPA's CPG for landscaping products. Refer to EPA's CPG web site, https://www.epa.gov/smm/comprehensive-procurement-guideline-cpg-program.
- C. If the Lessor satisfies performance of this Lease by new construction, and where conditions permit, the site shall be landscaped for low maintenance and water conservation with plants that are either native or well-adapted to local growing conditions.

6.17 LANDSCAPE MAINTENANCE (APR 2011)

Landscape maintenance shall be performed during the growing season at not less than a weekly cycle and shall consist of watering, weeding, mowing, and policing the area to keep it free of debris. Pruning and fertilization shall be done on an as-needed basis. In addition, dead, dying, or damaged plants shall be replaced.

6.18 RECYCLING-WAREHOUSE (MAY 2014)

- A. Where state or local law, code, or ordinance requires recycling programs for the Premises, Lessor shall comply with such state and/or local law, code, or ordinance.
- B. When implementing any recycling program, the Lessor shall provide an easily accessible, appropriately sized area (2 SF per 1,000 SF of Building gross floor area) that serves the Space for the collection and storage of materials for recycling. Telecom rooms are not acceptable as recycling space. During the Lease term, the Lessor agrees, upon request, to provide the Government with additional information concerning recycling programs maintained in the Building and in the Space.
- C. For Leases greater than 10,000 rentable SF, with a Lease term greater than six months, the Lessor shall establish a recycling program for (at a minimum) paper, corrugated cardboard, glass, plastics, and metals where local markets for recovered materials exist.

6.19 RANDOLPH-SHEPPARD COMPLIANCE (SEP 2013)

During the term of the Lease, the Lessor may not establish vending facilities within the leased Space that will compete with any Randolph-Sheppard vending facilities.

6.20 SAFEGUARDING AND DISSEMINATION—OF—SENSITIVE—BUT UNCLASSIFIED (SBU) BUILDING INFORMATION (OCT 2017) INTENTIONALLY DELETED

6.21 INDOOR AIR QUALITY (OCT 2016)

- A. The Lessor shall control airborne contaminants at the source and/or operate the Space in such a manner that the GSA indicator levels for asbestos, mold, carbon monoxide (CO), carbon dioxide (CO2), and formaldehyde are not exceeded. The indicator levels for office areas shall be: Asbestos 70 s/mm2; mold (see paragraph entitled "Mold"); CO 9 ppm; CO2 700 ppm above outdoor air; formaldehyde 0.016 ppm.
- B. The Lessor shall use available odor-free or low odor products when applying paints, glues, lubricants, and similar wet products. When such equivalent products are not available, lessor shall use the alternate products outside normal working hours. Except in an emergency, the Lessor shall provide at least 72 hours advance notice to the Government before applying chemicals or products with noticeable odors in occupied Spaces and shall adequately ventilate those Spaces during and after application.
- C. The Lessor shall serve as first responder to any occupant complaints about indoor air quality (IAQ). The Lessor shall promptly investigate such complaints and implement the necessary controls to address each complaint. Investigations shall include testing as needed, to ascertain the source and severity of the complaint.
- D. The Government reserves the right to conduct independent IAQ assessments and detailed studies in Space that it occupies, as well as in space serving the Space (e.g., common use areas, mechanical rooms, HVAC systems, etc.). The Lessor shall assist the Government in its assessments and detailed studies by:
 - 1. Making available information on Building operations and Lessor activities;

LESSOR: D GOVERNMENT:

LEASE NO. GS-03P-LMD00631, PAGE 35

- Providing access to Space for assessment and testing, if required; and
- Implementing corrective measures required by the LCO.
- E. The Lessor shall provide to the Government safety data sheets (SDS) upon request for the following products prior to their use during the term of the Lease: adhesives, caulking, sealants, insulating materials, fireproofing or firestopping materials, paints, carpets, floor and wall patching or leveling materials, lubricants, clear finish for wood surfaces, janitorial cleaning products, pesticides, rodenticides, and herbicides. The Government reserves the right to review such products used by the Lessor within:
 - 1. The Space:
 - 2. Common Building areas;
 - 3. Ventilation systems and zones serving the Space; and
 - 4. The area above suspended ceilings and engineering space in the same ventilation zone as the Space.

(b) (5)

6.22 RADON IN AIR (OCT 2016)

If Space planned for occupancy by the Government is on the second floor above grade or lower, the Lessor shall, prior to occupancy, test the leased Space for 2 days to 3 days using charcoal canisters. The Lessor is responsible to provide Space in which radon levels in air are below the GSA action levels of 4 picoCuries per liter (pCi/L) for childcare and 25 pCi/L for all other space. After the initial testing, a follow-up test for a minimum of 90 days using alpha track detectors shall be completed. For further information on radon, go to: https://www.epa.gov/radon.

- 6.22 RADON IN AIR (SEP 2013) INTENTIONALLY DELETED
- 6.23 RADON IN WATER (JUN 2012) INTENTIONALLY DELETED

6.24 HAZARDOUS MATERIALS (WAREHOUSE) (MAY 2014)

- A. The leased Space shall be free of hazardous materials, hazardous substances, and hazardous wastes, as defined by and according to applicable Federal, state, and local environmental regulations. Should there be reason to suspect otherwise, the Government reserves the right, at Lesson's expense, to require documentation or testing to confirm that the Space is free of all hazardous materials.
- B. Lessor shall, to the extent of its knowledge, notify Government of the introduction of any hazardous materials onto the Property by Lessor or others, including but not limited to, co-tenants occupying Space in the Building.
- C. All hazardous materials stored in the Space must be kept and maintained according to applicable Federal, State, and local environmental regulations. The Government will notify Lessor of any hazardous materials it will store in the Space.

6.25 MOLD (OCT 2018)

- A. Actionable mold is either visible mold or airborne mold of types and concentrations in excess of that found in the local outdoor air or non-problematic control areas elsewhere in the same building, whichever is lower. The Lessor shall safely remediate all actionable mold in accordance with sub-paragraph C below.
- B. The Lessor shall provide Space to the Government that is free from ongoing water leaks or moisture infiltration. The Space and ventilation zones serving the Space shall also be free of actionable mold.
- C. Within 72 hours following a flood, plumbing leak or heavy rain whereby the Government Space or air zones serving the Space may have become moisture damaged, the Lessor shall immediately repair any leakage sources and remediate the moisture damage. Whenever moisture damage or infiltration persists such that: mold is visible, mold odors are present, or occupants register complaints about mold, the Lessor shall employ a board-certified, industrial hygienist or equivalently qualified consultant to inspect and evaluate the Space and air zones serving the Space for visible and/or actionable mold presence; inspection shall take place no later than 15 calendar days following identification of a potential mold issue as described above. The Lessor shall promptly furnish these inspection results to the Government. After all leaks have been identified and corrected, the Lessor shall safely remediate all visible moldy and/or water damaged materials identified by the consultant using a qualified remediation contractor following the methods identified in "Mold Remediation in Schools and Commercial Buildings" (EPA 402-K-01-001, September 2008) and all applicable state laws pertaining to mold remediation practices. Remediation shall also remove actionable mold levels. Remediation shall be completed within a time frame acceptable to the Lease Contracting Officer which shall be no later than 90 calendar days following confirmation of the presence of actionable mold.
- D. The presence of actionable mold in the Premises may be treated as a Casualty, as determined by the Government, in accordance with the Fire and Other Casualty clause contained in the General Clauses of this Lease. In addition to the provisions of the Fire and Other Casualty clause of this Lease, should a portion of the Premises be determined by the Government to be un-tenantable due to an act of negligence by the Lessor or his agents, the Lessor shall provide reasonably acceptable alternative Space at the Lessor's expense, including the cost of moving, and any required alternations.

6.26 OCCUPANT EMERGENCY PLANS (SEP 2013)

The Lessor is required to cooperate, participate and comply with the development and implementation of the Government's Occupant Emergency Plan (OEP) and if necessary, a supplemental Shelter-in Place (SIP) Plan. Periodically, the Government may request that the Lessor assist in reviewing and revising its OEP and SIP. The Plan, among other things, must include an annual emergency evacuation drill, emergency notification procedures for the Lessor's Building engineer or manager, Building security, local emergency personnel, and Government agency personnel.

LESSOR: 137L GOVERNMENT:

6.27 FLAG DISPLAY (OCT 2016) INTENTIONALLY DELETED

6.28 PORTABLE FIRE EXTINGUISHERS (WAREHOUSE) (MAY 2014)

Lessor shall provide, inspect, and maintain portable fire extinguishers in accordance with NFPA No. 10.

6.29 TRASH DUMPSTER SERVICE - LESSOR PROVIDED (WAREHOUSE) (OCT 2016)

Lessor must provide trash dumpster service for the Space on a bi-weekly basis. Lessor must provide an outdoor area for two dumpsters, conveniently located to the Government's loading area for the trash dumpsters at no additional charge to the Government. Current location of the dumpsters is acceptable and shall not be considered in violation of the security requirements.

6.30 ACCESS TO BUILDING INFORMATION (MAY 2014)

Building Information—including mechanical, electrical, vertical transport, fire protection and life safety, security system plans and schematics, computer automation systems, and emergency operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only, approved by the Government, preferably by the development of an access list and controlled copy numbering. The LCO may direct that the names and locations of Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the Building directory.

LESSOR: AL GOVERNMENT:

SECTION 7 ADDITIONAL TERMS AND CONDITIONS

7.01 SECURITY REQUIREMENTS (OCT 2016)

The Lessor agrees to the requirements of Facility Security Level

attached to this Lease.

7.02 MODIFIED LEASE PARAGRAPHS (OCT 2016)

The following paragraphs have been modified in this Lease:

- 1.02 EXRPRESS APPERTUNANT RIGHTS (WAREHOUSE) (MAY 2014)
- 1.03 TRUCK TURNING RADIUS REQUIREMENTS (WAREHOUSE) (MAY 2014)
- 1.04 CLEAR CEILING HEIGHT REQUIREMENTS (WAREHOUSE)(MAY2014)
- 1.05 BAY WIDTH, BAY DEPTH, AND COLUMN SPACING REQUIRMENTS (WAREHOUSE) (MAY 2014)
- 1.06 RENT AND OTHER CONSIDERATION (OCT 2017)
- 1.22 **BUILDING IMPROVEMENTS**
- 2.09 **OPERATING COSTS ADJUSTMENT (JUN 2012)**
- 3.39 HEATING AND VENTILATION - SHELL (WAREHOUSE) (OCT 2016)
- 3.50 LOADING DOCKS (WAREHOUSE)(MAY2014)
- 4.01 SCHEDULE FOR COMPLETION OF SPACE
- HEATING AND AIR CONDITIONING 6.04
- JANITORIAL SERVICES (WAREHOUSE) (MAY 2014) 6.06
- 6.29 TRASH DUMPSTER SERVICE

7.03 ADDENDUM TO GSA FORM-3517B, GENERAL CLAUSES, NO FEDERALLY ELECTED OFFICIALS_TO_BENEFIT (OCT_2018) INTENTIONALLY DELETED

7.04 UNIQUE REQUIREMENTS

- A. Scope of Work for recent expansion is attached as part of this lease.
- The Government shall have exclusive use of the south side gate. In addition, the Government shall have exclusive use of the ware yard behind bays 1 through 39.

7.05 ADDITIONAL WAREYARD REQUIREMENTS

- The loading and wareyard behind the Space between loading docks 1 and 39 is for the Government's exclusive use. The Lessor shall install "No Parking" and "Do Not Enter" signs, or other means acceptable to the LCO, to restrict other tenants from accessing the area.
- B. The Government shall control all access in and out of the wareyard through a secured gate at the corner of the Government's occupied space.
- At a minimum, the wareyard surface shall be concrete capable of withstanding the weight of fully loaded tractor trailer. The wareyard shall be lit, (the cost of lighting fixtures and installation being a part of Shell Rent) in accordance with the same standards set forth for parking areas as covered in Lease Section 3.42.

7.06 SUBLETTING AND ASSIGNMENT

Related to GSA Form 3517B (REV 06/16) Section 1 (Subletting and Assignment) and Section 5 (Substitution of Tenant Agency), any subletting, assignment or substitution of tenant agency shall be subject to the prior written consent of the Lessor, which shall not be unreasonably withheld, conditioned or delayed.


7.07 PRIOR LEASE


GSA Lease Number GS-03B-11320, as amended, shall remain in full force and effect until the Commencement date of this Lease.

LESSOR: 12- GOVERNMENT:

LEASE NO. GS-03P-LMD00631, PAGE 38

GSA FORM L201WH (10/18)





HHS PSC North East MD Warehouse Expansion - Alterations Scope of Work

Scope of Work Alterations

A. PROJECT OUTLINE

1.1 Project Identification

Project Title: Building: Location:

HHS PSC Warehouse Expansion North East Commerce Center

4 Center Drive

North East, MD 21901

GSA Project Manager:
GSA Project Architect:
GSA Lossa Contracting Office

JD May Oluyomi Adewale (215) 446-4535 (215) 606-1759

GSA Project Architect:
GSA Lease Contracting Officer:
GSA Field Rep:

JoAnn Stewart Doug Taylor (215) 446-4697

Doug rayio

(410) 209-9545

B. Project Objective

The objective of this Scope of Work (SOW) is to identify alterations required in relation to the expansion of the existing HHS PSC warehouse footprint into the adjacent unoccupied warehouse space; a total of approximately 38,400 ABOA SF. The intent of the expansion is to provide additional capacity for the Supply Chain Management Service (SCMS) so it can accommodate the increased demand as a direct result of increased business with the Navy Bureau of Medicine and Surgery (BUMED), Health and Human Services Biomedical Advanced Research and Development Authority (BARDA), and the Air Force National Guard (ANG).

C. Project Description:

The Supply Chain Management Service (SCMS) currently manages a stockpile center in North East, Maryland. The SCMS is requesting additional space because the current space is at full capacity and cannot accommodate increased demand from its clients as indicated in section B above. The new space will be used to consolidate the various activities supporting the Department of Homeland Security BioWatch Program allowing for growth in the program. The proposed space is located in the same building and is directly adjacent to the current occupied space. The space will house consumable laboratory supplies for laboratories and field activities across the United States, rapidly deployable laboratories (RDLs), and space to maintain/calibrate portable sampling units (PSUs).

Expansion effort will, by necessity, encompass shell renovation, tenant improvement and HHS self-performed work within the approximately 38,400 square feet of interior space and some exterior work. For cost proposal documentation purposes the work will be divided into three (3) parts having separate line items. Lessor will organize design submissions as follows:

- 1. Shell Improvements Lessor is responsible for this portion of the work. Any item contributory to the provision of a "warm, lit" space falls into this category.
- 2. Tenant Improvements The Government is responsible for funding this portion of the work.
- Tenant Provided Improvements In addition to Government contracted tenant improvement work noted above HHS will self-perform certain tenant improvements. Government shall coordinate with Lessor for completion of these items, if necessary.

Lessor is to be aware that the facility will remain operational at all times during the construction.

Where there are conflicts existing between requirements indicated in this scope of work and other information provided; Lessor shall notify GSA project manager and Lease Contracting Officer immediately for clarification and direction.

INITIALS: MA LESSOR & GOVT

D. DESIGN REQUIREMENTS

Lessor must generate Construction Documents (CDs) that reflect the design intent as described in this SOW and other information provided. CDs shall include all mechanical, electrical, plumbing, fire protection, life safety, lighting and architectural improvements. CDs shall be annotated with all applicable specifications. CDs shall also clearly identify items existing to remain, demolition, and the new work to be done by the Lessor or others.

The Government shall review, comment and make suggestions or recommendations to the CDs during the design phase. The Government's review of the construction documents will be limited to the construction documents' conformance to the specific requirements of this scope of work and other information provided. The Lessor is responsible for ensuring compliance with local, state, federal, national, etc. codes and design standards. The Lessor is solely responsible and liable for the technical accuracy of the construction documents.

1. Shell Improvements (Expansion Space)

1.1 Demolition

Lessor shall remove existing abandoned electric, telephone, and data cabling devices as well as any other improvements or fixtures in place to accommodate the Government's requirements. Any demolition of existing improvements that is necessary to satisfy the Government's layout shall be done at lessor's expense. See attached floorplan for offices that the Government will retain.

1.2 **HVAC**

Below is the shell component of HVAC. The difference between these requirements and those listed below in Tenant Improvement Section 2.3 are considered to be tenant improvement costs.

- A. Warehouse areas: Temperature control for all warehouse areas shall be provided by ceiling mounted heating equipment capable of maintaining a minimum temperature of 55 degrees Fahrenheit (with all doors closed) throughout the warehouse area during the heating season regardless of the outside temperature. Unit heaters shall be controlled by individual thermostats mounted in the area of the unit heaters, or controlled from a central master time clock of the 7-day type with a separate manual overdrive switch (12 hours) or other automatic means to permit setback of temperature at night and on weekends. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the Government's designated representative. Central air rotation units will be acceptable if loading dock areas are equipped with unit heaters for direct heating over doors. In the warehouse area, unit heaters shall be mounted tight to the ceiling for maximum headroom. Lessor shall provide ventilation/air circulation in accordance with [the latest version of ASHRAE 62.1].
- B. Office Areas: Central HVAC systems shall be installed and operational, including, as appropriate, main and branch lines, VAV boxes, dampers, flex ducts, and diffusers, for an open office layout, including all Building common areas. The Lessor shall provide conditioned air through medium pressure duct work at a rate of .75 cubic feet per minute per ABOA SF and systems shall be designed with sufficient systems capacity to meet all requirements in this Lease.
- C. Areas having excessive heat gain or heat loss, or affected by solar radiation at different times of the day, shall be independently controlled.
- D. <u>Equipment Performance</u>. Temperature control for office Spaces shall be provided by concealed central heating and air conditioning equipment. The equipment shall maintain Space temperature control over a range of internal load fluctuations of plus 0.5 W/SF to minus 1.5 W/SF from initial design requirements of the tenant.
- E. <u>Ductwork Re-use and Cleaning</u>. Any ductwork to be reused and/or to remain in place shall be cleaned, tested, and demonstrated to be clean in accordance with the standards set forth by NADCA. The cleaning, testing, and demonstration shall occur immediately prior to Government occupancy to avoid contamination from construction dust and other airborne particulates.


INITIALS: MA LESSOR & GOVT

F. During working hours in periods of heating and cooling, ventilation shall be provided in accordance with the latest edition of the American National Standards Institute, American Society of Heating, Refrigeration and Air-Conditioning Engineers (ANSI/ASHRAE) Standard 62.1, Ventilation for Acceptable Indoor Air Quality.



- H. Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour.
- I. SUB-PARAGRAPH INTENTIONALLY DELETED
- J. Warehouse and Office areas: HVAC systems must conform to the locally approved building code.

1.3 Fire/Life Safety



1.4 Loading Dock Tarmac

Lessor shall repair existing loading dock tarmac in order to achieve a level and even driving surface. Extent of repair is from loading dock south side entry to HHS's last docking bay (Bays 1 through 39). Loading dock apron shall have sufficient structural capacity to handle standard 18 wheeler semi-trailer truck (minimum weight 40 tons) complete with requisite appropriately rated landing strip concrete pads.

1.5 Windows

Existing windows need to be cleaned and sealed (if necessary) to ensure no water penetration.

1.6 Warehouse Flooring

Floors shall be of a common level, non-slip and acceptable to the Contracting Officer. The uniformly distributed design live floor load of all warehouse floors shall be no less than 250 pounds per ABOA SF. Written certification of the floor load capacity by a registered professional engineer may be required, at no cost to the Government. Calculations and structural drawings may also be required. Warehouse and storage area floors shall be smooth concrete and must be sealed with an epoxy or urethane sealer, acceptable to the Contracting Officer with an expected service life of no less than 5 years. Existing floor in expansion space is acceptable to the Government.

INITIALS: A LESSOR & GOVT

1.7 <u>Lighting: Interior and Parking – Shell (Warehouse) (OCT 2016)</u> Warehouse/Storage Space & Overall:

- A. Lessor shall provide a minimum lighting level of 10 foot-candles, as measured 30 inches above the floor, in aisles and open storage areas in the warehouse Space with the storage racks full. Lessor shall provide a minimum lighting level in the shipping and receiving areas of 30 foot-candles, when measured 30 inches above the floor. Lessor must provide lighting that is equivalent to the energy efficiency requirements in any office areas. Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all non-office areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided as part of Shell Rent in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs.
- B. <u>Occupancy Sensors</u>: The Lessor shall provide ceiling mount occupancy sensors (over aisles and open areas), or scheduling controls through a building automation system (BAS) throughout the storage portion of the Space in order to reduce the hours that the lights are on when a particular area is unoccupied. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

C. <u>Building Perimeter</u>:

- Exterior parking areas, vehicle driveways, pedestrian walks, and the Building perimeter lighting levels, (especially at loading dock doors), shall be designed per Illuminating Engineering Society (IES) standards. Provide 5 foot-candles for doorway areas, 3 footcandles for transition areas and at least 1 foot-candle at the surface throughout the parking lot. Parking lot fixtures shall provide a maximum to minimum uniformity ratio of 15:1 and a maximum to average uniformity ratio of 4:1. Sodium vapor lighting fixtures are prohibited.
- 2. SUB-PARAGRAPH INTENTIONALLY DELETED
- D. SUB-PARAGRAPH INTENTIONALLY DELETED
- E. SUB-PARAGRAPH INTENTIONALLY DELETED

b) (5)

G. Office Area Lighting Levels: Fixtures shall have a minimum of two tubes and shall provide 50 foot-candles at desktop level (30" above finished floor) with a maximum uniformity ratio of 1.5:1. Lessor shall provide, as part of Shell Rent, 10 average foot-candles in all other Building areas within the Premises with a uniformity ratio of 4:1. Emergency egress lighting levels shall be provided in accordance with the local applicable building codes (but not less than 1 foot-candle) by either an onsite emergency generator or fixture mounted battery packs.

1.8 Loading Dock Access Gate

The Government shall have exclusive use of the south side gate. In addition, the Government shall have exclusive use of the ware yard behind bays 1 through 39.

1.9 Existing Restrooms

Existing Restrooms must be thoroughly cleaned and painted prior to acceptance. Remove and remediate any areas of mold. Replace all ceiling tiles.

Restrooms must be handicapped accessible.

Each main restroom must contain the following:

- A mirror and shelf above the lavatory.
- A toilet paper dispenser in each water closet stall that will hold at least two rolls and allow easy, unrestricted dispensing.
- A coat hook on the inside face of the door to each water closet stall and on several wall locations by the lavatories.
- At least one modern paper towel dispenser, soap dispenser, and waste receptacle for every two lavatories.

INITIALS: MA LESSOR & COVT

- 5. A counter area of at least 2 feet, 0 inches in length, exclusive of the lavatories (however, it may be attached to the lavatories) with a mirror above and a ground-fault interrupter-type convenience outlet located adjacent to the counter area. The counter should be installed to minimize pooling or spilling of water at the front edge.
- 6. A floor drain.
- Sub-paragraph intentionally deleted.
- Restrooms shall be properly exhausted, with a minimum of 10 air changes per hour. The exhaust fan systems shall be provided with a 24/7 seven day clock to allow programming.

2. Tenant Improvements

Lessor shall provide a detailed cost proposal including all labor, services, materials and equipment necessary to fully provide for the following items listed below:

2.1 Interior Connected Access

Provide two (2) new openings in existing masonry/GB hybrid partition for access between existing space and expansion space. Location to be aligned with other existing openings in adjacent warehouse bay as indicated by HHS. 1st Opening is 14 Feet from wall, 9 feet wide and 11 Feet high. Second opening at Rear Wall (Loading Doors), opening starts at 26'4" (on seam), 9 Feet Wide, 11 Feet High. See attached plan.

2.2 Finishes

For offices to remain in the expansion space (see attached floorplan), lessor shall replace all interior finishes to include: wall finish and floor finish. Replace all existing 4'x2' acoustic ceiling tiles (ACT) throughout the office areas. New ACT's to match existing removed. Ceiling height is 9 feet above finished floor. Clean existing ceramic floor tiles at the office reception as required to restore luster and burnish.

Replace all existing door hardware. Apply fresh door finish to match existing.

Painting Specs:

- A. Prior to acceptance, all surfaces within the office spaces to remain shall be newly finished in colors acceptable to the Government. Lessor shall provide a minimum of three (3) finish samples to the Government.
- B. The Lessor shall provide interior paints, primers, coatings, stains, and sealers that meet or are equivalent to the Green Seal GS-11 standard that incorporates environmental, health, and performance criteria.
- C. The Lessor shall use reprocessed latex paint in accordance with EPA's CPG (Comprehensive Procurement Guidelines) on all painted surfaces where feasible. The type of paint shall be acceptable to the Government.

Carpet Specs:

- 1. <u>Product sustainability and environmental requirements</u>. Floor covering and perimeter products must meet at least one of the environmentally preferable criteria within the non-federal, multi-attribute standards and ecolabels categories, as outlined under the Green Procurement Compilation at www.sftool.gov/greenprocurement.
- Face fiber content. Face yarm must be 100 percent rylon fiber. Loop Pile shall be 100
 percent Bulk Continuous Filament (BCF); cut and loop shall be 100 percent BCF for the loop
 portion and may be BCF or staple for the cut portion; cut pile carpet shall be staple or BCF.
- 3. Performance requirements for broadloom and modular tile:
 - a. <u>Static</u>: Less than or equal to 3.5 kV when tested by AATCC Test Method 134 (Step Test Option).
 - b. Flammability: Meets CPSC-FF-1-70, DOC-FF-1-70 Methenamine Tablet Test criteria.
 - Flooring Radiant Panel Test: Meets NFPA 253 Class I or II depending upon occupancy and fire code when tested under ASTM E-648 for glue down installation.
 - d. <u>Smoke Density</u>: NBS Smoke Chamber—Less than 450 Flaming Mode when tested under ASTM E-662.

INITIALS: 1 LESSOR & GOVT

NOTE: Testing must be performed in a NVLAP accredited laboratory.

- 4. Texture Appearance Retention Rating (TARR). Carpet must meet TARR rating of at least 3.0 TARR for moderate traffic areas such as private offices, and heavy traffic areas such as training space, conference rooms, courtrooms, etc., and at least 3.5 TARR for severe traffic areas, including open office space, cafeteria, corridors and lobbies. The carpet must be evaluated using ASTM D-5252 Hexapod Drum Test as per the commercial carpet test procedure and the TARR classification determined using ASTM D-7330.
- Carpet reclamation. Reclamation of existing carpet to be determined with potential vendor.
 When carpet is replaced, submit certification documentation from the reclamation facility to the LCO.
- Warranty. Submit a copy of the manufacturer's standard warranty to the LCO within the first 60 days of Government occupancy. The Government is to be a beneficiary of the terms of this warranty.

2.3 **HVAC**

A controlled room temperature of 68° – 77°F is required during all seasons, USP Controlled Room Temperature*. These temperatures shall be maintained through the leased premises and service areas at all times, regardless of outside temperatures. At all time, humidity shall be maintained below 60% relative humidity. Thermostats shall be secured from manual operation by key or locked cage. A key shall be provided to the GSA Property Manager or other designated Government official. The difference in cost between this requirement and that noted in Shell Paragraph 1.2 Shell HVAC above, is considered the tenant improvement portion of HVAC.

*For the shipping and storage of pharmaceuticals, the United States Pharmacopeia-National Formulary (USP-NF) defines controlled room temperature as between 20 to 25 °C (68 to 77 °F), with excursions between 15 to 30 °C (59 to 86 °F) allowed, provided the mean kinetic temperature does not exceed 25 °C (77 °F).

2.4 Lighting

OFFICE AREAS:

NOTE: FOR PRICING ESTIMATING PURPOSES, FIXTURES IN OFFICE AREAS WILL BE INSTALLED AT THE AVERAGE RATIO OF 1 FIXTURE PER 80 ABOA SF.

- A. FIXTURES: High efficiency T-8, T-5, or LED light fixtures (and associated ballasts or drivers) shall be installed as either ceiling grid or pendant mounted for an open-office plan. Ceiling grid fixtures shall be either 2' wide by 4' long or 2' wide by 2' long. Lessor shall provide a minimum overall lighting fixture efficiency of 85 percent. Lamps shall maintain a uniform color level throughout the lease term.
- B. LIGHTING LEVELS: Fixtures shall have a minimum of two tubes and shall provide 50 foot-candles at desktop level (30" above finished floor) with a maximum uniformity ratio of 1.5:1.

C. POWER DENSITY:

Existing Buildings: The maximum fixture power density shall not exceed 1.4 watts per ABOA SF.

New Construction: The maximum fixture power density shall not exceed 1.1 watts per ABOA SF.

D. DAYLIGHTING CONTROLS: If the office portion of the Space is more than 10,000 ABOA SF, the Lessor shall provide daylight dimming controls in atriums or within 15 feet of windows and skylights where daylight can contribute to energy savings. Daylight harvesting sensing and controls shall be either integral to the fixtures or ceiling mounted and shall maintain required lighting levels in office work areas.

INITIALS: Br LESSOR & GOVT

E. OCCUPANCY/VACANCY SENSORS: The Lessor shall provide ceiling mount occupancy sensors, or vacancy sensors (preferred), or scheduling controls through a building automation system (BAS) throughout the office portion of the Space in order to reduce the hours that the lights are on when a particular space is unoccupied. Occupancy sensors only shall be installed in the non-office areas of the Space as part of Shell Rent. No more than 1,000 square feet shall be controlled by any one sensor. Occupancy sensors in enclosed rooms shall continue to operate after any BAS has shut down the building at the end of the workday.

2.5 Eyewash Station

Remove existing utility sink/eyewash station. Provide and install any infrastructural modification required at the existing sink needed for the hook up of Government-furnished-contractor-installed (GFCI) mobile sink unit. Mobile sink data is as follows: Atlanta Culinary Equipment, Inc – Food service equipment, commercial cooking and hot food storage equipment- SE18182D. See manufacturers' website for pipe sizing and other hook up requirements.

2.6 Gate Access to Loading Area

The existing chain link fence gate providing access to the loading docks on the south side of the site must be capable of remote access control. Lessor shall provide and install backboxes, conduit/pull wire access control system from the gate to the warehouse office in the expansion space. Locations noted on attached floorplan.

3 Tenant Provided Improvement

The following work is to be self-performed by the tenant Government agency and is provided here for Lessor coordination. The Lessor design should account for required coordination by the general contractor. Conduit and power shall be coordinated in the design and installed by the Lessor. All coordination materials and labor to be billed as tenant improvement costs.

- 3.5 Provide and install mobile sink unit. Plumbing hook ups provided by Lessor under TI item 2.5 above.
- 3.6 HHS shall provide and install access control mechanism for exterior gate at loading dock access drive as part of HHS PSC security contract. Requirements such as but not limited to opening speed, crash rating, mode of operation etc shall be per PSC internal requirements. Lessor shall provide conduit and power as noted in 2.6 above.
- 3.7 Security System. HHS PSC will design and install a security system. Lessor to coordinate provision of power.
- 3.8 Telecom/Data/Phone. HHS PSC will design and install a Telecoms/data/phone system. Lessor to coordinate conduits and wall plate locations with HHS. Lessor to provide power.
- 3.9 Racking and other storage related equipment: HHS will plan the layout of, furnish and install its own high-bay metal storage racks within the expansion warehouse space.

E. DESIGN SUBMISSIONS

Prior to submitting a cost proposal, Lessor shall submit design/construction documents outlining the requirements of this scope of work. The Design Packages must include:

1. Specifications:

Project Specifications must be sufficiently detailed to direct the construction work outlined in this scope of work and other information provided. Specifications must specifically address the means to keep the facilities accessible and operational throughout the work.

INITIALS: 151 LESSOR & GOVT

In addition to preparation of technical specifications sections, the Lessor is responsible for editing all Division 1 specifications to address building, project, and customer specific requirements, including but not limited to the following:

- Hours of work
- Special security
- Construction waste management
- Staging area
- Contractor access to building
- Parking
- Phasing (if any)
- Temporary facilities
- Building and Space Access
- 1.1 GSA uses the CSI (Construction Standards Institute) "MasterFormat" (latest versions) system with the GSA Supplement for Division 1 as its project specifications format. GSA requests the Lessor develop the specifications in this format.
- 1.2 Specifications shall be in imperial units with no metric equivalent
- 1.3 The Project Specifications must completely encompass the scope of work and design of the project. Lessor must include requirements in the specification to ensure that the contractor obtains all required Federal, State and local permits. Extensive editing and additions to the above listed guide specifications will be required to tailor them to this scope of work.
- 1.4 The specifications must take into account a construction plan producing a minimum disruption of day-to-day activities, climate control, utilities, and services.
- 1.5 Construction Contract Submittal List
 As part of the Construction Document Submission, the Lessor shall submit a list of all submittals required under the construction contract. The list shall include specification section and paragraph numbers and type of submittal.

2. Drawings:

- 2.1 The Lessor must develop all contract drawings required to convey the project scope. The drawings must be scaled floor plans for each discipline required (architectural, mechanical, electrical, structural etc.), with separate sheets for new work and demolition as well as enlarged floor plans, equipment details, riser diagrams, schedules, etc. Drawings must clearly distinguish between new and existing work.
- Each drawing's title block must indicate project title, project number, building name, building address, building number, A/E's name, A/E's address and/or phone number, contract number, drawing title, drawing type, drawing number, and key plan. A cover sheet must be provided and shall include a list of the drawings, legend, vicinity map, and location map in addition to all items required for each drawing. Each A/E submission must be clearly dated and labeled (e.g. Tentative Design Submission, Final Design Submission). Each drawing sheet submitted must include a graphic scale in the lower right-hand portion of the sheet. The final set must be signed and sealed by a registered engineer and/or registered architect for the state in which the building is located.
- 2.3 The Contract Documents must sufficiently define the scope of work and must stand on their own. The drawings must not require a site visit of construction bidders in order to develop a bid price.
- 2.4 Drawings and specifications must be fully coordinated to ensure that all necessary work and materials are included for an operational facility of finished appearance.

INITIALS: Br LESSOR GOVT

- 2.5 Construction drawings must be provided on a USB/CD-Rom/DVD in CAD format. Upon project completion, the Lessor shall furnish to the Government a complete set of as built floor plans.
- 2.6 The Lessor must provide a USB/CD/DVD with Signed and Sealed Construction Documents in PDF Format in addition to the CAD files.

F. SCHEDULE

Submission schedule as follows:

Stage/Phase/Submission	Submission [Government Review	
Stage/Phase/Submission	Duration*	After	Period*
1) DESIGN STAGE			
Design Intent Document (DID) Phase			
DID (50%) Submission	14 days	Request for Proposal	14 days
Construction Document (CD) Phase			
Pre-Final CD (65%) Submission	14 days	GSA Acceptance of DIDs	14 days
Final CD (100%) Submission	14 days	GSA Review of 65% CDs	7 days
2) CONSTRUCTION STAGE			
Construction Delivery Phase	45 days	Issuance of NTP	
LESSOR/Final As-Built Drawings	30 days	Government Acceptance	

Note: Durations and review periods listed are in Calendar Days.

Lessor shall supply the following types and quantities of each submission as indicated in the distribution schedule below.



DISTRIBUTION SCHEDULE					
NAME	ADDRESS	PHONE #	# OF COPIES	FORMAT	SUBMISSIONS
James D. May	100 S Independence Mall W, Philadelphia, PA, 19106-2349	(215)446-4535	1 electronic submission (CD or USB drive)	Electronic submission to contain both PDFs and raw files (word doc, .dwg or BIMs)	All milestones
Yomi Adewale	100 S Independence Mall W, Philadelphia, PA, 19106-2349	(215)606-1759	1 Half size Hard copies and 1 electronic submission (CD or USB drive)	Electronic submission to contain both PDFs and raw files (word doc, .dwg or BIMs)	All milestones
JoAnn Stewart	100 S Independence Mall W, Philadelphia, PA, 19106-2349		1 Half size Hard copy and 1 electronic submission (email or USB)	Electronic submission to contain both PDFs and raw files (word doc, .dwg or BIMs)	All milestones
Saharnaz Javaheri,	Real Estate, Logistics, and Operations Support (RLO) U.S. Department of Health and Human Services Washington DC	(202)695-4047	1 Full size Hard copy and 1 electronic submission (CD or USB drive)	Electronic submission to be PDFs only	All milestones

In addition, Lessor shall comply with the Following Procedures:

- i. All site visits are to be coordinated with GSA/HHS in advance
- ii. All contract documents are incorporated and labeled as Sensitive but Unclassified (SBU) and treated appropriately. The following SBU verbiage shall be added to all sheets and documents:

SENSITIVE BUT UNCLASSIFIED (SBU) PROPERTY OF THE UNITIED STATES GOVERNMENT –
FOR OFFICIAL USE ONLY –
Do Not Remove This Notice.
Properly Destroy Documents When No Longer Needed.

G. CONSTRUCTION:

The Contractor shall perform all professional construction services as necessary to provide a complete project in accordance with this scope of work and associated attachments.

The expansion space is currently un-occupied. However, work to connect the expansion with the existing space as well as the delivery bay tarmac repairs may need to be completed in phases. Coordination to be further discussed with the Government and Lessor project teams.

INITIALS: MESSOR & LEOVE

H. PROPOSALS

The Lessor's price proposal shall be supported by sufficient cost or pricing data to both enable the Government to evaluate the reasonableness of the proposal(s) and act as documentation that the proposal(s) is based upon competitive pricing. After negotiation and acceptance of price, GSA shall issue a NTP to the Lessor through Lease Amendment.

I. SCHEDULE

The Government requires a detailed project schedule (such as Critical Path Method) illustrating design and construction milestones. Schedule shall be provided within seven (7) calendar days of NTP.

The Government places no restrictions on work hours but all work shall be coordinated with HHS so that day to day functions will not be disrupted by Lessors activities relating to this work.

J. SECURITY CLEARANCES

The contractors must have legal work status. HHS will run an NCIC check on contractors. Name and SSN to be provided by the Lessor. Fingerprints will be required. Estimated turn-around time on clearances is approximately two weeks. Escorts may be required for contractor access to HHS currently occupied space. Coordinate with HHS facility manager.

K. PROGRESS REPORTS / MEETINGS

After start of construction, the Lessor shall submit written progress reports at two week intervals. Each report shall include information as to the percentage of the work completed by phase and trade, expected completion and occupancy dates; changes introduced into the work.

Lessor shall conduct progress meetings every two weeks to brief Government personnel and/or contractors regarding the progress of design and construction of the Space. The Lessor and/or contractor shall be responsible for taking and distributing minutes of these meetings.

Planned meetings for this project include:

- 1. Design Kick-off and Design Review Meetings
- Pre-construction Meeting: The Lessor and Contractor shall attend a pre-construction
 meeting prior to construction. Construction may not begin until this meeting is held. This
 meeting serves to answer any questions from the Lessor or Contractor and to discuss
 building issues such as storage, security, access, working hours, etc.
- 3. Bi-weekly Progress Meetings

L. INSPECTIONS / ACCEPTANCE

The Government may periodically inspect construction work to review compliance with lease and project. Government inspection is required prior to acceptance of work. The space shall be considered substantially complete only if the space may be used for its intended purpose, and completion of remaining work will not unreasonably interfere with the Government's productive use of the space.

M. PAYMENT OF FEE


Upon completion and acceptance of all work, a Lease Amendment will be executed to expand current lease GS-03B-11320. Any tenant improvement costs associated with the expansion space will be included in the rent for the long-term replacement lease.


N. CORRESPONDENCE:

Scope of work questions, contractor requests for information (RFIs), or submittals shall be provided to GSA Contracting Officer, Project Architect and Project Manager.

O. ATTACHMENTS:

INITIALS: 11 LESSOR GOVT





SECURITY REQUIREMENTS - FACILITY SECURITY LEVEL

) (5)

THESE PARAGRAPHS CONTAIN ADDITIONAL SECURITY REQUIREMENTS, AND, UNLESS INDICATED OTHERWISE, ARE TO BE PRICED AS PART OF THE BUILDING SPECIFIC AMORTIZED CAPITAL (BSAC). WHERE THEY ARE IN CONFLICT WITH ANY OTHER REQUIREMENTS ON THIS LEASE, THE STRICTEST SHALL APPLY.

DEFINITIONS:



FACILITY ENTRANCES, LOBBY, COMMON AREAS, NON-PUBLIC, AND UTILITY AREAS.

FACILITY ENTRANCES AND LOBBY

EMPLOYEE ACCESS CONTROL AT ENTRANCES (SHELL)

(b) (5

COMMON AREAS, NON-PUBLIC, AND UTILITY AREAS.

PUBLIC RESTROOM ACCESS (SHELL)


The Government reserves the right to control access to public restrooms located within the Space.

SECURING CRITICAL AREAS (SHELL)

(b) (5)

Lease No. GS-03P-LMD00631

INITIALS: LESSOR & GOVT
Security Requirements (Level (REV 6/22/18) Page 1



VISITOR ACCESS CONTROL (SHELL)

Entrances are open to the public during business hours. (b) (5)

b) (5)

INTERIOR (GOVERNMENT SPACE)

DESIGNATED ENTRANCES (SHELL)

The Government shall have a designated main entrance.

IDENTITY VERIFICATION (SHELL)

The Government reserves the right to verify the identity of persons requesting access to the Space prior to allowing entry.

FORMAL KEY CONTROL PROGRAM (SHELL)

The Government reserves the right to implement a formal key control program. The Lessor shall have a means of allowing the electronic disabling of lost or stolen access media, if electronic media is used.

SITES AND EXTERIOR OF THE BUILDING

SIGNAGE

POSTING OF SIGNAGE IDENTIFYING THE SPACE AS GOVERNMENTAL (SHELL)

The Lessor shall not post sign(s) or otherwise identify the facility and parking areas as a Government, or specific Government tenant, occupied facility, including during construction, without written Government approval.

POSTING OF REGULATORY SIGNAGE (SHELL)

The Government may post or request the Lessor to post regulatory, statutory, sensitive areas and site specific signage.

Lease No. GS-03P-LMD00631

INITIALS: ______ LESSOR &______ GOVT
Security Requirements (Level (b) (REV 6/22/18) Page 2

LANDSCAPING

LANDSCAPING REQUIREMENTS (SHELL)

Lessor shall maintain landscaping (trees, bushes, hedges, land contour, etc.) around the facility.

(b) (5)

CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN (SHELL)

(b) (5)


HAZMAT STORAGE

If there is HAZMAT storage, Lessor shall locate it in a restricted area or storage container away from loading docks, entrances, and uncontrolled parking.

PLACEMENT OF RECEPTACLES, CONTAINERS, AND MAILBOXES

Trash receptacles, containers, mailboxes, vending machines, or other fixtures and/or features that could conceal packages, brief cases, or other portable containers shall be located 10 feet away from building.

SECURITY SYSTEMS



(b) (5)

Lease No. GS-03P-LMD00631 INITIALS: LESSOR & GOVT Security Requirements (Level 6) (REV 6/1/2/18) Page 3

(b) (5)	
(b) (5)	
(b) (5)	
(b) (5)	

INITIALS: 1/2 LESSOR & GOVT Security Requirements (Level (REV 6/22/18) Page 4

FΧ		

(b) (5)

(b) (5)

(b) (5)

STRUCTURE

WINDOWS

(b) (5)

OPERATIONS AND ADMINISTRATION

LESSOR TO WORK WITH FACILITY SECURITY COMMITTEE (FSC) (SHELL)

The Lessor shall cooperate and work with the buildings Facility Security Committee (FSC) throughout the term of the lease.

ACCESS TO BUILDING INFORMATION (SHELL)

Building Information—including mechanical, electrical, vertical transport, fire and life safety, security system plans and schematics, computer automation systems, and emergency

Lease No. GS-03P-LMD00631

INITIALS: // LESSOR & // GOVT Security Requirements (Level II) (REV 6/22/18) Page 5

operations procedures—shall be strictly controlled. Such information shall be released to authorized personnel only, approved by the Government, by the development of an access list and controlled copy numbering. The Contracting Officer may direct that the names and locations of -Government tenants not be disclosed in any publicly accessed document or record. If that is the case, the Government may request that such information not be posted in the building directory.

Lessor shall have emergency plans and associated documents readily available in the event of an emergency.

CYBERSECURITY (SHELL)

Lease No. GS-03P-LMD00631



INITIALS: 15 LESSOR & 1 GOVT
Security Requirements (Level (REV 6/22/18) Page 6

(b) (5)	
(b) (5)	
(b) (5)	
(b) (5)	

Lease No. GS-03P-LMD00631

INITIALS: 1/2 LESSOR & GOVT Security Requirements (Level (REV 6/22/18) Page 7

(b) (5)

INITIALS: LESSOR & GOVT Security Requirements (Level (REV-6/22/18) Page 8

GENERAL CLAUSES (Acquisition of Leasehold Interests in Real Property)

CATEGORY	CLAUSE NO.	48 CFR REF.	CLAUSE TITLE
GENERAL	1 2	552.270-11	SUBLETTING AND ASSIGNMENT SUCCESSORS BOUND
	3	552.270-23	SUBORDINATION, NON-DISTURBANCE AND ATTORNMENT
	4 5	552.270-24 552.270-25	STATEMENT OF LEASE SUBSTITUTION OF TENANT AGENCY
	6	552.270-26	NO WAIVER
	7 8	552,270-28	INTEGRATED AGREEMENT MUTUALITY OF OBLIGATION
	-	302.270-20	
PERFORMANCE	9 10		DELIVERY AND CONDITION DEFAULT BY LESSOR
	11	552.270-19	PROGRESSIVE OCCUPANCY
	12		MAINTENANCE OF THE PROPERTY, RIGHT TO INSPECT
	13		FIRE AND CASUALTY DAMAGE
	14 15	552.270-12	COMPLIANCE WITH APPLICABLE LAW ALTERATIONS
	16	002.270-12	ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY
PAYMENT	17 18	52.204-7 52.204-13	SYSTEM FOR AWARD MANAGEMENT SYSTEM FOR AWARD MANAGEMENT
	40	550 070 04	MAINTENANCE PROMPT PAYMENT
	19 20	552.270-31 52.232-23	ASSIGNMENT OF CLAIMS
	21	02,202	PAYMENT
	22	52.232-33	PAYMENT BY ELECTRONIC FUNDS TRANSFER— SYSTEM FOR AWARD MANAGEMENT
STANDARDS OF CONDU	CT 23	52.203-13	CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT
	24	552.270-32	COVENANT AGAINST CONTINGENT FEES
	25 26	52-203-7 52-223-6	ANTI-KICKBACK PROCEDURES DRUG-FREE WORKPLACE
	27	52.203-14	DISPLAY OF HOTLINE POSTER(S)
ADJUSTMENTS	28	552.270-30	PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY
	29	52.215-10	PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA
	30 31	552.270-13	PROPOSALS FOR ADJUSTMENT CHANGES
AUDITS	32 33	552.215-70 52.215-2	EXAMINATION OF RECORDS BY GSA AUDIT AND RECORDS—NEGOTIATION

EXHIBIT E			
DISPUTES	34	52.233-1	DISPUTES
LABOR STANDARDS	35 36 37	52.222-26 52.222-21 52.219-28	EQUAL OPPORTUNITY PROHIBITION OF SEGREGATED FACILITIES POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION
	38 39	52.222-35 52.222-36	EQUAL OPPORTUNITY FOR VETERANS EQUAL OPPORTUNITY FOR WORKERS WITH
			DISABILITIES
	40	52.222-37	EMPLOYMENT REPORTS ON VETERANS
SUBCONTRACTING	41	52.209-6	PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT
	42	52.215-12	SUBCONTRACTOR CERTIFIED COST OR PRICING DATA
	43	52.219-8	UTILIZATION OF SMALL BUSINESS CONCERNS
	44	52.219-9	SMALL BUSINESS SUBCONTRACTING PLAN
	45	52.219-16	LIQUIDATED DAMAGES—SUBCONTRACTING PLAN
	46	52.204-10	REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS
	47	552.219-73	GOALS FOR SUBCONTRACTING PLAN

The information collection requirements contained in this solicitation/contract that are not required by regulation have been approved by the Office of Management and Budget (OMB) pursuant to the Paperwork Reduction Act and assigned the OMB Control No. 3090-0163.

GENERAL CLAUSES

(Acquisition of Leasehold Interests in Real Property)

1. SUBLETTING AND ASSIGNMENT (JAN 2011)

The Government may sublet any part of the premises but shall not be relieved from any obligations under this lease by reason of any such subletting. The Government may at any time assign this lease, and be relieved from all obligations to Lessor under this lease excepting only unpaid rent and other liabilities, if any, that have accrued to the date of said assignment. Any subletting or assignment shall be subject to prior written consent of Lessor, which shall not be unreasonably withheld.

2. 552,270-11 SUCCESSORS BOUND (SEP 1999)

This lease shall bind, and inure to the benefit of, the parties and their respective heirs, executors, administrators, successors, and assigns.

3. 552,270-23 SUBORDINATION, NON-DISTURBANCE AND ATTORNMENT (SEP 1999)

- (a) Lessor warrants that it holds such title to or other interest in the premises and other property as is necessary to the Government's access to the premises and full use and enjoyment thereof in accordance with the provisions of this lease. Government agrees, in consideration of the warranties and conditions set forth in this clause, that this lease is subject and subordinate to any and all recorded mortgages, deeds of trust and other liens now or hereafter existing or imposed upon the premises, and to any renewal, modification or extension thereof. It is the intention of the parties that this provision shall be self-operative and that no further instrument shall be required to effect the present or subsequent subordination of this lease. Government agrees, however, within twenty (20) business days next following the Contracting Officer's receipt of a written demand, to execute such instruments as Lessor may reasonably request to evidence further the subordination of this lease to any existing or future mortgage, deed of trust or other security interest pertaining to the premises, and to any water, sewer or access easement necessary or desirable to serve the premises or adjoining property owned in whole or in part by Lessor if such easement does not interfere with the full enjoyment of any right granted the Government under this lease.
- (b) No such subordination, to either existing or future mortgages, deeds of trust or other lien or security instrument shall operate to affect adversely any right of the Government under this lease so long as the Government is not in default under this lease. Lessor will include in any future mortgage, deed of trust or other security instrument to which this lease becomes subordinate, or in a separate non-disturbance agreement, a provision to the foregoing effect. Lessor warrants that the holders of all notes or other obligations secured by existing mortgages, deeds of trust or other security instruments have consented to the provisions of this clause, and agrees to provide true copies of all such consents to the Contracting Officer promptly upon demand.
- (c) In the event of any sale of the premises or any portion thereof by foreclosure of the lien of any such mortgage, deed of trust or other security instrument, or the giving of a deed in lieu of foreclosure, the Government will be deemed to have attorned to any purchaser, purchasers, transferee or transferees of the premises or any portion thereof and its or their successors and assigns, and any such purchasers and transferees will be deemed to have assumed all obligations of the Lessor under this lease, so as to establish direct privity of estate and contract between Government and such purchasers or transferees, with the same force, effect and relative priority in time and right as if the lease had initially been entered into between such purchasers or transferees and the Government; provided, further, that the Contracting Officer and such purchasers or transferees shall, with reasonable promptness following any such sale or deed delivery in lieu of foreclosure, execute all such revisions to this lease, or other writings, as shall be necessary to document the foregoing relationship.
- (d) None of the foregoing provisions may be deemed or construed to imply a waiver of the Government's rights as a sovereign.

4. 552.270-24 STATEMENT OF LEASE (SEP 1999)

- (a) The Contracting Officer will, within thirty (30) days next following the Contracting Officer's receipt of a joint written request from Lessor and a prospective lender or purchaser of the building, execute and deliver to Lessor a letter stating that the same is issued subject to the conditions stated in this clause and, if such is the case, that (1) the lease is in full force and effect; (2) the date to which the rent and other charges have been paid in advance, if any; and (3) whether any notice of default has been issued.
 - (b) Letters issued pursuant to this clause are subject to the following conditions:
- (1) That they are based solely upon a reasonably diligent review of the Contracting Officer's lease file as of the date of issuance:
- (2) That the Government shall not be held liable because of any defect in or condition of the premises or building;
- (3) That the Contracting Officer does not warrant or represent that the premises or building comply with applicable Federal, State and local law; and
- (4) That the Lessor, and each prospective lender and purchaser are deemed to have constructive notice of such facts as would be ascertainable by reasonable pre-purchase and pre-commitment inspection of the Premises and Building and by inquiry to appropriate Federal, State and local Government officials.

5. 552.270-25 SUBSTITUTION OF TENANT AGENCY (SEP 1999)

The Government may, at any time and from time to time, substitute any Government agency or agencies for the Government agency or agencies, if any, named in the lease.

6. 552.270-26 NO WAIVER (SEP 1999)

No failure by either party to insist upon the strict performance of any provision of this lease or to exercise any right or remedy consequent upon a breach thereof, and no acceptance of full or partial rent or other performance by either party during the continuance of any such breach shall constitute a waiver of any such breach of such provision.

7. INTEGRATED AGREEMENT (JUN 2012)

This Lease, upon execution, contains the entire agreement of the parties and no prior written or oral agreement, express or implied, shall be admissible to contradict the provisions of the Lease. Except as expressly attached to and made a part of the Lease, neither the Request for Lease Proposals nor any pre-award communications by either party shall be incorporated in the Lease.

8. 552.270-28 MUTUALITY OF OBLIGATION (SEP 1999)

The obligations and covenants of the Lessor, and the Government's obligation to pay rent and other Government obligations and covenants, arising under or related to this Lease, are interdependent. The Government may, upon issuance of and delivery to Lessor of a final decision asserting a claim against Lessor, set off such claim, in whole or in part, as against any payment or payments then or thereafter due the Lessor under this lease. No setoff pursuant to this clause shall constitute a breach by the Government of this lease.

9. DELIVERY AND CONDITION (JAN 2011)

(a) Unless the Government elects to have the space occupied in increments, the space must be delivered ready for occupancy as a complete unit.

INITIALS: LESSOR & GOVERNMEN

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 4 (REV 06/16)

(b) The Government may elect to accept the Space notwithstanding the Lessor's failure to deliver the Space substantially complete; if the Government so elects, it may reduce the rent payments.

10. DEFAULT BY LESSOR (APR 2012)

- (a) The following conditions shall constitute default by the Lessor, and shall give rise to the following rights and remedies for the Government:
- (1) Prior to Acceptance of the Premises. Failure by the Lessor to diligently perform all obligations required for Acceptance of the Space within the times specified, without excuse, shall constitute a default by the Lessor. Subject to provision of notice of default to the Lessor, and provision of a reasonable opportunity for the Lessor to cure its default, the Government may terminate the Lease on account of the Lessor's default.
- (2) After Acceptance of the Premises. Failure by the Lessor to perform any service, to provide any item, or satisfy any requirement of this Lease, without excuse, shall constitute a default by the Lessor. Subject to provision of notice of default to the Lessor, and provision of a reasonable opportunity for the Lessor to cure its default, the Government may perform the service, provide the item, or obtain satisfaction of the requirement by its own employees or contractors. If the Government elects to take such action, the Government may deduct from rental payments its costs incurred in connection with taking the action. Alternatively, the Government may reduce the rent by an amount reasonably calculated to approximate the cost or value of the service not performed, item not provided, or requirement not satisfied, such reduction effective as of the date of the commencement of the default condition.
 - (3) Grounds for Termination. The Government may terminate the Lease if:
- (i) The Lessor's default persists notwithstanding provision of notice and reasonable opportunity to cure by the Government, or
- (ii) The Lessor fails to take such actions as are necessary to prevent the recurrence of default conditions,

and such conditions (i) or (ii) substantially impair the safe and healthful occupancy of the Premises, or render the Space unusable for its intended purposes.

- (4) Excuse. Failure by the Lessor to timely deliver the Space or perform any service, provide any item, or satisfy any requirement of this Lease shall not be excused if its failure in performance arises from:
 - (i) Circumstances within the Lessor's control;
 - (ii) Circumstances about which the Lessor had actual or constructive knowledge prior to the Lease Award Date that could reasonably be expected to affect the Lessor's capability to perform, regardless of the Government's knowledge of such matters;
 - (iii) The condition of the Property;
 - (iv) The acts or omissions of the Lessor, its employees, agents or contractors; or
 - (v) The Lessor's inability to obtain sufficient financial resources to perform its obligations.
- (5) The rights and remedies specified in this clause are in addition to any and all remedies to which the Government may be entitled as a matter of law.

INITIALS: 4 & COLERNMENT

11. 552.270-19 PROGRESSIVE OCCUPANCY (SEP 1999)

The Government shall have the right to elect to occupy the space in partial increments prior to the substantial completion of the entire leased premises, and the Lessor agrees to schedule its work so as to deliver the space incrementally as elected by the Government. The Government shall pay rent commencing with the first business day following substantial completion of the entire leased premise unless the Government has elected to occupy the leased premises incrementally. In case of incremental occupancy, the Government shall pay rent pro rata upon the first business day following substantial completion of each incremental unit. Rental payments shall become due on the first workday of the month following the month in which an increment of space is substantially complete, except that should an increment of space be substantially completed after the fifteenth day of the month, the payment due date will be the first workday of the second month following the month in which it was substantially complete. The commencement date of the firm lease term will be a composite determined from all rent commencement dates.

12. MAINTENANCE OF THE PROPERTY, RIGHT TO INSPECT (APR 2015)

The Lessor shall maintain the Property, including the building, building systems, and all equipment, fixtures, and appurtenances furnished by the Lessor under this Lease, in good repair and tenantable condition so that they are suitable in appearance and capable of supplying such heat, air conditioning, light, ventilation, safety systems, access and other things to the premises, without reasonably preventable or recurring disruption, as is required for the Government's access to, occupancy, possession, use and enjoyment of the premises as provided in this lease. For the purpose of so maintaining the premises, the Lessor may at reasonable times enter the premises with the approval of the authorized Government representative in charge. Upon request of the Lease Contracting Officer (LCO), the Lessor shall provide written documentation that building systems have been properly maintained, tested, and are operational within manufacturer's warranted operating standards. The Lessor shall maintain the Premises in a safe and healthful condition according to applicable OSHA standards and all other requirements of this Lease, including standards governing indoor air quality, existence of mold and other biological hazards, presence of hazardous materials, etc. The Government shall have the right, at any time after the Lease Award Date and during the term of the Lease, to inspect all areas of the Property to which access is necessary for the purpose of determining the Lessor's compliance with this clause.

13. FIRE AND CASUALTY DAMAGE (JUN 2016)

If the building in which the Premises are located is totally destroyed or damaged by fire or other casualty, this Lease shall immediately terminate. If the building in which the Premises are located are only partially destroyed or damaged, so as to render the Premises untenantable, or not usable for their intended purpose, the Lessor shall have the option to elect to repair and restore the Premises or terminate the Lease. The Lessor shall be permitted a reasonable amount of time, not to exceed 270 days from the event of destruction or damage, to repair or restore the Premises, provided that the Lessor submits to the Government a reasonable schedule for repair of the Premises within 60 days of the event of destruction or damage. If the Lessor fails to timely submit a reasonable schedule for completing the work, the Government may elect to terminate the Lease effective as of the date of the event of destruction or damage. If the Lessor elects to repair or restore the Premises, but fails to repair or restore the Premises within 270 days from the event of destruction or damage, or fails to diligently pursue such repairs or restoration so as to render timely completion commercially impracticable, the Government may terminate the Lease effective as of the date of the destruction or damage. During the time that the Premises are unoccupied, rent shall be abated. Termination of the Lease by either party under this clause shall not give rise to liability for either party.

Nothing in this lease shall be construed as relieving Lessor from liability for damage to, or destruction of, property of the United States of America caused by the willful or negligent act or omission of Lessor.

14. COMPLIANCE WITH APPLICABLE LAW (JAN 2011)

Lessor shall comply with all Federal, state and local laws applicable to its ownership and leasing of the Property, including, without limitation, laws applicable to the construction, ownership, alteration or operation of all buildings, structures, and facilities located thereon, and obtain all necessary permits, licenses and similar items at its own expense. The Government will comply with all Federal, State and local laws applicable to and enforceable against

it as a tenant under this lease, provided that nothing in this Lease shall be construed as a waiver of the sovereign immunity of the Government. This Lease shall be governed by Federal law.

15. 552.270-12 ALTERATIONS (SEP 1999)

The Government shall have the right during the existence of this lease to make alterations, attach fixtures, and erect structures or signs in or upon the premises hereby leased, which fixtures, additions or structures so placed in, on, upon, or attached to the said premises shall be and remain the property of the Government and may be removed or otherwise disposed of by the Government. If the lease contemplates that the Government is the sole occupant of the building, for purposes of this clause, the leased premises include the land on which the building is sited and the building itself. Otherwise, the Government shall have the right to tie into or make any physical connection with any structure located on the property as is reasonably necessary for appropriate utilization of the leased space.

16. ACCEPTANCE OF SPACE AND CERTIFICATE OF OCCUPANCY (APR 2015)

- (a) Ten (10) working days prior to the completion of the Space, the Lessor shall issue written notice to the Government to schedule the inspection of the Space for acceptance. The Government shall accept the Space only if the construction of building shell and TIs conforming to this Lease and the approved DIDs is substantially complete, and a Certificate of Occupancy has been issued as set forth below.
- (b) The Space shall be considered substantially complete only if the Space may be used for its intended purpose and completion of remaining work will not unreasonably interfere with the Government's enjoyment of the Space. Acceptance shall be final and binding upon the Government with respect to conformance of the completed TIs to the approved DIDs, with the exception of items identified on a punchlist generated as a result of the inspection, concealed conditions, latent defects, or fraud, but shall not relieve the Lessor of any other Lease requirements.
- (c) The Lessor shall provide a valid Certificate of Occupancy, issued by the local jurisdiction, for the intended use of the Government. If the local jurisdiction does not issue Certificates of Occupancy or if the Certificate of Occupancy is not available, the Lessor may satisfy this condition by providing a report prepared by a licensed fire protection engineer that indicates that the Space and Building are compliant with all applicable local codes and ordinances and all fire protection and life safety-related requirements of this Lease to ensure an acceptable level of safety is provided. Under such circumstances, the Government shall only accept the Space without a Certificate of Occupancy if a licensed fire protection engineer determines that the offered space is compliant with all applicable local codes and ordinances and fire protection and life safety-related requirements of this Lease.

17. 52.204-7 SYSTEM FOR AWARD MANAGEMENT (JUL 2013)

This clause is incorporated by reference.

18. 52.204-13 SYSTEM FOR AWARD MANAGEMENT MAINTENANCE (JUL 2013)

This clause is incorporated by reference.

19. 552.270-31 PROMPT PAYMENT (JUN 2011)

The Government will make payments under the terms and conditions specified in this clause. Payment shall be considered as being made on the day a check is dated or an electronic funds transfer is made. All days referred to in this clause are calendar days, unless otherwise specified.

(a) Payment due date-

(1) Rental payments. Rent shall be paid monthly in arrears and will be due on the first workday of each month, and only as provided for by the lease.

- (i) When the date for commencement of rent falls on the 15th day of the month or earlier, the initial monthly rental payment under this contract shall become due on the first workday of the month following the month in which the commencement of the rent is effective.
- (ii) When the date for commencement of rent falls after the 15th day of the month, the initial monthly rental payment under this contract shall become due on the first workday of the second month following the month in which the commencement of the rent is effective.
 - (2) Other payments. The due date for making payments other than rent shall be the later of the following two events:
- (i) The 30th day after the designated billing office has received a proper invoice from the Contractor.
- (ii) The 30th day after Government acceptance of the work or service. However, if the designated billing office fails to annotate the invoice with the actual date of receipt, the invoice payment due date shall be deemed to be the 30th day after the Contractor's invoice is dated, provided a proper invoice is received and there is no disagreement over quantity, quality, or Contractor compliance with contract requirements.
 - (b) Invoice and inspection requirements for payments other than rent.
- (1) The Contractor shall prepare and submit an invoice to the designated billing office after completion of the work. A proper invoice shall include the following items:
 - (i) Name and address of the Contractor.
 - (ii) Invoice date.
 - (iii) Lease number.
 - (iv) Government's order number or other authorization.
 - (v) Description, price, and quantity of work or services delivered.
- (vi) Name and address of Contractor official to whom payment is to be sent (must be the same as that in the remittance address in the lease or the order).
- (vii) Name (where practicable), title, phone number, and mailing address of person to be notified in the event of a defective invoice.
- (2) The Government will inspect and determine the acceptability of the work performed or services delivered within seven days after the receipt of a proper invoice or notification of completion of the work or services unless a different period is specified at the time the order is placed. If actual acceptance occurs later, for the purpose of determining the payment due date and calculation of interest, acceptance will be deemed to occur on the last day of the seven day inspection period. If the work or service is rejected for failure to conform to the technical requirements of the contract, the seven days will be counted beginning with receipt of a new invoice or notification. In either case, the Contractor is not entitled to any payment or interest unless actual acceptance by the Government occurs.
 - (c) Interest Penalty.
- (1) An interest penalty shall be paid automatically by the Government, without request from the Contractor, if payment is not made by the due date.
- (2) The interest penalty shall be at the rate established by the Secretary of the Treasury under Section 12 of the Contract Disputes Act of 1978 (41 U.S.C. 611) that is in effect on the day after the due date. This rate is referred to as the "Renegotiation Board Interest Rate," and it is published in the Federal Register

semiannually on or about January 1 and July 1. The interest penalty shall accrue daily on the payment amount approved by the Government and be compounded in 30-day increments inclusive from the first day after the due date through the payment date.

- (3) Interest penalties will not continue to accrue after the filing of a claim for such penalties under the clause at 52,233–1, Disputes, or for more than one year. Interest penalties of less than \$1.00 need not be paid.
- (4) Interest penalties are not required on payment delays due to disagreement between the Government and Contractor over the payment amount or other issues involving contract compliance or on amounts temporarily withheld or retained in accordance with the terms of the contract. Claims involving disputes, and any interest that may be payable, will be resolved in accordance with the clause at 52.233-1, Disputes.
- (d) Overpayments. If the Lessor becomes aware of a duplicate payment or that the Government has otherwise overpaid on a payment, the Contractor shall—
- (1) Return the overpayment amount to the payment office cited in the contract along with a description of the overpayment including the—
 - (i) Circumstances of the overpayment (e.g., duplicate payment, erroneous payment, liquidation errors, date(s) of overpayment);
 - (ii) Affected lease number; (iii) Affected lease line item or sub-line item, if applicable; and
 - (iii) Lessor point of contact.
 - (2) Provide a copy of the remittance and supporting documentation to the Contracting Officer.

20. 52.232-23 ASSIGNMENT OF CLAIMS (MAY 2014)

(Applicable to leases over the micro-purchase threshold.)

- (a) The Contractor, under the Assignment of Claims Act, as amended, 31 U.S.C. 3727, 41 U.S.C. 6305 (hereafter referred to as "the Act"), may assign its rights to be paid amounts due or to become due as a result of the performance of this contract to a bank, trust company, or other financing institution, including any Federal lending agency. The assignee under such an assignment may thereafter further assign or reassign its right under the original assignment to any type of financing institution described in the preceding sentence.
- (b) Any assignment or reassignment authorized under the Act and this clause shall cover all unpaid amounts payable under this contract, and shall not be made to more than one party, except that an assignment or reassignment may be made to one party as agent or trustee for two or more parties participating in the financing of this contract.
- (c) The Contractor shall not furnish or disclose to any assignee under this contract any classified document (including this contract) or information related to work under this contract until the Contracting Officer authorizes such action in writing.

21. PAYMENT (MAY 2011)

- (a) When space is offered and accepted, the amount of American National Standards Institute/Building Owners and Managers Association Office Area (ABOA) square footage delivered will be confirmed by:
- (1) The Government's measurement of plans submitted by the successful Offeror as approved by the Government, and an inspection of the space to verify that the delivered space is in conformance with such

INITIALS

ESSOR & GOVERNMI

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 9 (REV 06/16)

plans or

- (2) A mutual on-site measurement of the space, if the Contracting Officer determines that it is necessary.
- (b) Payment will not be made for space which is in excess of the amount of ABOA square footage stated in the lease.
- (c) If it is determined that the amount of ABOA square footage actually delivered is less than the amount agreed to in the lease, the lease will be modified to reflect the amount of ABOA space delivered and the annual rental will be adjusted as follows:

ABOA square feet not delivered multiplied by one plus the common area factor (CAF), multiplied by the rate per rentable square foot (RSF). That is: (1+CAF) x Rate per RSF = Reduction in Annual Rent

22. 52.232-33 PAYMENT BY ELECTRONIC FUNDS TRANSFER—SYSTEM FOR AWARD MANAGEMENT (JUL 2013)

This clause is incorporated by reference.

23. 52.203-13 CONTRACTOR CODE OF BUSINESS ETHICS AND CONDUCT (OCT 2015)

(Applicable to leases over \$5.5 million total contract value and performance period is 120

days or more.)

This clause is incorporated by reference.

24. 552.270-32 COVENANT AGAINST CONTINGENT FEES (JUN 2011)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

- (a) The Contractor warrants that no person or agency has been employed or retained to solicit or obtain this contract upon an agreement or understanding for a contingent fee, except a bona fide employee or agency. For breach or violation of this warranty, the Government shall have the right to annul this contract without liability or, in its discretion, to deduct from the contract price or consideration, or otherwise recover the full amount of the contingent fee.
- (b) Bona fide agency, as used in this clause, means an established commercial or selling agency (including licensed real estate agents or brokers), maintained by a Contractor for the purpose of securing business, that neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds itself out as being able to obtain any Government contract or contracts through improper influence.
- (1) Bona fide employee, as used in this clause, means a person, employed by a Contractor and subject to the Contractor's supervision and control as to time, place, and manner of performance, who neither exerts nor proposes to exert improper influence to solicit or obtain Government contracts nor holds out as being able to obtain any Government contract or contracts through improper influence.
- (2) Contingent fee, as used in this clause, means any commission, percentage, brokerage, or other fee that is contingent upon the success that a person or concern has in securing a Government contract.
- (3) Improper influence, as used in this clause, means any influence that induces or tends to induce a Government employee or officer to give consideration or to act regarding a Government contract on any basis other than the merits of the matter.

25. 52.203-7 ANTI-KICKBACK PROCEDURES (MAY 2014)

(Applicable to leases over the Simplified Lease AcquisitionThreshold.) This clause is incorporated by reference.

NITIALS: LESSOR & GOVERNMEN

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 10 (REV 06/16)

26. 52.223-6 DRUG-FREE WORKPLACE (MAY 2001)

(Applicable to leases over the Simplified Lease Acquisition Threshold, as well as to leases of any value awarded to an individual.)

This clause is incorporated by reference.

27. 52.203-14 DISPLAY OF HOTLINE POSTER(S) (OCT 2015)

(Applicable to leases over \$5.5 Million total contract value and performance period is 120 days or more.)

(a) Definition.

"United States," as used in this clause, means the 50 States, the District of Columbia, and outlying areas.

- (b) Display of fraud hotline poster(s). Except as provided in paragraph (c)—
- (1) During contract performance in the United States, the Contractor shall prominently display in common work areas within business segments performing work under this contract and at contract work sites-
 - (i) Any agency fraud hotline poster or Department of Homeland Security (DHS) fraud hotline poster identified in paragraph (b)(3) of this clause; and
 - (ii) Any DHS fraud hotline poster subsequently identified by the Contracting Officer.
- (2) Additionally, if the Contractor maintains a company website as a method of providing information to employees, the Contractor shall display an electronic version of the poster(s) at the website.
- (3) Any required posters may be obtained as follows:

Poster(s)

Obtain from

GSA Office of Inspector General "FRAUDNET HOTLINE

Contracting Officer

(Contracting Officer shall insert—

- Appropriate agency name(s) and/or title of applicable Department of Homeland Security fraud (i) hotline poster); and
- (ii) The website(s) or other contact information for obtaining the poster(s).)
- (c) If the Contractor has implemented a business ethics and conduct awareness program, including a reporting mechanism, such as a hotline poster, then the Contractor need not display any agency fraud hotline posters as required in paragraph (b) of this clause, other than any required DHS posters.
- (d) Subcontracts. The Contractor shall include the substance of this clause, including this paragraph (d), in all subcontracts that exceed \$5.5 million, except when the subcontract—
 - (1)Is for the acquisition of a commercial item; or
 - (2) Is performed entirely outside the United States.

28. 552.270-30 PRICE ADJUSTMENT FOR ILLEGAL OR IMPROPER ACTIVITY (JUN 2011)

(Applicable to leases over the Simplified Lease Acquisition Threshold.)

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 11 (REV 06/16)

- (a) If the head of the contracting activity (HCA) or his or her designee determines that there was a violation of subsection 27(a) of the Office of Federal Procurement Policy Act, as amended (41 U.S.C. 423), as implemented in the Federal Acquisition Regulation, the Government, at its election, may—
 - (1) Reduce the monthly rental under this lease by five percent of the amount of the rental for each month of the remaining term of the lease, including any option periods, and recover five percent of the rental already paid;
 - (2) Reduce payments for alterations not included in monthly rental payments by five percent of the amount of the alterations agreement; or
 - (3) Reduce the payments for violations by a Lessor's subcontractor by an amount not to exceed the amount of profit or fee reflected in the subcontract at the time the subcontract was placed.
- (b) Prior to making a determination as set forth above, the HCA or designee shall provide to the Lessor a written notice of the action being considered and the basis thereof. The Lessor shall have a period determined by the agency head or designee, but not less than 30 calendar days after receipt of such notice, to submit in person, in writing, or through a representative, information and argument in opposition to the proposed reduction. The agency head or designee may, upon good cause shown, determine to deduct less than the above amounts from payments.
- (c) The rights and remedies of the Government specified herein are not exclusive, and are in addition to any other rights and remedies provided by law or under this lease.

29. 52.215-10 PRICE REDUCTION FOR DEFECTIVE COST OR PRICING DATA (AUG 2011)

(Applicable when cost or pricing data are required for work or services over \$750,000.) This clause is incorporated by reference.

30. 552.270-13 PROPOSALS FOR ADJUSTMENT (SEP 1999)

- (a) The Contracting Officer may, from time to time during the term of this lease, require changes to be made in the work or services to be performed and in the terms or conditions of this lease. Such changes will be required under the Changes clause.
- (b) If the Contracting Officer makes a change within the general scope of the lease, the Lessor shall submit, in a timely manner, an itemized cost proposal for the work to be accomplished or services to be performed when the cost exceeds \$100,000. The proposal, including all subcontractor work, will contain at least the following detail—
 - (1) Material quantities and unit costs;
 - (2) Labor costs (identified with specific item or material to be placed or operation to be performed;
 - (3) Equipment costs;
 - (4) Worker's compensation and public liability insurance;
 - (5) Overhead:
 - (6) Profit; and
 - (7) Employment taxes under FICA and FUTA.
- (c) The following Federal Acquisition Regulation (FAR) provisions also apply to all proposals exceeding \$500,000 in cost—

- The Lessor shall provide cost or pricing data including subcontractor cost or pricing data (48 CFR 15,403-4) and
- The Lessor's representative, all Contractors, and subcontractors whose portion of the work exceeds \$500,000 must sign and return the "Certificate of Current Cost or Pricing Data" (48 CFR 15.406-2).
- Lessors shall also refer to 48 CFR Part 31, Contract Cost Principles, for information on which costs are allowable, reasonable, and allocable in Government work.

31. CHANGES (MAR 2013)

- The LCO may at any time, by written order, direct changes to the Tenant Improvements within the Space, Building Security Requirements, or the services required under the Lease.
- If any such change causes an increase or decrease in Lessor's costs or time required for performance of its obligations under this Lease, whether or not changed by the order, the Lessor shall be entitled to an amendment to the Lease providing for one or more of the following:
 - (1) An adjustment of the delivery date;
 - (2) An equitable adjustment in the rental rate;
 - (3) A lump sum equitable adjustment; or
 - (4) A change to the operating cost base, if applicable.
- The Lessor shall assert its right to an amendment under this clause within 30 days from the date of receipt of the change order and shall submit a proposal for adjustment. Failure to agree to any adjustment shall be a dispute under the Disputes clause. However, the pendency of an adjustment or existence of a dispute shall not excuse the Lessor from proceeding with the change as directed.
- Absent a written change order from the LCO, or from a Government official to whom the LCO has explicitly and in writing delegated the authority to direct changes, the Government shall not be liable to Lessor under this clause.

32, 552,215-70 **EXAMINATION OF RECORDS BY GSA (FEB 1996)**

The Contractor agrees that the Administrator of General Services or any duly authorized representative shall, until the expiration of 3 years after final payment under this contract, or of the time periods for the particular records specified in Subpart 4.7 of the Federal Acquisition Regulation (48 CFR 4.7), whichever expires earlier, have access to and the right to examine any books, documents, papers, and records of the Contractor involving transactions related to this contract or compliance with any clauses thereunder. The Contractor further agrees to include in all its subcontracts hereunder a provision to the effect that the subcontractor agrees that the Administrator of General Services or any duly authorized representatives shall, until the expiration of 3 years after final payment under the subcontract, or of the time periods for the particular records specified in Subpart 4.7 of the Federal Acquisition Regulation (48 CFR 4.7), whichever expires earlier, have access to and the right to examine any books, documents, papers, and records of such subcontractor involving transactions related to the subcontract or compliance with any clauses thereunder. The term "subcontract" as used in this clause excludes (a) purchase orders not exceeding \$100,000 and (b) subcontracts or purchase orders for public utility services at rates established for uniform applicability to the general public.

33. 52.215-2 AUDIT AND RECORDS—NEGOTIATION (OCT 2010)

(Applicable to leases over the Simplified Lease Acquisition Threshold.) This clause is incorporated by reference.

INITIALS: BLESSOR & GOV

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 13 (REV 06/16)

34. 52.233-1 DISPUTES (MAY 2014)

This clause is incorporated by reference.

35. 52.222-26 EQUAL OPPORTUNITY (APR 2015)

This clause is incorporated by reference.

36. 52.222-21 PROHIBITION OF SEGREGATED FACILITIES (APR 2015)

This clause is incorporated by reference.

37. 52.219-28 POST-AWARD SMALL BUSINESS PROGRAM REREPRESENTATION (JUL 2013)

(Applicable to leases exceeding the micro-purchase threshold.) This clause is incorporated by reference.

38, 52,222-35 EQUAL OPPORTUNITY FOR VETERANS (OCT 2015)

(Applicable to leases \$150,000 or more, total contract value.)

(a) Definitions. As used in this clause-

"Active duty wartime or campaign badge veteran," "Armed Forces service medal veteran," "disabled veteran," protected veteran," "qualified disabled veteran," and "recently separated veteran" have the meanings given at FAR 22.1301.

- (b) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-300.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified protected veterans, and requires affirmative action by the Contractor to employ and advance in employment qualified protected veterans.
- (c) Subcontracts. The Contractor shall insert the terms of this clause in subcontracts of \$150,000 or more unless exempted by rules, regulations, or orders of the Secretary of Labor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

39. 52.222-36 EQUAL OPPORTUNITY FOR WORKERS WITH DISABILITIES (JUL 2014)

(Applicable to leases over \$15,000 total contract value.)

- (a) Equal opportunity clause. The Contractor shall abide by the requirements of the equal opportunity clause at 41 CFR 60-741.5(a), as of March 24, 2014. This clause prohibits discrimination against qualified individuals on the basis of disability, and requires affirmative action by the Contractor to employ and advance in employment qualified individuals with disabilities.
- (b) Subcontracts. The Contractor shall include the terms of this clause in every subcontract or purchase order in excess of \$15,000 unless exempted by rules, regulations, or orders of the Secretary, so that such provisions will be binding upon each subcontractor or vendor. The Contractor shall act as specified by the Director, Office of Federal Contract Compliance Programs of the U.S. Department of Labor, to enforce the terms, including action for noncompliance. Such necessary changes in language may be made as shall be appropriate to identify properly the parties and their undertakings.

40. 52.222-37 EMPLOYMENT REPORTS ON VETERANS (FEB 2016)

(Applicable to leases \$150,000 or more, total contract value.) This clause is incorporated by reference.

INITIALS

SOR & GOVERNMEN

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 14 (REV 06/16)

41. 52.209-6 PROTECTING THE GOVERNMENT'S INTEREST WHEN SUBCONTRACTING WITH CONTRACTORS DEBARRED, SUSPENDED, OR PROPOSED FOR DEBARMENT (OCT 2015)

(Applicable to leases over \$35,000 total contract value.) This clause is incorporated by reference.

42. 52.215-12 SUBCONTRACTOR CERTIFIED COST OR PRICING DATA (OCT 2010)

(Applicable if over \$750,000 total contract value.) This clause is incorporated by reference.

43. 52.219-8 UTILIZATION OF SMALL BUSINESS CONCERNS (OCT 2014)

(Applicable to leases over the Simplified Lease Acquisition Threshold.) This clause is incorporated by reference.

44. 52.219-9 SMALL BUSINESS SUBCONTRACTING PLAN (OCT 2015) ALTERNATE III (OCT 2015)

(Applicable to leases over \$700,000 total contract value.)

This clause is incorporated by reference.

45. 52,219-16 LIQUIDATED DAMAGES—SUBCONTRACTING PLAN (JAN 1999)

(Applicable to leases over \$700,000 total contract value.) This clause is incorporated by reference.

46. 52.204-10 REPORTING EXECUTIVE COMPENSATION AND FIRST-TIER SUBCONTRACT AWARDS (OCT 2015)

(Applicable if over \$30,000 total contract value.) This clause is incorporated by reference.

47. 552.219-73 **GOALS FOR SUBCONTRACTING PLAN (JUN 2005), ALTERNATE I (SEP 1999)**

(Applicable if over \$700,000 total contract value.)

This clause is incorporated by reference.

LEASE NO. GS-03P-LMD00631 GSA FORM 3517B PAGE 15 (REV 06/16)

Representation Regarding Certain Telecommunications and Video Surveillance Services or Equipment (Acquisitions of Leasehold Interests in Real Property)

Complete appropriate boxes, sign the form, and return form, along with any other required disclosure information, to LCO or his/her designee. The Offeror makes the following additional Representations. NOTE: The "Offeror," as used on this form, is the owner of the property offered, not an individual or agent representing the owner.

52.204-24 Representation Regarding Certain Telecommunications and Video Surveillance Services or Equipment (AUG 2019)

- (a) Definitions. As used in this provision—
 "Covered telecommunications equipment or services", "Critical technology", and "Substantial or essential component" have the meanings provided in clause 52.204-25, Prohibition on Contracting for Certain Telecommunications and Video Surveillance Services or Equipment.
- (b) Prohibition. Section 889(a)(1)(A) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2019, from procuring or obtaining, or extending or renewing a contract to procure or obtain, any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. Contractors are not prohibited from providing—
 - (1) A service that connects to the facilities of a third-party, such as backhaul, roaming, or interconnection arrangements; or
 - (2) Telecommunications equipment that cannot route or redirect user data traffic or permit visibility into any user data or packets that such equipment transmits or otherwise handles.
- (c) Representation. The Offeror represents that—It [] will, [x] will not provide covered telecommunications equipment or services to the Government in the performance of any contract, subcontract or other contractual instrument resulting from this solicitation.
- (d) Disclosures. If the Offeror has responded affirmatively to the representation in paragraph (c) of this provision, the Offeror shall provide the following information as part of the offer—
 - (1) All covered telecommunications equipment and services offered (include brand; model number, such as original equipment manufacturer (OEM) number, manufacturer part number, or wholesaler number; and item description, as applicable);
 - (2) Explanation of the proposed use of covered telecommunications equipment and services and any factors relevant to determining if such use would be permissible under the prohibition in paragraph (b) of this provision;
 - (3) For services, the entity providing the covered telecommunications services (include entity name, unique entity identifier, and Commercial and Government Entity (CAGE) code, if known); and

LESSOR: 182 GOVERNMENT

EXHIBIT F

(4) For equipment, the entity that produced the covered telecommunications equipment (include entity name, unique entity identifier, CAGE code, and whether the entity was the OEM or a distributor, if known).

OFFEROR OR LEGALLY AUTHORIZED REPRESENTATIVE

NAME, ADDRESS (INCLUDING ZIP CODE)

CENTER DRIVE TITLE HOLDER LP 254 W 31st Street, 4th Floor NEW YORK, NY 10001-3967

(b) (6)

Date

General Clause Addendum to the Lease FAR 52.204-25 and GSAR 552.204-70

52.204-25 PROHIBITION ON CONTRACTING FOR CERTAIN
TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT
(AUG 2019)

(a) Definitions. As used in this clause—

"Covered foreign country" means The People's Republic of China.

"Covered telecommunications equipment or services" means -

- (1) Telecommunications equipment produced by Huawei Technologies Company or ZTE Corporation (or any subsidiary or affiliate of such entities);
- (2) For the purpose of public safety, security of Government facilities, physical security surveillance of critical infrastructure, and other national security purposes, video surveillance and telecommunications equipment produced by Hytera Communications Corporation, Hangzhou Hikvision Digital Technology Company, or Dahua Technology Company (or any subsidiary or affiliate of such entities);
- (3) Telecommunications or video surveillance services provided by such entities or using such equipment; or
- (4) Telecommunications or video surveillance equipment or services produced or provided by an entity that the Secretary of Defense, in consultation with the Director of National Intelligence or the Director of the Federal Bureau of Investigation, reasonably believes to be an entity owned or controlled by, or otherwise connected to, the government of a covered foreign country.

"Critical technology" means-

- (1) Defense articles or defense services included on the United States Munitions List set forth in the International Traffic in Arms Regulations under subchapter M of chapter I of title 22, Code of Federal Regulations;
- (2) Items included on the Commerce Control List set forth in Supplement No. 1 to part 774 of the Export Administration Regulations under subchapter C of chapter VII of title 15, Code of Federal Regulations, and controlled—

LESSOR: SOUTH TO THE STATE OF T

- (i) Pursuant to multilateral regimes, including for reasons relating to national security, chemical and biological weapons proliferation, nuclear nonproliferation, or missile technology; or
 - (ii) For reasons relating to regional stability or surreptitious listening;
- (3) Specially designed and prepared nuclear equipment, parts and components, materials, software, and technology covered by part 810 of title 10, Code of Federal Regulations (relating to assistance to foreign atomic energy activities);
- (4) Nuclear facilities, equipment, and material covered by part 110 of title 10, Code of Federal Regulations (relating to export and import of nuclear equipment and material);
- (5) Select agents and toxins covered by part 331 of title 7, Code of Federal Regulations, part 121 of title 9 of such Code, or part 73 of title 42 of such Code; or
- (6) Emerging and foundational technologies controlled pursuant to section 1758 of the Export Control Reform Act of 2018 (50 U.S.C. 4817).
- "Substantial or essential component" means any component necessary for the proper function or performance of a piece of equipment, system, or service.
- (b) Prohibition. Section 889(a)(1)(A) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2019, from procuring or obtaining or extending or renewing a contract to procure or obtain, any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. The Contractor is prohibited from providing to the Government any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system, unless an exception at paragraph (c) of this clause applies or the covered telecommunication equipment or services are covered by a waiver described in Federal Acquisition Regulation 4.2104.
- (c) Exceptions. This clause does not prohibit contractors from providing-
- (1) A service that connects to the facilities of a third-party, such as backhaul, roaming, or interconnection arrangements; or
- (2) Telecommunications equipment that cannot route or redirect user data traffic or permit visibility into any user data or packets that such equipment transmits or otherwise handles.

LESSOR: 15h COVERNMENT: LEASE NO. GS-03P-LND00631

- (d) Reporting requirement.
- (1) In the event the Contractor identifies covered telecommunications equipment or services used as a substantial or essential component of any system, or as critical technology as part of any system, during contract performance, or the Contractor is notified of such by a subcontractor at any tier or by any other source, the Contractor shall report the information in paragraph (d)(2) of this clause to the Contracting Officer, unless elsewhere in this contract are established procedures for reporting the information; in the case of the Department of Defense, the Contractor shall report to the website at https://dibnet.dod.mil. For indefinite delivery contracts, the Contractor shall report to the Contracting Officer for the indefinite delivery contract and the Contracting Officer(s) for any affected order or, in the case of the Department of Defense, identify both the indefinite delivery contract and any affected orders in the report provided at https://dibnet.dod.mil.
- (2) The Contractor shall report the following information pursuant to paragraph (d)(1) of this clause
- (i) Within one business day from the date of such identification or notification: the contract number; the order number(s), if applicable; supplier name; supplier unique entity identifier (if known); supplier Commercial and Government Entity (CAGE) code (if known); brand; model number (original equipment manufacturer number, manufacturer part number, or wholesaler number); item description; and any readily available information about mitigation actions undertaken or recommended.
- (ii) Within 10 business days of submitting the information in paragraph (d)(2)(i) of this clause: any further available information about mitigation actions undertaken or recommended. In addition, the Contractor shall describe the efforts it undertook to prevent use or submission of covered telecommunications equipment or services, and any additional efforts that will be incorporated to prevent future use or submission of covered telecommunications equipment or services.
- (e) Subcontracts. The Contractor shall insert the substance of this clause, including this paragraph (e), in all subcontracts and other contractual instruments, including subcontracts for the acquisition of commercial items.

(End of clause)

552.204-70 REPRESENTATION REGARDING CERTAIN TELECOMMUNICATIONS AND VIDEO SURVEILLANCE SERVICES OR EQUIPMENT (AUG 2019)

LESSOR: ///
GOVERNMENT: LEASE NO. GS-09P-1 MD00631

- (a) Definitions. As used in this clause"Covered telecommunications equipment or services", "Critical technology", and
 "Substantial or essential component" have the meanings provided in FAR 52.204-25,
 Prohibition on Contracting for Certain Telecommunications and Video Surveillance
 Services or Equipment.
- (b) Prohibition. Section 889(a)(1)(A) of the John S. McCain National Defense Authorization Act for Fiscal Year 2019 (Pub. L. 115-232) prohibits the head of an executive agency on or after August 13, 2019, from procuring or obtaining, or extending or renewing a contract to procure or obtain, any equipment, system, or service that uses covered telecommunications equipment or services as a substantial or essential component of any system, or as critical technology as part of any system. Contractors are not prohibited from providing-
 - (1) A service that connects to the facilities of a third-party, such as backhaul, roaming, or interconnection arrangements; or
 - (2) Telecommunications equipment that cannot route or redirect user data traffic or permit visibility into any user data or packets that such equipment transmits or otherwise handles.
- (c) Representation. The Offeror or Contractor represents that it [] will or [] will not [Contractor to complete and submit to the Contracting Officer] provide covered telecommunications equipment or services to the Government in the performance of any contract, subcontract, order, or other contractual instrument resulting from this contract. This representation shall be provided as part of the proposal and resubmitted on an annual basis from the date of award.
- (d) *Disclosures*. If the Offeror or Contractor has responded affirmatively to the representation in paragraph (c) of this clause, the Offeror or Contractor shall provide the following additional information to the Contracting Officer—
 - (1) All covered telecommunications equipment and services offered or provided (include brand; model number, such as original equipment manufacturer (OEM) number, manufacturer part number, or wholesaler number; and item description, as applicable);
 - (2) Explanation of the proposed use of covered telecommunications equipment and services and any factors relevant to determining if such use would be permissible under the prohibition in paragraph (b) of this provision;
 - (3) For services, the entity providing the covered telecommunications services (include entity name, unique entity identifier, and Commercial and Government Entity (CAGE) code, if known); and
 - (4) For equipment, the entity that produced the covered telecommunications equipment (include entity name, unique entity identifier, CAGE code, and whether the entity was the OEM or a distributor, if known).

(End of clause)

LESSOR:
GOVERNMENT:
LEASE NO GS-03P-LMD00631